




TYPE G-2 GUTTER




TYPE G-2, MODIFIED GUTTER




TYPE G-3 GUTTER



TYPE G-3, MODIFIED GUTTER



ADJACENT TO FLEXIBLE PAVEMENT



ADJACENT TO PCC PAVEMENT

TYPE "C" CURB
(RAMP TOLL PLAZAS ONLY)

NOTES:

- FOR TYPE C CURB TRANSITIONS, THE LEADING ENDS OF CURB IN THE DIRECTION OF TRAFFIC SHALL BEGIN FLUSH WITH ADJACENT PAVEMENT OR SHOULDER SURFACE AND TRANSITION TO FULL HEIGHT AT THE RATE OF ONE INCH VERTICAL TO ONE FOOT HORIZONTAL.
- | GUTTER TRANSITION DETAILS | STANDARD DRAWING |
|--|------------------|
| TRAFFIC BARRIER TERMINAL TYPE T1 (SPECIAL) | B-28 |
| TRAFFIC BARRIER TERMINAL TYPE T1-A (SPECIAL) | B-29 |
| TRAFFIC BARRIER TERMINAL TYPE T5 AND T10 | B-2 |
| TRAFFIC BARRIER TERMINAL TYPE T6 | B-3 |
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
- REINFORCEMENT STEEL SHALL BE ACCURATELY PLACED AND FIRMLY HELD IN THE POSITION SPECIFIED USING EPOXY COATED STEEL CHAIRS. CHAIR SPACING SHALL NOT EXCEED, 4'-0".
- GUTTER REINFORCEMENT SHALL BE PLACED 3" ABOVE BOTTOM OF GUTTER FOLLOWING THE SUBGRADE SLOPE.
- OTHER GUTTER AND CURB TRANSITION DETAILS WILL BE SHOWN ON THE PLANS.
- THE DEVELOPMENT LENGTH FOR SPLICING REINFORCEMENT BARS SHALL BE IN ACCORDANCE WITH THE LATEST IDOT-BRIDGE MANUAL.


APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009




DATE	REVISIONS
6-1-2009	REVISED NOTES
3-1-2010	ADDED G-2 MODIFIED GUTTER AND GUTTER TRANSITION TERMINATION
1-1-2011	ADDED TYPE "C" CURB ADJACENT TO FLEXIBLE PAVEMENT, ADDED GUTTER EXPANSION/CRACK CONTROL JOINT, REVISED NOTES.

GUTTER AND CURB DETAILS





STANDARD B1-03




GUTTER TRANSITION TERMINATION



GUTTER PLAN



SECTION C-C




EXPANSION-CRACK CONTROL JOINTS TYPE G-3/G-2 GUTTER


NOTES:

- GUTTER CRACK CONTROL JOINTS TO ALIGN IN PROLONGATION WITH PCC SHOULDER JOINTS WHERE EXISTING.
- SEE SHEET 1 OF THIS SERIES FOR NOTES.





GUTTER TRANSITION AT ENTRANCE RAMP TERMINALS



GUTTER TRANSITION AT EXIT RAMP TERMINALS

GUTTER TRANSITION NOTES:

1. PROVIDE 1" EXPANSION JOINT WITH PREFORMED JOINT FILLER BETWEEN TRANSITION SECTION AND WINGWALL.
2. SEE STANDARD B3 FOR GUTTER TRANSITIONS AT BRIDGE APPROACH.
3. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).





APPROVED..... DATE 6-1-2009...
Paul Kovacs
 CHIEF ENGINEER

DATE	REVISIONS
6-1-2009	REVISED NOTES, MODIFIED G2/G3 GUTTER TRANSITIONS
9-1-2009	ADDED GUTTER TRANSITION TERMINAL DETAIL REVISED NOTES
3-1-2010	RELOCATED GUTTER TRANSITION DETAIL TO STANDARD B28, REVISED NOTES
	REVISED TYPE G-3, G-2 GUTTER AT BRIDGE APPROACH





TYPE G-2 AND G-3
 GUTTER TRANSITIONS

STANDARD B2-02




TYPE G-3 GUTTER TRANSITION AT BRIDGE DEPARTURE



TYPE G-2 GUTTER AT BRIDGE DEPARTURE



NOTE:
SEE SHEET 1 OF THIS SERIES FOR NOTES.

APPROVED.....

 CHIEF ENGINEER DATE 6-1-2009...


Illinois Tollway
Open Roads for a Faster Future

TYPE G-2 AND G-3
 GUTTER TRANSITIONS


STANDARD B2-02




G-3 SECTION A-A
AT CONCRETE PARAPET
(SEE NOTE 8)



G-3 SECTION B-B
9'-3" FROM PARAPET



G-3 SECTION C-C
15'-10 1/4" FROM PARAPET



G-3 SECTION D-D
37'-0" FROM PARAPET

GUTTER TRANSITION NOTES:

1. SLOPE TO MATCH ADJACENT SHOULDER SLOPE (TYPICALLY 4%).
2. THE TYPE G-3 GUTTER TRANSITION SHALL BE PAID FOR PER FOOT FOR CONCRETE GUTTER TYPE G-3.
3. PROVIDE 1" EXPANSION JOINT WITH PREFORMED JOINT FILLER BETWEEN TRANSITION SECTION AND WINGWALL OR BARRIER WALL.
4. INSTALLATION ON CURVED WINGWALLS SIMILAR.
5. FOR DETAILS OF ANCHOR INSTALLATION TYPE T6 SEE TOLLWAY STANDARD C9 (TRAFFIC BARRIER TERMINAL, TYPE T6).
6. GUTTER TRANSITIONS SHALL BE CONSTRUCTED TO FIT THE STANDARD LOCATION OF THE ANCHOR INSTALLATION TYPE T6.
7. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
8. GUTTER SECTION SHOWN AT BARRIER WALL TO MATCH VERTICAL PROFILE OF TYPE F SAFETY SHAPE. MODIFY GUTTER FACE TO MATCH OTHER PARAPET PROFILES.
9. GUTTER REINFORCEMENT STEEL #4 EXPOXY COATED REBAR.

LEGEND

(A) AGGREGATE SHOULDERS SPECIAL, TYPE C

APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009

TYPE G-3 GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T6


DATE	REVISIONS
6-1-2009	MODIFIED BARRIER TERMINAL DETAILS
3-1-2010	REVISED NOTES REVISED G-2/G-3 GUTTER TRANSITION DETAILS, REVISED NOTES
1-1-2011	REVISED NOTE 8




TYPE G-2/G-3 GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T6

STANDARD B3-02

* GUARDRAIL BLOCKOUTS AND RAIL ARE OMITTED FOR CLARITY




ELEVATION




**G-2 SECTION A-A
AT CONCRETE PARAPET**


(SEE NOTE 8)



**G-2 SECTION B-B
8'-9 1/4" FROM PARAPET**



**G-2 SECTION C-C
15'-0 1/4" FROM PARAPET**



**G-2 SECTION D-D
27'-6 1/4" FROM PARAPET**

NOTES:

1. SEE SHEET 1 OF THIS SERIES FOR GENERAL NOTES.
2. THE TYPE G-2 GUTTER TRANSITION SHALL BE PAID PER FOOT FOR CONCRETE GUTTER TYPE G-2.

LEGEND

- (A) AGGREGATE SHOULDERS SPECIAL, TYPE C

TYPE G-2 GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T6


Paul Kovacs

APPROVED... CHIEF ENGINEER... DATE 6-1-2009...




TYPE G-2/G-3 GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T6


STANDARD B3-02




SODDED DITCH



**EMBANKMENT UNDER 20 FEET IN HEIGHT
TOE OF EMBANKMENT DITCHES**



SIDE DITCH DIKE



**EMBANKMENT
OVER 20 FEET IN HEIGHT**

NOTES FOR EMBANKMENT DITCHES:

1. WIDTH AND SLOPE MAY VARY DEPENDING ON SOIL CONDITION OR R.O.W. REQUIREMENTS.
2. THESE SECTIONS APPLY TO A DESIRABLE SECTION FOR NEW CONSTRUCTION. HOWEVER, THE WIDTH AND SLOPES MAY VARY DEPENDING ON SOIL CONDITIONS OR R.O.W. CONSTRAINTS.
3. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).


APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009

DATE	REVISIONS
6-1-2009	REVISED NOTES




DITCHES AND DITCH DIKE


STANDARD B4-01



HALF PLAN




SECTION A-A
ADJACENT TO CURB & GUTTER



NOTE:
0.62 C.Y. CONCRETE / L.F.

SECTION B-B



SECTION C-C
ADJACENT TO CURB

CONCRETE FLUME

NOTES:


1. CONCRETE FLUMES SHALL BE CONSTRUCTED FLUSH WITH THE ADJACENT EXISTING OR PROPOSED SURFACES.
2. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
3. THE LOCATION OF THE ANCHOR WALL MAY BE ADJUSTED AS DIRECTED BY THE ENGINEER.
4. #4 CONTINUOUS BARS OR #4 TIE BARS 2'-6" LONG AT 12" O/C SHALL BE PROVIDED AT ALL CONSTRUCTION JOINTS.
5. EXPANDED METAL FABRIC OF EQUIVALENT STRENGTH MAY BE USED IN LIEU OF WELDED WIRE FABRIC SUBJECT TO ENGINEER'S APPROVAL.
6. THE MATERIALS AND CONSTRUCTION OF THE CONCRETE FLUME SHALL CONFORM TO THE APPLICABLE PORTIONS OF SECTION 606 OF THE STANDARD SPECIFICATIONS.




APPROVED *Jeff Daley* CHIEF ENGINEER DATE 1-1-2007

DATE	REVISIONS


CONCRETE FLUME
STANDARD B5-00



PLAN
SINGLE PIPE DESIGN




PLAN VIEW OF STRUCTURE LOCATIONS




NOTES:
ADDITIONAL 'A' BARS SHALL BE FURNISHED AND PLACED BY THE CONTRACTOR. THE ADDITIONAL BARS ARE NOT INCLUDED IN THE LISTED QUANTITIES BUT WILL BE PAID FOR AS REINFORCING STEEL.
1 ADDITIONAL BAR REQUIRED FOR EACH 15° SKEW OR FRACTION THEREOF.


PIPE DIA'S 18", 24", & 30" 1 SPA.
PIPE DIA'S 36", 42", & 48" 2 EQ. SPA.




FRONT ELEVATION



PLAN
CAST-IN-PLACE HEADWALL



PLAN
PRECAST HEADWALL
TWIN PIPE DESIGN




NOTE:


'v' BARS ARE TO BEGIN AT THE PIPE END OF THE SLOPED EXTERIOR HEADWALLS. 'm' BARS ARE TO BEGIN AT THE PIPE END OF THE SLOPED INTERIOR HEADWALLS.

** CUT BARS IN FIELD TO FIT MIN. 2" CLEARANCE

SECTION A-A




ISOMETRIC VIEW



INSTALLATION DETAIL

NOTES:

1. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
2. BAR BENDING DETAILS ARE DIMENSIONED OUT TO OUT OF BARS.
3. ALL EXPOSED EDGES SHALL HAVE A 3/4" - 45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW THE FINISHED GROUND LINE.
4. CARE SHALL BE EXERCISED IN REMOVING ANY LENGTH OF EXISTING PIPE SO THE REMAINING PIPE IS UNDAMAGED AND FULLY FUNCTIONING.
5. FOR DIMENSIONS AND QUANTITIES FOR SINGLE PIPE DESIGN SEE SHEET 2 (OF 5) IN THIS SERIES.
6. FOR DIMENSIONS AND QUANTITIES FOR TWIN PIPE DESIGN SEE SHEET 3 (OF 5) IN THIS SERIES.
7. FOR STEEL GRATING DETAILS SEE SHEET 5 (OF 5) IN THIS SERIES.
8. THE STATION, OFFSET AND INVERT ELEVATION FOR THE HEADWALL SHALL APPLY AT THE END OF THE CONNECTING PIPE OPENING.



PRECAST DETAIL
CUT-OFF WALL

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009

DATE	REVISIONS
6-1-2009	MISC. DIMENSION CHANGE
1-1-2011	REVISED NOTES
	REVISED NOTES



HEADWALL TYPE III
18"-24"-30"-36"-42"-48"
FOR 1:4, 1:6, AND 1:10 SLOPES

STANDARD B6-02

DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III 1:4 SLOPE


PIPE DIA	DIMENSIONS												NO. OF SPACES			CONCRETE CLASS SI CU. YD.	REINF. STEEL LBS.
	H	L	M	P	S	T	U	V	W	A	E	B	C	D			
18"	2'-0"	7'-4"	2'-3"	2"	7'-6 ³ / ₄ "	2"	2'-8"	3'-0"	4'-4"	2'-2"	1'-8"	--	1	--	1.7	132	
24"	2'-8"	10'-0"	3'-0"	3"	10'-3 ³ / ₄ "	2"	2'-8"	4'-0"	5'-4"	2'-2"	2'-2"	--	2	--	2.8	201	
30"	3'-2"	12'-0"	3'-6"	4"	12'-4 ¹ / ₂ "	2"	2'-8"	5'-0"	6'-4"	2'-8"	2'-8"	2	--	--	4.0	275	
36"	3'-8"	14'-0"	4'-3"	4"	14'-5 ¹ / ₄ "	2"	2'-8"	6'-0"	7'-4"	2'-2"	1'-8"	--	4	--	5.3	351	
42"	4'-3"	16'-4"	4'-8"	6"	16'-10"	2"	3'-2"	6'-6"	7'-10"	2'-8"	1'-8"	4	--	--	6.8	436	
48"	4'-9"	18'-4"	5'-0"	6"	18'-10 ³ / ₄ "	2"	3'-2"	7'-0"	8'-4"	2'-2"	1'-8"	--	6	--	8.2	513	

DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III 1:6 SLOPE


PIPE DIA	DIMENSIONS												NO. OF SPACES			CONCRETE CLASS SI CU. YD.	REINF. STEEL LBS.
	H	L	M	P	S	T	U	V	W	A	E	B	C	D			
18"	2'-0"	11'-0"	2'-3"	2"	11'-1 ³ / ₄ "	2"	2'-8"	3'-0"	4'-4"	2'-2"	1'-8"	--	1	2	2.2	183	
24"	2'-8"	15'-0"	3'-0"	3"	15'-2 ¹ / ₂ "	2"	2'-8"	4'-0"	5'-4"	2'-8"	2'-8"	3	--	--	3.8	278	
30"	3'-2"	18'-0"	3'-6"	4"	18'-3"	2"	2'-8"	5'-0"	6'-4"	2'-2"	1'-8"	--	5	1	5.3	385	
36"	3'-8"	21'-0"	4'-3"	4"	21'-3 ¹ / ₂ "	2"	2'-8"	6'-0"	7'-4"	2'-8"	2'-2"	3	3	--	7.3	492	
42"	4'-3"	24'-6"	4'-8"	6"	24'-10"	2"	3'-2"	6'-6"	7'-10"	2'-8"	1'-8"	5	--	3	9.4	616	
48"	4'-9"	27'-6"	5'-0"	6"	27'-10 ¹ / ₂ "	2"	3'-2"	7'-0"	8'-4"	2'-8"	2'-2"	7	1	--	11.3	727	

DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III 1:10 SLOPE


PIPE DIA	DIMENSIONS												NO. OF SPACES			CONCRETE CLASS SI CU. YD.	REINF. STEEL LBS.
	H	L	M	P	S	T	U	V	W	A	E	B	C	D			
18"	2'-0"	18'-4"	2'-3"	2"	18'-5"	2"	2'-8"	3'-0"	4'-4"	2'-2"	1'-8"	--	5	1	3.4	279	
24"	2'-8"	25'-0"	3'-0"	3"	25'-1 ¹ / ₂ "	2"	2'-8"	4'-0"	5'-4"	2'-2"	1'-8"	--	8	1	5.8	434	
30"	3'-2"	30'-0"	3'-6"	4"	30'-1 ³ / ₄ "	2"	2'-8"	5'-0"	6'-4"	2'-2"	1'-8"	--	11	--	8.2	610	
36"	3'-8"	35'-0"	4'-3"	4"	35'-2"	2"	2'-8"	6'-0"	7'-4"	2'-2"	2'-2"	--	13	--	11.2	778	
42"	4'-3"	40'-10"	4'-8"	6"	41'-0 ¹ / ₂ "	2"	3'-2"	6'-6"	7'-10"	2'-2"	1'-8"	--	12	5	14.3	984	
48"	4'-9"	45'-10"	5'-0"	6"	46'-0 ³ / ₄ "	2"	3'-2"	7'-0"	8'-4"	2'-2"	1'-8"	--	15	4	17.4	1165	




TYPE 1



TYPE 2



TYPE 3



TYPE 4

SINGLE PIPE DESIGN

REINFORCING BAR SCHEDULE FOR ONE HEADWALL TYPE III 1:4 SLOPE

PIPE DIA	NO. 4 REINFORCING BARS					
	MARK	TYPE	NO. REQ'D.	LENGTH	a	b
18"	a18	1	1	8'-7"	2'-5"	
	d18	2	20	2'-6"	1'-9"	9"
	h18	STR.	6	7'-0"		
	n18	2	5	3'-0"	2'-0"	1'-0"
	t18	STR.	10	4'-0"		
	u18	STR.	4	1'-9"		
	w18	STR.	5	7'-0"		
24"	a24	1	1	10'-5"	3'-0"	
	d24	2	26	2'-3"	1'-6"	9"
	h24	STR.	6	9'-8"		
	n24	2	6	3'-0"	2'-0"	1'-0"
	t24	STR.	13	5'-0"		
	u24	STR.	4	2'-6"		
	v24	3	6	3'-9"	1'-3"	2'-6"
	w24	STR.	6	9'-8"		
30"	a30	1	1	11'-9"	3'-5"	
	d30	2	30	2'-3"	1'-6"	9"
	h30	STR.	8	11'-8"		
	n30	2	7	3'-0"	2'-0"	1'-0"
	t30	STR.	15	6'-0"		
	u30	STR.	4	3'-0"		
	v30	3	8	4'-3"	1'-3"	3'-0"
	w30	STR.	7	11'-8"		
36"	a36	1	1	13'-7"	4'-0"	
	d36	2	36	2'-3"	1'-6"	9"
	h36	STR.	8	13'-8"		
	n36	2	8	3'-0"	2'-0"	1'-0"
	t36	STR.	17	7'-0"		
	u36	STR.	6	3'-6"		
	v36	3	10	4'-9"	1'-3"	3'-6"
	w36	STR.	8	13'-8"		
42"	a42	1	1	15'-5"	4'-7"	
	d42	2	40	2'-3"	1'-6"	9"
	h42	STR.	10	16'-0"		
	n42	2	8	3'-6"	2'-6"	1'-0"
	t42	STR.	19	7'-6"		
	u42	STR.	6	4'-1"		
	v42	3	12	5'-4"	1'-3"	4'-1"
	w42	STR.	8	16'-0"		
48"	a48	1	1	17'-3"	5'-2"	
	d48	2	44	2'-3"	1'-6"	9"
	h48	STR.	10	18'-0"		
	n48	2	9	3'-6"	2'-6"	1'-0"
	t48	STR.	21	8'-0"		
	u48	STR.	6	4'-7"		
	v48	3	14	5'-10"	1'-3"	4'-7"
	w48	STR.	9	18'-0"		

REINFORCING BAR SCHEDULE FOR ONE HEADWALL TYPE III 1:6 SLOPE

PIPE DIA	NO. 4 REINFORCING BARS					
	MARK	TYPE	NO. REQ'D.	LENGTH	a	b
18"	a18	1	1	8'-7"	2'-5"	
	d18	2	28	2'-6"	1'-9"	9"
	h18	STR.	6	10'-8"		
	n18	2	5	3'-0"	2'-0"	1'-0"
	t18	STR.	14	4'-0"		
	u18	STR.	4	1'-9"		
	w18	STR.	5	10'-8"		
24"	a24	1	1	10'-5"	3'-0"	
	d24	2	36	2'-3"	1'-6"	9"
	h24	STR.	6	14'-8"		
	n24	2	6	3'-0"	2'-0"	1'-0"
	t24	STR.	18	5'-0"		
	u24	STR.	4	2'-6"		
	v24	3	8	3'-9"	1'-3"	2'-6"
	w24	STR.	6	14'-8"		
30"	a30	1	1	11'-9"	3'-5"	
	d30	2	42	2'-3"	1'-6"	9"
	h30	STR.	8	17'-8"		
	n30	2	7	3'-0"	2'-0"	1'-0"
	t30	STR.	21	6'-0"		
	u30	STR.	4	3'-0"		
	v30	3	11	4'-3"	1'-3"	3'-0"
	w30	STR.	7	17'-8"		
36"	a36	1	1	13'-7"	4'-0"	
	d36	2	50	2'-3"	1'-6"	9"
	h36	STR.	8	20'-8"		
	n36	2	8	3'-0"	2'-0"	1'-0"
	t36	STR.	24	7'-0"		
	u36	STR.	6	3'-6"		
	v36	3	14	4'-9"	1'-3"	3'-6"
	w36	STR.	8	20'-8"		
42"	a42	1	1	15'-5"	4'-7"	
	d42	2	56	2'-3"	1'-6"	9"
	h42	STR.	10	24'-2"		
	n42	2	8	3'-6"	2'-6"	1'-0"
	t42	STR.	27	7'-6"		
	u42	STR.	6	4'-1"		
	v42	3	17	5'-4"	1'-3"	4'-1"
	w42	STR.	8	24'-2"		
48"	a48	1	1	17'-3"	5'-2"	
	d48	2	62	2'-3"	1'-6"	9"
	h48	STR.	10	27'-2"		
	n48	2	9	3'-6"	2'-6"	1'-0"
	t48	STR.	30	8'-0"		
	u48	STR.	6	4'-7"		
	v48	3	20	5'-10"	1'-3"	4'-7"
	w48	STR.	9	27'-2"		

REINFORCING BAR SCHEDULE FOR ONE HEADWALL TYPE III 1:10 SLOPE

PIPE DIA	NO. 4 REINFORCING BARS					
	MARK	TYPE	NO. REQ'D.	LENGTH	a	b
18"	a18	1	1	8'-7"	2'-5"	
	d18	2	42	2'-6"	1'-9"	9"
	h18	STR.	6	18'-0"		
	n18	2	5	3'-0"	2'-0"	1'-0"
	t18	STR.	21	4'-0"		
	u18	STR.	4	1'-9"		
	w18	STR.	5	18'-0"		
24"	a24	1	1	10'-5"	3'-0"	
	d24	2	56	2'-3"	1'-6"	9"
	h24	STR.	6	24'-8"		
	n24	2	6	3'-0"	2'-0"	1'-0"
	t24	STR.	28	5'-0"		
	u24	STR.	4	2'-6"		
	v24	3	13	3'-9"	1'-3"	2'-6"
	w24	STR.	6	24'-8"		
30"	a30	1	1	11'-9"	3'-5"	
	d30	2	66	2'-3"	1'-6"	9"
	h30	STR.	8	29'-8"		
	n30	2	7	3'-0"	2'-0"	1'-0"
	t30	STR.	33	6'-0"		
	u30	STR.	4	3'-0"		
	v30	3	18	4'-3"	1'-3"	3'-0"
	w30	STR.	7	29'-8"		
36"	a36	1	1	13'-7"	4'-0"	
	d36	2	78	2'-3"	1'-6"	9"
	h36	STR.	8	34'-8"		
	n36	2	8	3'-0"	2'-0"	1'-0"
	t36	STR.	38	7'-0"		
	u36	STR.	6	3'-6"		
	v36	3	23	4'-9"	1'-3"	3'-6"
	w36	STR.	8	34'-8"		
42"	a42	1	1	15'-5"	4'-7"	
	d42	2	90	2'-3"	1'-6"	9"
	h42	STR.	10	40'-6"		
	n42	2	8	3'-6"	2'-6"	1'-0"
	t42	STR.	44	7'-6"		
	u42	STR.	6	4'-1"		
	v42	3	27	5'-4"	1'-3"	4'-1"
	w42	STR.	8	40'-6"		
48"	a48	1	1	17'-3"	5'-2"	
	d48	2	100	2'-3"	1'-6"	9"
	h48	STR.	10	45'-6"		
	n48	2	9	3'-6"	2'-6"	1'-0"
	t48	STR.	49	8'-0"		
	u48	STR.	6	4'-7"		
	v48	3	32	5'-10"	1'-3"	4'-7"
	w48	STR.	9	45'-6"		

NOTES:

- THE 'v' BARS, TYPE 3, SHALL BE ORDERED FULL LENGTH AND CUT IN THE FIELD. THE REMAINING PORTION OF THE 'v' BARS SHALL BE USED IN THE OTHER WALL.
- THE LONG LEG OF THE 'd' AND 'n' BARS SHALL BE VERTICAL.
- QUANTITIES ON THIS DRAWING ARE BASED ON THE CAST-IN-PLACE DESIGN.
- "STR." = STRAIGHT BAR.
- ALL REINFORCING BARS ARE #4 BARS.
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).



HEADWALL TYPE III
18"-24"-30"-42"-48"
FOR 1:4, 1:6, AND 1:10 SLOPES

STANDARD B6-02

APPROVED: *Paul Kovacs*
CHIEF ENGINEER DATE 6-1-2009

**DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III 1:4 SLOPE
TWIN PIPE CULVERT**


PIPE DIA	DIMENSIONS											NO. OF SPACES			CONCRETE CLASS SI CU. YD.	REINF. STEEL LBS.
	H	L	M	P	S	T	U	V	W	A	E	B	C	D		
18"	2'-0"	7'-4"	2'-3"	2"	7'-6 ³ / ₄ "	2"	2'-8"	3'-0"	8'-0"	2'-2"	1'-8"	--	1	--	2.9	228
24"	2'-8"	10'-0"	3'-0"	3"	10'-3 ³ / ₄ "	2"	2'-8"	4'-0"	10'-0"	2'-2"	2'-2"	--	2	--	4.6	347
30"	3'-2"	12'-0"	3'-6"	4"	12'-4 ¹ / ₂ "	2"	2'-8"	5'-0"	12'-0"	2'-8"	2'-8"	2	--	--	7.1	475
36"	3'-8"	14'-0"	4'-3"	4"	14'-5 ¹ / ₄ "	2"	2'-8"	6'-0"	14'-0"	2'-2"	1'-8"	--	4	--	9.7	611
42"	4'-3"	16'-4"	4'-8"	6"	16'-10"	2"	3'-2"	6'-6"	15'-0"	2'-8"	1'-8"	4	--	--	12.5	766
48"	4'-9"	18'-4"	5'-0"	6"	18'-10 ³ / ₄ "	2"	3'-2"	7'-0"	16'-0"	2'-2"	1'-8"	--	6	--	15.1	890

**DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III 1:6 SLOPE
TWIN PIPE CULVERT**


PIPE DIA	DIMENSIONS											NO. OF SPACES			CONCRETE CLASS SI CU. YD.	REINF. STEEL LBS.
	H	L	M	P	S	T	U	V	W	A	E	B	C	D		
18"	2'-0"	11'-0"	2'-3"	2"	11'-1 ¹ / ₄ "	2"	2'-8"	3'-0"	8'-0"	2'-2"	1'-8"	--	1	2	5.1	312
24"	2'-8"	15'-0"	3'-0"	3"	15'-2 ¹ / ₂ "	2"	2'-8"	4'-0"	10'-0"	2'-8"	2'-8"	3	--	--	6.7	476
30"	3'-2"	18'-0"	3'-6"	4"	18'-3"	2"	2'-8"	5'-0"	12'-0"	2'-2"	1'-8"	--	5	1	9.6	662
36"	3'-8"	21'-0"	4'-3"	4"	21'-3 ¹ / ₂ "	2"	2'-8"	6'-0"	14'-0"	2'-8"	2'-2"	3	3	--	13.2	852
42"	4'-3"	24'-6"	4'-8"	6"	24'-10"	2"	3'-2"	6'-6"	15'-0"	2'-8"	1'-8"	5	--	3	16.9	1079
48"	4'-9"	27'-6"	5'-0"	6"	27'-10 ¹ / ₂ "	2"	3'-2"	7'-0"	16'-0"	2'-8"	2'-2"	7	1	--	20.4	1255

**DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III 1:10 SLOPE
TWIN PIPE CULVERT**


PIPE DIA	DIMENSIONS											NO. OF SPACES			CONCRETE CLASS SI CU. YD.	REINF. STEEL LBS.
	H	L	M	P	S	T	U	V	W	A	E	B	C	D		
18"	2'-0"	18'-4"	2'-3"	2"	18'-5"	2"	2'-8"	3'-0"	8'-0"	2'-2"	1'-8"	--	5	1	6.0	472
24"	2'-8"	25'-0"	3'-0"	3"	25'-1 ¹ / ₂ "	2"	2'-8"	4'-0"	10'-0"	2'-2"	1'-8"	--	8	1	10.2	739
30"	3'-2"	30'-0"	3'-6"	4"	30'-1 ³ / ₄ "	2"	2'-8"	5'-0"	12'-0"	2'-2"	1'-8"	--	11	--	14.7	1039
36"	3'-8"	35'-0"	4'-3"	4"	35'-2"	2"	2'-8"	6'-0"	14'-0"	2'-2"	2'-2"	--	13	--	20.0	1340
42"	4'-3"	40'-10"	4'-8"	6"	41'-0 ¹ / ₂ "	2"	3'-2"	6'-6"	15'-0"	2'-2"	1'-8"	--	12	5	25.7	1714
48"	4'-9"	45'-10"	5'-0"	6"	46'-0 ³ / ₄ "	2"	3'-2"	7'-0"	16'-0"	2'-2"	1'-8"	--	15	4	31.1	2002




TYPE 1



TYPE 2



TYPE 3



TYPE 4

TWIN PIPE DESIGN

**REINFORCING BAR SCHEDULE
FOR ONE HEADWALL
TYPE III 1:4 SLOPE TWIN PIPE CULVERT**

PIPE DIA	NO. 4 REINFORCING BARS					
	MARK	TYPE	NO. REQ'D.	LENGTH	a	b
18"	a18	1	2	8'-7"	2'-5"	
	d18	2	32	2'-6"	1'-9"	9"
	h18	STR.	9	7'-0"		
	n18	2	9	3'-0"	2'-0"	1'-0"
	t18	STR.	10	7'-8"		
	u18	STR.	8	1'-9"		
	w18	STR.	9	7'-0"		
24"	a24	1	2	10'-5"	3'-0"	
	d24	2	41	2'-3"	1'-6"	9"
	h24	STR.	9	9'-8"		
	n24	2	11	3'-0"	2'-0"	1'-0"
	t24	STR.	13	9'-8"		
	u24	STR.	8	2'-6"		
	v24	3	6	3'-9"	1'-3"	2'-6"
m24	4	3	3'-9"	1'-3"	2'-0"	
w24	STR.	11	9'-8"			
30"	a30	1	2	11'-9"	3'-5"	
	d30	2	47	2'-3"	1'-6"	9"
	h30	STR.	12	11'-8"		
	n30	2	13	3'-0"	2'-0"	1'-0"
	t30	STR.	15	11'-8"		
	u30	STR.	8	3'-0"		
	v30	3	8	4'-3"	1'-3"	3'-0"
m30	4	4	4'-3"	1'-3"	2'-3"	
w30	STR.	13	11'-8"			
36"	a36	1	2	13'-7"	4'-0"	
	d36	2	57	2'-3"	1'-6"	9"
	h36	STR.	12	13'-8"		
	n36	2	15	3'-0"	2'-0"	1'-0"
	t36	STR.	17	13'-8"		
	u36	STR.	12	3'-6"		
	v36	3	10	4'-9"	1'-3"	3'-6"
m36	4	5	4'-9"	1'-3"	2'-6"	
w36	STR.	15	13'-8"			
42"	a42	1	2	15'-5"	4'-7"	
	d42	2	63	2'-3"	1'-6"	9"
	h42	STR.	15	16'-0"		
	n42	2	16	3'-6"	2'-6"	1'-0"
	t42	STR.	19	14'-8"		
	u42	STR.	12	4'-1"		
	v42	3	12	5'-4"	1'-3"	4'-1"
m42	4	6	5'-4"	1'-3"	2'-10"	
w42	STR.	16	16'-0"			
48"	a48	1	2	17'-3"	5'-2"	
	d48	2	69	2'-3"	1'-6"	9"
	h48	STR.	15	18'-0"		
	n48	2	17	3'-6"	2'-6"	1'-0"
	t48	STR.	21	15'-8"		
	u48	STR.	12	4'-7"		
	v48	3	14	5'-10"	1'-3"	4'-7"
m48	4	7	5'-10"	1'-3"	3'-1"	
w48	STR.	17	18'-0"			

**REINFORCING BAR SCHEDULE
FOR ONE HEADWALL
TYPE III 1:6 SLOPE TWIN PIPE CULVERT**

PIPE DIA	NO. 4 REINFORCING BARS					
	MARK	TYPE	NO. REQ'D.	LENGTH	a	b
18"	a18	1	2	8'-7"	2'-5"	
	d18	2	44	2'-6"	1'-9"	9"
	h18	STR.	9	10'-8"		
	n18	2	9	3'-0"	2'-0"	1'-0"
	t18	STR.	14	7'-8"		
	u18	STR.	8	1'-9"		
	w18	STR.	9	10'-8"		
24"	a24	1	2	10'-5"	3'-0"	
	d24	2	56	2'-3"	1'-6"	9"
	h24	STR.	9	14'-8"		
	n24	2	11	3'-0"	2'-0"	1'-0"
	t24	STR.	18	9'-8"		
	u24	STR.	8	2'-6"		
	v24	3	8	3'-9"	1'-3"	2'-6"
m24	4	4	3'-9"	1'-3"	2'-0"	
w24	STR.	11	14'-8"			
30"	a30	1	2	11'-9"	3'-5"	
	d30	2	65	2'-3"	1'-6"	9"
	h30	STR.	12	17'-8"		
	n30	2	13	3'-0"	2'-0"	1'-0"
	t30	STR.	21	11'-8"		
	u30	STR.	8	3'-0"		
	v30	3	11	4'-3"	1'-3"	3'-0"
m30	4	6	4'-3"	1'-3"	2'-2"	
w30	STR.	13	17'-8"			
36"	a36	1	2	13'-7"	4'-0"	
	d36	2	78	2'-3"	1'-6"	9"
	h36	STR.	12	20'-8"		
	n36	2	15	3'-0"	2'-0"	1'-0"
	t36	STR.	24	13'-8"		
	u36	STR.	12	3'-6"		
	v36	3	14	4'-9"	1'-3"	3'-6"
m36	4	7	4'-9"	1'-3"	2'-6"	
w36	STR.	15	20'-8"			
42"	a42	1	2	15'-5"	4'-7"	
	d42	2	87	2'-3"	1'-6"	9"
	h42	STR.	15	24'-2"		
	n42	2	16	3'-6"	2'-6"	1'-0"
	t42	STR.	27	14'-8"		
	u42	STR.	12	4'-1"		
	v42	3	17	5'-4"	1'-3"	4'-1"
m42	4	9	5'-4"	1'-3"	2'-9"	
w42	STR.	16	24'-2"			
48"	a48	1	2	17'-3"	5'-2"	
	d48	2	96	2'-3"	1'-6"	9"
	h48	STR.	15	27'-2"		
	n48	2	17	3'-6"	2'-6"	1'-0"
	t48	STR.	30	15'-8"		
	u48	STR.	12	4'-7"		
	v48	3	20	5'-10"	1'-3"	4'-7"
m48	4	10	5'-10"	1'-3"	3'-1"	
w48	STR.	17	27'-2"			

**REINFORCING BAR SCHEDULE
FOR ONE HEADWALL
TYPE III 1:10 SLOPE TWIN PIPE CULVERT**

PIPE DIA	NO. 4 REINFORCING BARS					
	MARK	TYPE	NO. REQ'D.	LENGTH	a	b
18"	a18	1	2	8'-7"	2'-5"	
	d18	2	65	2'-6"	1'-9"	9"
	h18	STR.	9	18'-0"		
	n18	2	9	3'-0"	2'-0"	1'-0"
	t18	STR.	21	7'-8"		
	u18	STR.	8	1'-9"		
	w18	STR.	9	18'-0"		
24"	a24	1	2	10'-5"	3'-0"	
	d24	2	86	2'-3"	1'-6"	9"
	h24	STR.	9	24'-8"		
	n24	2	11	3'-0"	2'-0"	1'-0"
	t24	STR.	28	9'-8"		
	u24	STR.	8	2'-6"		
	v24	3	13	3'-9"	1'-3"	2'-6"
m24	4	7	3'-9"	1'-3"	1'-11"	
w24	STR.	11	24'-8"			
30"	a30	1	2	11'-9"	3'-5"	
	d30	2	101	2'-3"	1'-6"	9"
	h30	STR.	12	29'-8"		
	n30	2	13	3'-0"	2'-0"	1'-0"
	t30	STR.	33	11'-8"		
	u30	STR.	8	3'-0"		
	v30	3	18	4'-3"	1'-3"	3'-0"
m30	4	9	4'-3"	1'-3"	2'-2"	
w30	STR.	13	29'-8"			
36"	a36	1	2	13'-7"	4'-0"	
	d36	2	120	2'-3"	1'-6"	9"
	h36	STR.	12	34'-8"		
	n36	2	15	3'-0"	2'-0"	1'-0"
	t36	STR.	38	13'-8"		
	u36	STR.	12	3'-6"		
	v36	3	23	4'-9"	1'-3"	3'-6"
m36	4	12	4'-9"	1'-3"	2'-5"	
w36	STR.	15	34'-8"			
42"	a42	1	2	15'-5"	4'-7"	
	d42	2	138	2'-3"	1'-6"	9"
	h42	STR.	15	40'-6"		
	n42	2	16	3'-6"	2'-6"	1'-0"
	t42	STR.	44	14'-8"		
	u42	STR.	12	4'-1"		
	v42	3	27	5'-4"	1'-3"	4'-1"
m42	4	14	5'-4"	1'-3"	2'-10"	
w42	STR.	16	40'-6"			
48"	a48	1	2	17'-3"	5'-2"	
	d48	2	153	2'-3"	1'-6"	9"
	h48	STR.	15	45'-6"		
	n48	2	17	3'-6"	2'-6"	1'-0"
	t48	STR.	49	15'-8"		
	u48	STR.	12	4'-7"		
	v48	3	32	5'-10"	1'-3"	4'-7"
m48	4	16	5'-10"	1'-3"	3'-1"	
w48	STR.	17	45'-6"			

NOTES:


- THE 'v' BARS, TYPE 3, AND 'm' BARS, TYPE 4, SHALL BE ORDERED FULL LENGTH AND CUT IN THE FIELD. THE REMAINING PORTION OF THE 'v' BARS SHALL BE USED IN THE OTHER EXTERIOR WALL. THE 'm' BARS SHALL BE USED IN THE INTERIOR WALL.
- THE LONG LEG OF THE 'd' AND 'n' BARS SHALL BE VERTICAL.
- QUANTITIES ON THIS DRAWING ARE BASED ON THE CAST-IN-PLACE DESIGN.
- "STR." = STRAIGHT BAR.
- ALL REINFORCING BARS ARE #4 BARS.
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).

Paul Kovacs
APPROVED CHIEF ENGINEER DATE 6-1-2009




HEADWALL TYPE III
18''-24''-30''-36''-42''-48''
FOR 1:4, 1:6, AND 1:10 SLOPES

STANDARD B6-02




PLAN




SECTION A-A

NOTE:
 'v' BARS ARE TO BEGIN AT THE PIPE END OF THE SLOPED EXTERIOR HEADWALLS. SEE DETAIL 1 FOR PLACING OF BARS AROUND WALL OPENING.


** CUT BARS IN FIELD TO FIT MIN. 2" CLEARANCE



ISOMETRIC VIEW



SECTION B-B



DETAIL 1


NOTE:
 'd' BARS, 'v' BARS AND 'w' BARS SHALL BE BENT OR DIPPED AS REQUIRED, AROUND THE WALL OPENING. 'h' BARS SHALL BE BENT OR CUT AS REQUIRED, AROUND THE OPENING.

DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III 1:4 SLOPE

PIPE DIA	DIMENSIONS											NO. OF SPACES			CONCRETE CLASS SI CU. YD.	REINF. STEEL LBS.	
	H	L	M	N	P	S	T	U	V	W	A	E	B	C			D
18"	3'-2"	12'-0"	3'-6"	1'-6"	4"	12'-4 1/2"	2"	2'-8"	3'-0"	4'-4"	2'-8"	2'-8"	2	--	--	2.8	244
24"	3'-8"	14'-0"	4'-3"	1'-8"	4"	14'-5 1/4"	2"	2'-8"	4'-0"	5'-4"	2'-2"	1'-8"	--	4	--	4.1	316
30"	4'-3"	16'-4"	4'-8"	1'-10"	6"	16'-10"	2"	2'-8"	5'-0"	6'-4"	2'-8"	1'-8"	4	--	--	5.6	422
36"	4'-9"	18'-4"	5'-0"	2'-0"	6"	18'-10 3/4"	2"	2'-8"	6'-0"	7'-4"	2'-2"	1'-8"	--	6	--	7.2	514
42"	5'-4"	20'-8"	5'-4"	2'-3"	6"	21'-3 3/4"	2"	3'-2"	6'-6"	7'-10"	2'-8"	2'-2"	3	3	--	8.8	625
48"	5'-11"	23'-0"	5'-8"	2'-6"	6"	23'-8 1/2"	2"	3'-2"	7'-0"	8'-4"	2'-8"	2'-2"	3	4	--	10.6	731


DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III 1:6 SLOPE

PIPE DIA	DIMENSIONS											NO. OF SPACES			CONCRETE CLASS SI CU. YD.	REINF. STEEL LBS.	
	H	L	M	N	P	S	T	U	V	W	A	E	B	C			D
18"	3'-2"	18'-0"	3'-6"	1'-6"	4"	18'-3"	2"	2'-8"	3'-0"	4'-4"	2'-2"	1'-8"	--	5	1	4.1	340
24"	3'-8"	21'-0"	4'-3"	1'-8"	4"	21'-3 1/2"	2"	2'-8"	4'-0"	5'-4"	2'-8"	2'-2"	3	3	--	5.7	440
30"	4'-3"	24'-6"	4'-8"	1'-10"	6"	24'-10"	2"	2'-8"	5'-0"	6'-4"	2'-8"	1'-8"	5	--	3	7.8	593
36"	4'-9"	27'-6"	5'-0"	2'-0"	6"	27'-10 1/2"	2"	2'-8"	6'-0"	7'-4"	2'-8"	2'-2"	7	1	--	10.0	722
42"	5'-4"	31'-0"	5'-4"	2'-3"	6"	31'-5 1/4"	2"	3'-2"	6'-6"	7'-10"	2'-8"	2'-2"	5	5	--	12.3	874
48"	5'-11"	34'-6"	5'-8"	2'-6"	6"	34'-11 3/4"	2"	3'-2"	7'-0"	8'-4"	2'-8"	2'-2"	3	9	--	14.7	1025



TYPE 1

TYPE 2



TYPE 3

NOTES:

1. THE 'v' BARS, TYPE 3, SHALL BE ORDERED FULL LENGTH AND CUT IN THE FIELD. THE REMAINING PORTION OF THE 'v' BARS SHALL BE USED IN THE OTHER WALL. THE LONG LEG OF THE 'd' BARS AND THE 'n' BARS SHALL BE VERTICAL.
2. THE LONG LEG OF THE 'd' AND 'n' BARS SHALL BE VERTICAL.
3. QUANTITIES ON THIS DRAWING ARE BASED ON THE CAST-IN-PLACE DESIGN.
4. "STR." = STRAIGHT BAR.
5. ALL REINFORCING BARS ARE #4 BARS.
6. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).

REINFORCING BAR SCHEDULE FOR ONE HEADWALL TYPE III 1:4 SLOPE

PIPE DIA	NO. 4 REINFORCING BARS					
	MARK	TYPE	NO. REQ'D.	LENGTH	a	b
18"	a18	1	1	8'-7"	2'-5"	
	d18	2	30	2'-3"	1'-6"	9"
	h18	STR.	8	11'-8"		
	n18	2	5	3'-0"	2'-0"	1'-0"
	t18	STR.	19	4'-0"		
	u18	STR.	4	3'-0"		
	v18	3	8	4'-3"	1'-3"	3'-0"
	w18	STR.	5	17'-8"		
24"	a24	1	1	10'-5"	3'-0"	
	d24	2	35	2'-3"	1'-6"	9"
	h24	STR.	8	13'-8"		
	n24	2	6	3'-0"	2'-0"	1'-0"
	t24	STR.	22	5'-0"		
	u24	STR.	5	3'-6"		
30"	a30	1	1	11'-9"	3'-5"	
	d30	2	42	2'-3"	1'-6"	9"
	h30	STR.	10	16'-0"		
	n30	2	7	3'-0"	2'-0"	1'-0"
	t30	STR.	24	6'-0"		
	u30	STR.	6	4'-1"		
36"	a36	1	1	13'-7"	4'-0"	
	d36	2	47	2'-3"	1'-6"	9"
	h36	STR.	10	18'-0"		
	n36	2	8	3'-0"	2'-0"	1'-0"
	t36	STR.	27	7'-0"		
	u36	STR.	7	4'-7"		
42"	a42	1	1	15'-5"	4'-7"	
	d42	2	52	2'-3"	1'-6"	9"
	h42	STR.	12	20'-4"		
	n42	2	8	3'-6"	2'-6"	1'-0"
	t42	STR.	30	7'-6"		
	u42	STR.	8	5'-2"		
48"	a48	1	1	17'-3"	5'-2"	
	d48	2	56	2'-3"	1'-6"	9"
	h48	STR.	12	22'-8"		
	n48	2	9	3'-6"	2'-6"	1'-0"
	t48	STR.	33	8'-0"		
	u48	STR.	8	5'-9"		

REINFORCING BAR SCHEDULE FOR ONE HEADWALL TYPE III 1:6 SLOPE

PIPE DIA	NO. 4 REINFORCING BARS					
	MARK	TYPE	NO. REQ'D.	LENGTH	a	b
18"	a18	1	1	8'-7"	2'-5"	
	d18	2	43	2'-3"	1'-6"	9"
	h18	STR.	8	17'-8"		
	n18	2	5	3'-0"	2'-0"	1'-0"
	t18	STR.	25	4'-0"		
	u18	STR.	4	3'-0"		
	v18	3	11	4'-3"	1'-3"	3'-0"
	w18	STR.	5	17'-8"		
24"	a24	1	1	10'-5"	3'-0"	
	d24	2	50	2'-3"	1'-6"	9"
	h24	STR.	8	20'-8"		
	n24	2	6	3'-0"	2'-0"	1'-0"
	t24	STR.	29	5'-0"		
	u24	STR.	5	3'-6"		
30"	a30	1	1	11'-9"	3'-5"	
	d30	2	58	2'-3"	1'-6"	9"
	h30	STR.	10	24'-2"		
	n30	2	7	3'-0"	2'-0"	1'-0"
	t30	STR.	33	6'-0"		
	u30	STR.	6	4'-1"		
36"	a36	1	1	13'-7"	4'-0"	
	d36	2	65	2'-3"	1'-6"	9"
	h36	STR.	10	27'-2"		
	n36	2	8	3'-0"	2'-0"	1'-0"
	t36	STR.	37	7'-0"		
	u36	STR.	7	4'-7"		
42"	a42	1	1	15'-5"	4'-7"	
	d42	2	72	2'-3"	1'-6"	9"
	h42	STR.	12	30'-8"		
	n42	2	8	3'-6"	2'-6"	1'-0"
	t42	STR.	40	7'-6"		
	u42	STR.	8	5'-2"		
48"	a48	1	1	17'-3"	5'-2"	
	d48	2	80	2'-3"	1'-6"	9"
	h48	STR.	12	34'-2"		
	n48	2	9	3'-6"	2'-6"	1'-0"
	t48	STR.	45	8'-0"		
	u48	STR.	8	5'-9"		

SIDE ENTRANCE DESIGN

FOR STEEL GRATING DETAILS SEE SHEET 5 (OF 5) IN THIS SERIES

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009



HEADWALL TYPE III 18"-24"-30"-36"-42"-48" FOR 1:4, 1:6 AND 1:10 SLOPES

STANDARD B6-02

GRATE DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III END ENTRANCE 1:4 SLOPE

INSIDE PIPE DIAMETER	GRATES		BARS FOR ONE GRATE				HEADWALL GRATES (LBS.)	
	NUMBER REQUIRED	TYPE REQ'D.	BAR NO. 1		BAR NO. 2		EACH GRATE	TOTAL
			BARS REQ'D.	LENGTH	BARS REQ'D.	LENGTH		
18"	2	B	2	3'-7"	5	1'-10 1/2"	53	154
	1	C	2	3'-7"	5	1'-4 1/2"	48	
24"	4	B	2	4'-7"	7	1'-10 1/2"	69	276
	-	-	-	-	-	-	-	
30"	4	A	2	5'-7"	9	2'-4 1/2"	94	376
	-	-	-	-	-	-	-	
36"	5	B	2	6'-7"	11	1'-10 1/2"	103	608
	1	C	2	6'-7"	11	1'-4 1/2"	93	
42"	5	A	2	7'-1"	12	2'-4 1/2"	121	705
	1	C	2	7'-1"	12	1'-4 1/2"	100	
48"	7	B	2	7'-7"	13	1'-10 1/2"	119	941
	1	C	2	7'-7"	13	1'-4 1/2"	108	

GRATE DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III END ENTRANCE 1:6 SLOPE

INSIDE PIPE DIAMETER	GRATES		BARS FOR ONE GRATE				HEADWALL GRATES (LBS.)	
	NUMBER REQUIRED	TYPE REQ'D.	BAR NO. 1		BAR NO. 2		EACH GRATE	TOTAL
			BARS REQ'D.	LENGTH	BARS REQ'D.	LENGTH		
18"	2	B	2	3'-7"	5	1'-10 1/2"	53	250
	3	C	2	3'-7"	5	1'-4 1/2"	48	
24"	5	A	2	4'-7"	7	2'-4 1/2"	75	375
	-	-	-	-	-	-	-	
30"	6	B	2	5'-7"	9	1'-10 1/2"	86	672
	2	C	2	5'-7"	9	1'-4 1/2"	78	
36"	4	A	2	6'-7"	11	2'-4 1/2"	112	860
	4	B	2	6'-7"	11	1'-10 1/2"	103	
42"	6	A	2	7'-1"	12	2'-4 1/2"	121	1126
	4	C	2	7'-1"	12	1'-4 1/2"	100	
48"	8	A	2	7'-7"	13	2'-4 1/2"	130	1278
	2	B	2	7'-7"	13	1'-10 1/2"	119	

GRATE DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III END ENTRANCE 1:10 SLOPE

INSIDE PIPE DIAMETER	GRATES		BARS FOR ONE GRATE				HEADWALL GRATES (LBS.)	
	NUMBER REQUIRED	TYPE REQ'D.	BAR NO. 1		BAR NO. 2		EACH GRATE	TOTAL
			BARS REQ'D.	LENGTH	BARS REQ'D.	LENGTH		
18"	6	B	2	3'-7"	5	1'-10 1/2"	53	414
	2	C	2	3'-7"	5	1'-4 1/2"	48	
24"	9	B	2	4'-7"	7	1'-10 1/2"	69	747
	2	C	2	4'-7"	7	1'-4 1/2"	63	
30"	12	B	2	5'-7"	9	1'-10 1/2"	86	1110
	1	C	2	5'-7"	9	1'-4 1/2"	78	
36"	15	B	2	6'-7"	11	1'-10 1/2"	103	1535
	-	-	-	-	-	-	-	
42"	13	B	2	7'-1"	12	1'-10 1/2"	111	2043
	6	C	2	7'-1"	12	1'-4 1/2"	100	
48"	16	B	2	7'-7"	13	1'-10 1/2"	119	2443
	5	C	2	7'-7"	13	1'-4 1/2"	108	

GRATE DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III SIDE ENTRANCE 1:4 SLOPE


INSIDE PIPE DIAMETER	GRATES		BARS FOR ONE GRATE				HEADWALL GRATES (LBS.)	
	NUMBER REQUIRED	TYPE REQ'D.	BAR NO. 1		BAR NO. 2		EACH GRATE	TOTAL
			BARS REQ'D.	LENGTH	BARS REQ'D.	LENGTH		
18"	4	A	2	3'-7"	5	2'-4 1/2"	57	228
	-	-	-	-	-	-	-	
24"	5	B	2	4'-7"	7	1'-10 1/2"	69	408
	1	C	2	4'-7"	7	1'-4 1/2"	63	
30"	5	A	2	5'-7"	9	2'-4 1/2"	94	548
	1	C	2	5'-7"	9	1'-4 1/2"	78	
36"	7	B	2	6'-7"	11	1'-10 1/2"	103	814
	1	C	2	6'-7"	11	1'-4 1/2"	93	
42"	4	A	2	7'-1"	12	2'-4 1/2"	121	928
	4	B	2	7'-1"	12	1'-10 1/2"	111	
48"	4	A	2	7'-7"	13	2'-4 1/2"	130	1115
	5	B	2	7'-7"	13	1'-10 1/2"	119	

GRATE DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE III SIDE ENTRANCE 1:6 SLOPE


INSIDE PIPE DIAMETER	GRATES		BARS FOR ONE GRATE				HEADWALL GRATES (LBS.)	
	NUMBER REQUIRED	TYPE REQ'D.	BAR NO. 1		BAR NO. 2		EACH GRATE	TOTAL
			BARS REQ'D.	LENGTH	BARS REQ'D.	LENGTH		
18"	6	B	2	3'-7"	5	1'-10 1/2"	53	414
	2	C	2	3'-7"	5	1'-4 1/2"	48	
24"	4	A	2	4'-7"	7	2'-4 1/2"	75	576
	4	B	2	4'-7"	7	1'-10 1/2"	69	
30"	6	A	2	5'-7"	9	2'-4 1/2"	94	876
	4	C	2	5'-7"	9	1'-4 1/2"	78	
36"	8	A	2	6'-7"	11	2'-4 1/2"	112	1102
	2	B	2	6'-7"	11	1'-10 1/2"	103	
42"	6	A	2	7'-1"	12	2'-4 1/2"	121	1392
	6	B	2	7'-1"	12	1'-10 1/2"	111	
48"	4	A	2	7'-7"	13	2'-4 1/2"	130	1602
	10	B	2	7'-7"	13	1'-10 1/2"	119	

NOTES:









- ALL STRUCTURAL STEEL SHALL BE AASHTO M270, GRADE 36.
- GALVANIZING SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.
- FOR PLACEMENT OF GRATES, SEE SHEET 1 OR 4 (OF 5) IN THIS SERIES.
- ALL TABLE DIMENSIONS AND QUANTITIES ARE FOR SINGLE PIPE CULVERT HEADWALLS. TO ADAPT ANY OF THESE TABLES FOR DOUBLE PIPE CULVERTS, DOUBLE THE NUMBER OF GRATES REQUIRED AND DOUBLE THE TOTAL WEIGHT (LBS.) OF THE GRATES.
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).



TYPICAL GRATE



SECTION A-A



BAR INSTALLATION DETAIL

SLOPE DRAIN INLET

NOTES FOR SLOPE DRAIN INLET:

1. THE LOCATION OF THE SLOPE DRAIN INLET SHALL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. THE INLET MUST BE LOCATED IN THE FIELD TO CLEAR THE POST SPACING OF EXISTING OR PROPOSED GUARDRAIL. WHERE CONDITIONS REQUIRE THAT THE SLOPE DRAIN INLET BE LOCATED ADJACENT TO A GUARDRAIL ANCHOR INSTALLATION, THE SLOPE DRAIN INLET MUST BE CONSTRUCTED OUTSIDE THE LIMIT OF THE ANCHOR INSTALLATION.
2. INLET CONSTRUCTION EXCLUSIVE OF P.C.C. APRON SHALL BE COMPLETED PRIOR TO SHOULDER OVERLAY. CONSTRUCTION OF P.C.C. APRON SHALL FOLLOW SHOULDER OVERLAY.
3. THE MATERIALS AND CONSTRUCTION OF THE INLET SHALL CONFORM TO THE APPLICABLE PORTIONS OF THE STANDARD SPECIFICATIONS AND THE SPECIAL PROVISIONS.
4. THE CONCRETE CURB WITHIN THE P.C.C. APRON WILL TRANSITION TO MATCH THE SHAPE OF ABUTTING CURBS.
5. INCREASE NORMAL SHOULDER SLOPE WITHIN LIMITS OF P.C.C. APRON AND SHAPE TO DRAIN INTO INLET OPENING. THE INLET OPENING SHALL BE 2 1/2" BELOW THE NORMAL SHOULDER EDGE ELEVATION.
6. GALVANIZED STEEL COVER PLATE SHALL CONFORM TO THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS. GALVANIZING SHALL BE IN ACCORDANCE WITH ASTM A123 (AASHTO M111).
7. EXPANDED METAL FABRIC OF EQUAL STRENGTH MAY BE USED IN LIEU OF WELDED WIRE FABRIC SUBJECT TO ENGINEER'S APPROVAL.
8. PRECAST CONCRETE UNITS FOR SLOPE DRAIN INLET WILL BE ACCEPTABLE PROVIDED THEY MEET ALL THE REQUIREMENTS SHOWN ON THIS DRAWING. FABRICATION DRAWINGS SHOWING PIPE OPENINGS, REINFORCEMENT AND OTHER PERTINENT DIMENSIONS WILL BE REQUIRED FOR EACH UNIT, FOR APPROVAL BY THE ENGINEER PRIOR TO FABRICATION.
9. REINFORCEMENT BARS AND WELDED WIRE FABRIC DESIGNATED (E) SHALL BE EPOXY COATED.

NOTES FOR CATCH BASIN TYPE B:

1. THE LOCATION OF THE CATCH BASIN SHALL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
2. FOR MATERIALS AND CONSTRUCTION REQUIREMENTS OF THE CATCH BASIN, REFER TO THE STANDARD SPECIFICATIONS.
3. FRAME AND GRATE FOR CATCH BASIN TYPE B SHALL BE NEENAH FOUNDRY COMPANY TYPE R-3455C OR APPROVED EQUAL.
4. AT LOCATIONS WHERE EXISTING UNDERDRAINS AND/OR STORM SEWER PIPES ARE TO BE CONNECTED TO THE NEW CATCH BASIN, THE REMOVAL OF EXISTING PIPES, FURNISHING OF NEW PIPE SECTIONS OF THE SAME SIZE AND OTHER MATERIALS NECESSARY FOR THE CONNECTIONS SHALL BE INCIDENTAL TO THE COST OF CATCH BASIN TYPE B.
5. PRECAST CONCRETE UNITS FOR CATCH BASIN WILL BE ACCEPTABLE PROVIDED THEY MEET ALL THE REQUIREMENTS AS SHOWN ON THIS DRAWING. BASE EXTENSION OF 3" NOT REQUIRED FOR PRECAST UNITS. FABRICATION DRAWINGS SHOWING PIPE OPENINGS, REINFORCEMENT AND OTHER PERTINENT DIMENSIONS WILL BE REQUIRED FOR EACH UNIT, FOR APPROVAL BY THE ENGINEER PRIOR TO FABRICATION.
6. REINFORCEMENT BARS DESIGNATED (E) SHALL BE EPOXY COATED.

CATCH BASIN TYPE B






APPROVED *Jeff Daley* CHIEF ENGINEER DATE 1-1-2007

DATE	REVISIONS

Illinois Tollway
Open Roads for a Faster Future


CATCH BASIN TYPE B AND SLOPE DRAIN INLET

STANDARD B7-00



NOTE:
 * POSITION OF OPENING VARIES FROM 3'-2" TO 5'-4" MEASURED FROM BACK OF GUTTER LINE

CATCH BASIN TYPE "G" SERIES




REINFORCED CONCRETE LID
 TYPE G-3 FRAME AND GRATE
 TYPE G-3 MODIFIED FRAME AND GRATE



DRAINAGE STRUCTURE TYPE G-3, MODIFIED

NOTES:


1. PRECAST CONCRETE UNITS WILL BE ACCEPTABLE PROVIDED THEY MEET ALL THE REQUIREMENTS AS SHOWN ON THIS DRAWING. BASE EXTENSION OF 3" NOT REQUIRED FOR PRECAST UNITS. FABRICATION DRAWINGS SHOWING PIPE OPENINGS, REINFORCEMENT AND OTHER PERTINENT DIMENSIONS WILL BE REQUIRED FOR EACH UNIT, FOR APPROVAL BY THE ENGINEER PRIOR TO FABRICATION.
2. CATCH BASINS TYPE G-SERIES SHALL BE USED IN THE SWALE ON THE HIGH SIDE OF SUPERELEVATED PAVEMENT.
3. CATCH BASINS TYPE G-2 SHALL BE USED ALONG RAMPS WHERE G-2 GUTTER IS PROVIDED.
4. CATCH BASINS TYPE G-3 SHALL BE USED WHERE G-3 GUTTER IS PROVIDED.
5. CATCH BASINS TYPE G-3 MODIFIED SHALL BE USED IN PAVEMENT SECTIONS AND ON THE LOW SIDE OF SUPERELEVATED PAVEMENT.
6. CATCH BASINS TYPE G-3 MODIFIED SHALL BE PROVIDED WITH A REINFORCED CONCRETE SLAB TOP AS DETAILED ON THIS DRAWING.
7. TYPE S FRAME AND GRATE SHALL BE NEENAH R-3338-F MODIFIED BY THE ADDITION OF THE FOURTH SIDE OF THE FRAME, OR APPROVED EQUAL.
8. REFER TO STANDARD B9 (FRAME AND GRATE TYPE S, REINFORCED CONCRETE LID FOR TYPES G-3 & S FRAMES) FOR FRAME AND GRATE DETAILS.
9. TYPE G-2 FRAME AND GRATE SHALL BE NEENAH R-3508-A2 OR APPROVED EQUAL.
10. TYPE G-3 FRAME AND GRATE SHALL BE NEENAH INLET FOR ROLL TYPE CURB R-3501-U OR EAST JORDAN IRON WORKS 10004 OR APPROVED EQUAL.
11. TYPE G-3, MODIFIED FRAME AND GRATE SHALL BE NEENAH INLET FOR ROLL TYPE CURB SPECIAL R-3501-UI OR APPROVED EQUAL.
12. MORTAR OR SEALER SHALL BE USED WHEN A PRECAST REINFORCED CONCRETE LID IS USED.
13. REINFORCEMENT BARS DESIGNATED (E) SHALL BE EPOXY COATED.




TYPICAL REINFORCEMENT AROUND STORM SEWER PIPE




SECTION Y-Y




SECTION Z-Z




TYPE G-2 FRAME & GRATE




SECTION T-T




SECTION U-U



SECTION W-W



TYPE G-3 FRAME & GRATE



TYPE G-3, MODIFIED FRAME & GRATE


APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009

DATE	REVISIONS
6-1-2009	DELETE REINF. CONC. LID TYPE S FRAME & GRATE


Illinois Tollway
Open Roads for a Faster Future

CATCH BASINS TYPES G AND TYPE G MODIFIED, FRAMES AND GRATES
 TYPE G-2, G-3 & G-3 MODIFIED


STANDARD B8-01




PLAN




PLAN




d - BARS




v - BARS



SECTION A-A




ELEVATION



* MATCH EXISTING SLOPE

SECTION B-B



SECTION C-C

NOTES:

1. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
2. BAR BENDING DETAILS ARE DIMENSIONED OUT TO OUT OF BARS.
3. ALL EXPOSED EDGES SHALL HAVE A 3/4"-45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW THE FINISHED GROUND LINE.
4. CARE SHALL BE EXERCISED IN REMOVING ANY LENGTH OF EXISTING PIPE SO THE REMAINING PIPE IS UNDAMAGED AND FULLY FUNCTIONING.
5. THE STATION, OFFSET AND INVERT ELEVATION FOR THE HEADWALL SHALL APPLY AT THE END OF THE CONNECTING PIPE OPENING.
6. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT.
7. TYPES I AND II SLOPED HEADWALLS TO BE USED ONLY IN SLOPE STEEPER THAN 1:3.

PIPE DIA.	MARK	NO. & SIZE	LENGTH
6"	b	4-#4	2'-0"
	w	4-#4	4'-9"
12"	b	4-#4	2'-6"
	w	4-#4	5'-10"
15"	b	4-#4	3'-3"
	w	4-#4	6'-5"
18"	b	4-#4	4'-0"
	w	4-#4	7'-0"

DESIGN NO.	INSIDE DIA. OF PIPE	CL. SP CONC. 2 HDWLS.	REINF. BARS. 2 HDWLS.
F-6-2	6"	0.8 C.Y.	40 #
F-12-2	12"	1.0 C.Y.	45 #
F-15-2	15"	1.2 C.Y.	50 #
F-18-2	18"	1.4 C.Y.	50 #

PIPE DIA.	MARK	NO. & SIZE	LENGTH	REINFORCING BARS		
				a	b	c
12"	d	8-#4	3'-6"	2'-6"	1'-0"	---
	v	6-#4	10'-3"	4'-3"	2'-0"	4'-0"
15"	d1	8-#4	3'-9"	2'-9"	1'-0"	---
	v1	6-#4	10'-9"	4'-3"	2'-0"	4'-6"
18"	d2	8-#4	4'-6"	3'-3"	1'-0"	---
	v2	6-#4	11'-3"	4'-3"	2'-0"	5'-0"

DESIGN NO.	INSIDE DIA. OF PIPE	CL. SP CONC. 2 HDWLS.	REINF. BARS. 2 HDWLS.
E-12-2	12"	2.2 C.Y.	95 #
E-15-2	15"	2.3 C.Y.	100 #
E-18-2	18"	2.4 C.Y.	105 #

SLOPED HEADWALL
TYPE I

SLOPED HEADWALL
TYPE II

APPROVED *Paul Kovacs* DATE 1-1-2011
CHIEF ENGINEER



DATE	REVISIONS

Illinois Tollway
Open Roads for a Faster Future







SLOPED HEADWALLS
TYPE I AND TYPE II

STANDARD B9-00

DIMENSIONS AND QUANTITIES IN ONE SLOPED HEADWALL TYPE III



NOTE:
EACH #4d BAR SHALL BE PLACED SUCH THAT IT WILL PROJECT 9" INTO THE CAST IN PLACE (CIP) CONCRETE AND IT SHALL BE 3" BELOW THE TOP SURFACE. HOOKS IN THE PRECAST SECTION SHALL BE TIPPED TO CLEAR ALL CONCRETE SURFACES A MIN. OF 2".



PIPE DIA	DIMENSIONS											PRE CAST CONC. CU. YD.	CAST-IN-PLACE CU. YD.	WELDED WIRE FABRIC SQ. YD.	NO. OF #4d BARS	REINF. STEEL LBS.	MARK	LENGTH
	A	B	C	N	M	P	S	L	V	W								
6"	9"	2 3/4"	1'-9 3/4"	1'-0"	1'-8"	1'-6 3/4"	2'-11 1/4"	7'-2"	1'-0"	3'-6"	.19	.51	2.67	12	16	4d6	2'-0"	
12"	1'-3 1/2"	2 3/4"	2'-4 1/4"	1'-0"	1'-8"	1'-6 3/4"	4'-6 3/4"	8'-9 1/2"	1'-0"	4'-0"	.36	.65	3.80	14	19	4d12	2'-0"	
15"	1'-6 1/2"	2 3/4"	2'-7 1/4"	1'-0"	1'-8"	1'-6 3/4"	5'-3 3/4"	9'-6 1/2"	1'-0"	4'-3"	.47	.73	5.13	16	21	4h15	2'-0"	
18"	1'-10"	2 3/4"	2'-10 3/4"	1'-0"	1'-8"	1'-6 3/4"	6'-2 1/4"	10'-5"	1'-0"	4'-6"	.61	.80	5.65	18	24	4d18	2'-0"	
21"	2'-1"	2 3/4"	3'-1 3/4"	1'-0"	1'-9"	1'-6 3/4"	6'-11 1/4"	11'-3"	1'-3"	5'-3"	.74	1.0	7.42	22	29	4d21	2'-0"	
24"	2'-4 1/2"	2 3/4"	3'-5 1/4"	1'-0"	2'-0"	1'-6 3/4"	7'-9 3/4"	12'-4 1/2"	1'-6"	6'-0"	.86	1.24	8.80	24	32	4d24	2'-0"	
27"	2'-7 1/2"	2 3/4"	3'-8 1/4"	1'-1 1/2"	2'-3"	1'-6 3/4"	8'-6 3/4"	13'-6"	1'-9"	6'-9"	1.03	1.53	12.35	24	32	4d27	2'-0"	
30"	2'-11"	2 3/4"	3'-11 3/4"	1'-3"	2'-6"	1'-6 3/4"	9'-5 1/4"	14'-9"	2'-0"	7'-6"	1.22	2.00	15.08	26	35	4d30	2'-0"	

PIPE DIA	DIMENSIONS											PRE CAST CONC. CU. YD.	CAST-IN-PLACE CU. YD.	WELDED WIRE FABRIC SQ. YD.	NO. OF #4d BARS	REINF. STEEL LBS.	MARK	LENGTH
	A	B	C	N	M	P	S	L	V	W								
6"	9"	1 3/4"	1'-8 3/4"	1'-0"	1'-8"	2'-1"	3'-7"	8'-4"	1'-0"	3'-6"	.21	.57	3.27	12	16	4d6	2'-0"	
12"	1'-3 1/2"	1 3/4"	2'-3 1/4"	1'-0"	1'-8"	2'-1"	5'-9"	10'-6"	1'-0"	4'-0"	.44	.75	4.58	16	21	4d12	2'-0"	
15"	1'-6 1/2"	1 3/4"	2'-6 1/4"	1'-0"	1'-8"	2'-1"	6'-9"	11'-6"	1'-0"	4'-3"	.57	.83	5.66	18	24	4h15	2'-0"	
18"	1'-10"	1 3/4"	2'-9 3/4"	1'-0"	1'-8"	2'-1"	7'-11"	12'-8"	1'-0"	4'-6"	.73	.93	7.57	22	29	4d18	2'-0"	
21"	2'-1"	1 3/4"	3'-0 3/4"	1'-0"	1'-9"	2'-1"	8'-11"	13'-9"	1'-3"	5'-3"	.89	1.16	9.83	24	32	4d21	2'-0"	
24"	2'-4 1/2"	1 3/4"	3'-4 1/4"	1'-0"	2'-0"	2'-1"	10'-1"	15'-2"	1'-6"	6'-0"	1.12	1.45	12.51	28	37	4d24	2'-0"	
27"	2'-7 1/2"	1 3/4"	3'-7 1/4"	1'-1 1/2"	2'-3"	2'-1"	11'-1"	16'-6 1/2"	1'-9"	6'-9"	1.32	1.77	13.28	30	40	4d27	2'-0"	
30"	2'-11"	1 3/4"	3'-10 3/4"	1'-3"	2'-6"	2'-1"	12'-3"	18'-1"	2'-0"	7'-6"	1.58	2.14	18.77	32	43	4d30	2'-0"	

PIPE DIA	DIMENSIONS											PRE CAST CONC. CU. YD.	CAST-IN-PLACE CU. YD.	WELDED WIRE FABRIC SQ. YD.	NO. OF #4d BARS	REINF. STEEL LBS.	MARK	LENGTH
	A	B	C	N	M	P	S	L	V	W								
6"	9"	1 1/2"	1'-8 1/2"	1'-0"	1'-8"	3'-0"	5'-3"	10'-11"	1'-0"	3'-6"	.29	.71	4.11	16	21	4d6	2'-0"	
12"	1'-3 1/2"	1 1/2"	2'-3"	1'-0"	1'-8"	3'-0"	8'-6"	14'-2"	1'-0"	4'-0"	.60	.96	7.27	22	29	4d12	2'-0"	
15"	1'-6 1/2"	1 1/2"	2'-6"	1'-0"	1'-8"	3'-0"	10'-0"	15'-8"	1'-0"	4'-3"	.79	1.07	8.91	26	35	4h15	2'-0"	
18"	1'-10"	1 1/2"	2'-9 1/2"	1'-0"	1'-8"	3'-0"	11'-9"	17'-5"	1'-0"	4'-6"	1.03	1.20	10.95	28	37	4d18	2'-0"	
21"	2'-1"	1 1/2"	3'-0 1/2"	1'-0"	1'-9"	3'-0"	13'-3"	19'-0"	1'-3"	5'-3"	1.29	1.51	14.00	34	45	4d21	2'-0"	
24"	2'-4 1/2"	1 1/2"	3'-4"	1'-0"	2'-0"	3'-0"	15'-0"	21'-0"	1'-6"	6'-0"	1.59	1.89	15.49	38	51	4d24	2'-0"	
27"	2'-7 1/2"	1 1/2"	3'-7"	1'-1 1/2"	2'-3"	3'-0"	16'-6"	22'-10 1/2"	1'-9"	6'-9"	1.90	2.30	21.82	40	53	4d27	2'-0"	
30"	2'-11"	1 1/2"	3'-10 1/2"	1'-3"	2'-6"	3'-0"	18'-3"	25'-0"	2'-0"	7'-6"	2.27	2.79	26.60	44	59	4d30	2'-0"	

NOTES:

- CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
- THE CAST IN PLACE (CIP) SLOPED HEADWALL SHALL BE CONSTRUCTED FLUSH WITH EXISTING OR PROPOSED SLOPE.
- THE SLOPED HEADWALL DETAILS SHOWN ON THIS DRAWING ARE FOR USE ONLY WITH PIPES HAVING DIAMETER OR SPAN OF 30" OR LESS.
- AFTER THE PRECAST SLOPED HEADWALL HAS BEEN PLACED, THE SPACE BETWEEN THE HEADWALL AND PIPE SHALL BE COMPLETELY FILLED WITH AN APPROVED NON-SHRINK GROUT WITH A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 5000 PSI. THE COST FOR FURNISHING AND PLACING THE GROUT SHALL BE INCIDENTAL TO SLOPED HEADWALLS.
- WELDED WIRE FABRIC SHALL BE 6x6-W4xW4, 58 LBS. PER 100 SQ.FT.
- QUANTITIES FOR CONCRETE, WELDED WIRE FABRIC, AND REINFORCING STEEL SHOWN IN THE SCHEDULES OF QUANTITIES ARE BASED ON A "H" DIMENSION OF 0'-0".
- PRECAST UNIT USE IS OPTIONAL. THE ENTIRE STRUCTURE MAY BE CAST IN PLACE.
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009

DATE	REVISIONS
5-10-2007	CHANGES TO NOTES 4 AND 7
	NOTE 9 ADDED
6-1-2009	ADDED TABLE INFORMATION
	ADDED DIMENSION NOTATIONS TO SLOPED HEADWALL
3-1-2010	REVISED NOTES
1-1-2011	REVISED NOTES


Illinois Tollway
Open Roads for a Faster Future

SLOPED HEADWALLS
TYPE III DETAILS


STANDARD B10-04



PLAN




SECTION H-H



SECTION E-E

F = 1/2" DIA. (PIPE) + 1'-0" (MIN.)



SECTION D-D


NOTES:

1. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
2. THE SLOPED HEADWALL TYPE IV SHALL BE CONSTRUCTED FLUSH WITH EXISTING OR PROPOSED SLOPE.
3. THE SLOPED HEADWALL DETAILS SHOWN IN THIS DRAWING ARE FOR USE ONLY WITH PIPES HAVING DIAMETER OR SPAN OF 18" OR LESS.
4. WELDED WIRE FABRIC SHALL BE 6"x6" W4xW4, 58 LBS. PER 100 SQ. FT.
5. QUANTITIES FOR CONCRETE HEADWALLS (CLASS SI) AND WELDED WIRE FABRIC SHOWN IN THE SCHEDULES OF QUANTITIES ARE BASED ON THE FOLLOWING:
 - A. DIMENSION "G" IS 0'-0".
 - B. DIMENSION "H" IS 1'-0".
 - C. PAVED DITCH LENGTH IS 20'-0".
 - D. PAVED DITCH BOTTOM SHALL MATCH EXISTING OR PROPOSED DITCH, 2'-0" OR 4'-0".
 - E. BACKSLOPE AND FORESLOPE ARE THE SAME. ADJUSTMENT TO QUANTITIES FOR SLOPED HEADWALLS WITH DIMENSIONS OR BACKSLOPE/ FORESLOPE COMBINATIONS OTHER THAN ABOVE SHALL BE INDICATED ON THE PLANS.
 - F. THE QUANTITIES ARE SHOWN FOR INFORMATION ONLY.
6. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT.

QUANTITIES FOR SLOPED HEADWALLS TYPE IV


(SEE NOTE 5)

SLOPE	PIPE DIA.	CONCRETE HEADWALLS (CLASS SI) (CUBIC YARDS)	CONCRETE HEADWALLS (CLASS SI) (CUBIC YARDS)	WELDED WIRE FABRIC (SQUARE FEET)	WELDED WIRE FABRIC (SQUARE FEET)
		2'-0" BOTTOM	4'-0" BOTTOM	2'-0" BOT.	4'-0" BOT.
1:3	6"	5.41	6.45	239	295
	12"	5.61	6.64	251	307
	15"	5.80	6.84	262	318
	18"	6.01	7.05	274	330
1:4	6"	6.68	7.03	297	353
	12"	6.93	7.97	312	368
	15"	7.19	8.23	327	383
	18"	7.47	8.51	343	399
1:6	6"	9.26	10.30	414	470
	12"	9.63	10.67	437	493
	15"	10.02	11.05	459	515
	18"	10.42	11.46	483	539



SECTION C-C

DETAIL FOR PIPE AT DITCH FLOW LINE



SECTION C-C

DETAIL FOR PIPE ABOVE DITCH FLOW LINE


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 1-1-2011

DATE	REVISIONS
5/10/07	CHANGES TO NOTES 5 AND 6
1-1-2011	REVISED NOTES




SLOPED HEADWALLS TYPE IV DETAILS

STANDARD B11-02



PLAN



SECTION A-A
DRAIN CHANNEL INSTALLATION

NOTES:


1. OUTLET PIPES AND PREFORMED CHANNEL INVERTS SHALL BE SLOPED AT 0.6% OR STEEPER TOWARD OUTLET REGARDLESS OF THE SURFACE SLOPE.
2. TRENCH DRAIN MAY BE STUBBED DIRECTLY INTO DRAINAGE STRUCTURES OR OUTLET PIPES MAY BE USED TO CONNECT TRENCH DRAIN TO DRAINAGE STRUCTURES.
3. A CLEAN-OUT PORT COMPATIBLE WITH THE MANUFACTURED SYSTEM SHALL BE PROVIDED FOR TRENCH DRAINS AT THE UPSTREAM END AND AT INTERVALS NOT TO EXCEED 100 FEET. THE CLEAN-OUT SHALL HAVE A REMOVABLE LOAD RESISTANT COVER OR GRATE.
4. TRENCH EXCAVATION MUST ALLOW FOR A MINIMUM OF 12 INCHES OF CONCRETE TO BE PLACED UNDER AND ALONGSIDE THE TRENCH DRAIN CHANNEL SYSTEM.
5. THE FINISHED LEVEL OF CONCRETE MUST BE APPROXIMATELY 1/8" ABOVE THE TOP OF THE DRAIN CHANNEL.
6. TRENCH DRAINS SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS DETAILS AND SPECIFICATIONS.
7. PROVIDE 1" EXPANSION JOINT WITH PREFORMED JOINT FILLER BETWEEN PAVED SHOULDER AND TRENCH DRAIN ENCASEMENT.
8. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL PLACEMENT (V:H).
9. WHEN THE CONCRETE ENCASEMENT FOR TRENCH DRAIN IS WITHIN 6' OF THE PAVEMENT, REPLACE THE GORE SURFACING WITH CLASS SI CONCRETE 9" DEPTH; PAY ITEM: PORTLAND CEMENT CONCRETE SHOULDER (9").




APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 1-1-2011

DATE	REVISIONS
1-1-2011	DELETED SLOTTED DRAIN ADDED TRENCH DRAIN


TRENCH DRAIN DETAIL
STANDARD B12-02



SECTION B-B
PIPE OUTLET TO DRAINAGE STRUCTURE




SECTION E-E
RAMP ON OUTSIDE OF
SUPERELEVATED MAINLINE SECTION








SECTION D-D

* 1:10 MAXIMUM FOR NEW CONSTRUCTION
1:4 MAXIMUM FOR REHABILITATION




SECTION C-C

** 4% DESIRABLE FOR NEW CONSTRUCTION
1:10 MAXIMUM FOR NEW CONSTRUCTION
1:4 MAXIMUM FOR REHABILITATION




NOTE:
 A 3/4" x 9 1/2" BOLT WITH ADDITIONAL W WASHER PLACED IN A 3/8" HOLE DRILLED THROUGH THE HEADWALL OR A 3/4" x 8" THREADED ROD EPOXY GROUTED IN A 3/8" HOLE WITH A MINIMUM EMBEDMENT OF 6 5/8" MAY BE USED IN LIEU OF CAST-IN-PLACE BOLT SHOWN.



NOTE:
 BARS O ARE TO BE FIELD CUT PER CUTTING DIAGRAM. PLACE BARS WITH DIMENSIONS C4-C6 BEGINNING AT HEADWALL AND BARS WITH DIMENSIONS C3-C6 BEGINNING AT THE TOEWALL END.



NOTE:
 DOWEL BAR J & H NOT REQUIRED WITH EXISTING BOX CULVERTS PROVIDING THE REINFORCING FROM THE EXISTING BOX IS EXTENDED INTO THE NEW CONCRETE A MINIMUM OF 1'-3".




NOTE:
 BARS V, P1 AND U ARE TO BE FIELD CUT PER CUTTING DIAGRAM. PLACE ONE-HALF THE BARS IN OR NEAR EACH WINGWALL BEGINNING WITH THE SHORTEST BARS V AND BARS P1 AT THE TOEWALL END AND LONGEST BARS U AT THE BOTTOM OF THE WALL.




PIPE RUNNER DETAILS

GENERAL NOTES:


- ALL CONCRETE SHALL BE CLASS S1.
- ALL EXPOSED CONCRETE EDGES SHALL HAVE A 3/4" x 45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW FINISHED GROUND LEVEL. COVER FROM THE FACE OF CONCRETE TO THE FACE OF REINFORCEMENT BARS SHALL BE 2", UNLESS OTHERWISE SHOWN.
- CONCRETE QUANTITIES SHOWN ON SHEET 2 (OF 2) IN THIS SERIES ARE FOR REINFORCED CONCRETE BOX CULVERT SECTIONS AND ADDITIONAL CONCRETE REQUIRED IN HEADWALLS FOR PIPE OR ARCH CULVERT SECTIONS SHALL BE ADDED TO THESE QUANTITIES.
- THIS STANDARD MAY BE USED FOR CULVERTS WITH SKEW OF 0° ± 7.5°. AS SHOWN PER CULVERT SKEW ORIENTATION ON THIS SHEET.
- DESIGN: SAFETY PIPE RUNNERS ARE DESIGNED FOR A TRANSVERSING LOAD OF 1,800 POUNDS AT YIELD AS RECOMMENDED BY RESEARCH REPORT 280-1, SAFETY TREATMENT OF ROADSIDE CROSS DRAINAGE STRUCTURES, TEXAS TRANSPORTATION INSTITUTE, MARCH 1981.
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
- FOR EROSION PROTECTION SEE STANDARD B19.



*** NOTE:**
 WHERE L0 OR L1 EXCEEDS THE FOLLOWING LENGTH, THE PIPE RUNNER SHALL BE STRENGTHENED OVER THE MIDSPAN AS SHOWN.
 PIPE LENGTH 12'-8"
 3"Ø, SCH. 40



S = DESIGN SPAN
 H = DESIGN HEIGHT



** DOWEL BARS EXTENDING INTO THE CONCRETE BOX CULVERT ARE INCLUDED IN THE QUANTITIES

APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009



DATE	REVISIONS
6-1-2009	REVISED NOTES
3-1-2010	REVISED EROSION PROTECTION AND NOTES


SAFETY END TREATMENT FOR SINGLE CULVERTS
 0° SKEW 1:4 SLOPE H ≤ 4'
 STANDARD B13-02

CULVERT SIZE	TABLE OF DIMENSIONS								TOTAL QUANTITIES ONE END				PIPE RUNNERS FOR ONE END - SIZE 3" DIA.			
									CONC.	RE-BAR	PIPE RUNNER	RIPRAP HAND-LAID	HEADWALL PIPE		WINGWALL PIPE	
	S x H	L	N	V	W	TA	X	Y	CU. YD.	LBS.	FT.	SO. YD.	NO.	LO	NO.	LI
3 x 2	10'-10"	11'-2"	7"	8'-5"	6"	0'-3"	--	2.8	346	22.16	5.1	2	11'-1"	0	--	
3 x 3	14'-10"	15'-3/2"	7"	10'-5"	6"	1'-6"	10'-10"	4.4	489	37.50	6.5	1	15'-2"	2	11'-2"	
4 x 2	10'-10"	11'-2"	7"	9'-5"	6"	0'-9"	--	3.0	372	22.16	5.3	2	11'-1"	0	--	
4 x 3	14'-10"	15'-3/2"	7"	11'-5"	6"	2'-0"	12'-10"	4.7	521	41.50	6.7	1	15'-2"	2	13'-2"	
4 x 4	18'-10"	19'-5"	7"	13'-5"	6"	0'-9"	11'-10"	6.7	727	63.00	8.1	2	19'-4"	2	12'-2"	
5 x 2	10'-10"	11'-2"	7"	10'-5"	6"	1'-3"	5'-10"	3.2	397	34.16	5.5	2	11'-1"	2	6'-0"	
5 x 3	14'-10"	15'-3/2"	7"	12'-5"	6"	1'-3"	9'-10"	4.9	554	50.50	6.9	2	15'-2"	2	10'-1"	
5 x 4	18'-10"	19'-5"	7"	14'-5"	6"	1'-3"	13'-10"	7.0	765	67.17	8.3	2	19'-4"	2	14'-3"	
6 x 3	14'-10"	15'-3/2"	7"	13'-5"	6"	1'-9"	11'-10"	5.1	586	54.67	7.0	2	15'-2"	2	12'-2"	
6 x 4	18'-10"	19'-5"	7"	15'-5"	6"	0'-6"	10'-10"	7.2	803	80.33	8.5	3	19'-4"	2	11'-2"	
7 x 3	14'-10"	15'-3/2"	7"	14'-5"	6 1/2"	2'-3"	13'-10"	5.6	618	58.83	7.2	2	15'-2"	2	14'-3"	
7 x 4	18'-10"	19'-5"	7"	16'-5"	6 1/2"	1'-0"	12'-10"	7.8	839	84.33	8.6	3	19'-4"	2	13'-2"	
8 x 4	18'-10"	19'-5"	7"	17'-5"	7"	0'-3"	9'-10"	8.4	877	97.50	8.8	4	19'-4"	2	10'-1"	

PIPE ARCH AND ELLIPTICAL PIPE CULVERTS

FOR PIPE ARCH OR ELLIPTICAL PIPE CULVERTS SELECT APPROPRIATE "S" & "H" FROM SIZES SHOWN. ADD THE FOLLOWING ADDITIONAL BARS:

- (a) 1 ADDITIONAL Y BAR
- (b) #4 - T1 BARS @ APPROX. 12" CTS. (NO. = S + 2)




T1 BARS

THE WEIGHT OF THE ADDITIONAL BARS AND THE ADDITIONAL QUANTITY OF CONCRETE IN THE HEADWALL SHALL BE ADDED TO THE QUANTITIES SHOWN.

CULVERT SIZE	TABLE OF REINFORCING STEEL FOR ONE END																															
	DOWEL H #4 @ 12"		DOWEL J #6		BARS P #4 @ 12"		BARS P1 #4 @ 12"			BARS Q #4 @ 12"						BARS R 3-#4	BARS S 4-#4	BARS U #4 @ 12"			BARS V #4 @ 12"			4 BARS W		BARS Y 8-#5	BARS T 8-#5					
	NO.	LENGTH.	NO.	LENGTH.	NO.	LENGTH.	NO.	C1	C2	LENGTH.	NO.	C3	C4	C5	C6	LENGTH.	LENGTH.	LENGTH.	NO.	C7	C8	LENGTH.	NO.	C9	C10	LENGTH.	SIZE	LENGTH.	LENGTH.	LENGTH.		
3 x 2	6	2'-6"	4	4'-0"	4	13'-9"	2	8'-4"	4'-4"	17'-10"	5	8'-8"	4'-2"	6'-2"	6'-8"	12'-10"	8'-9"	11'-6"	2	8'-7"	4'-5"	13'-0"	10	2'-9"	6"	6'-3"	#5	10'-4"	3'-8"	3'-2"		
3 x 3	8	2'-6"	4	4'-0"	4	17'-9"	3	12'-4"	4'-4"	21'-10"	7	10'-8"	4'-2"	7'-2"	7'-8"	14'-10"	10'-9"	15'-7"	3	12'-8"	4'-5"	17'-1"	14	3'-9"	6"	7'-3"	#5	14'-6"	3'-8"	4'-2"		
4 x 2	6	2'-6"	4	4'-0"	5	13'-9"	2	8'-4"	4'-4"	17'-10"	5	9'-8"	5'-2"	7'-2"	7'-8"	14'-10"	9'-9"	11'-6"	2	8'-7"	4'-5"	13'-0"	10	2'-9"	6"	6'-3"	#5	10'-4"	4'-8"	3'-2"		
4 x 3	8	2'-6"	4	4'-0"	5	17'-9"	3	12'-4"	4'-4"	21'-10"	7	11'-8"	5'-2"	8'-2"	8'-8"	16'-10"	11'-9"	15'-7"	3	12'-8"	4'-5"	17'-1"	14	3'-9"	6"	7'-3"	#5	14'-6"	4'-8"	4'-2"		
4 x 4	10	2'-6"	4	4'-0"	5	21'-9"	4	16'-4"	4'-4"	25'-10"	9	13'-8"	5'-2"	9'-2"	9'-8"	18'-10"	13'-9"	19'-9"	4	16'-9"	4'-5"	21'-2"	18	4'-9"	6"	8'-3"	#6	18'-7"	4'-8"	5'-2"		
5 x 2	6	2'-6"	4	4'-0"	6	13'-9"	2	8'-4"	4'-4"	17'-10"	5	10'-8"	6'-2"	8'-2"	8'-8"	16'-10"	10'-9"	11'-6"	2	8'-7"	4'-5"	13'-0"	10	2'-9"	6"	6'-3"	#5	10'-4"	5'-8"	3'-2"		
5 x 3	8	2'-6"	4	4'-0"	6	17'-9"	3	12'-4"	4'-4"	21'-10"	7	12'-8"	6'-2"	9'-2"	9'-8"	18'-10"	13'-9"	15'-7"	3	12'-8"	4'-5"	17'-1"	14	3'-9"	6"	7'-3"	#5	14'-6"	5'-8"	4'-2"		
5 x 4	10	2'-6"	4	4'-0"	6	21'-9"	4	16'-4"	4'-4"	25'-10"	9	14'-8"	6'-2"	10'-2"	10'-8"	20'-10"	15'-9"	19'-9"	4	16'-9"	4'-5"	21'-2"	18	4'-9"	6"	8'-3"	#6	18'-7"	5'-8"	5'-2"		
6 x 3	8	2'-6"	4	4'-0"	7	17'-9"	3	12'-4"	4'-4"	21'-10"	7	13'-8"	7'-2"	10'-2"	10'-8"	20'-10"	14'-9"	15'-7"	3	12'-8"	4'-5"	17'-1"	14	3'-9"	6"	7'-3"	#5	14'-6"	6'-8"	4'-2"		
6 x 4	10	2'-6"	4	4'-0"	7	21'-9"	4	16'-4"	4'-4"	25'-10"	9	15'-8"	7'-2"	11'-2"	11'-8"	22'-10"	16'-9"	19'-9"	4	16'-9"	4'-5"	21'-2"	18	4'-9"	6"	8'-3"	#6	18'-7"	6'-8"	5'-2"		
7 x 3	8	2'-6"	4	4'-0"	8	17'-9"	3	12'-4"	4'-4"	21'-10"	7	14'-8"	8'-2"	11'-2"	11'-8"	22'-10"	15'-9"	15'-7"	3	12'-8"	4'-5"	17'-1"	14	3'-9"	6"	7'-3"	#5	14'-6"	7'-8"	4'-2"		
7 x 4	10	2'-6"	4	4'-0"	8	21'-9"	4	16'-4"	4'-4"	25'-10"	9	16'-8"	8'-2"	12'-2"	12'-8"	24'-10"	17'-9"	19'-9"	4	16'-9"	4'-5"	21'-2"	18	4'-9"	6"	8'-3"	#6	18'-7"	7'-8"	5'-2"		
8 x 4	10	2'-6"	4	4'-0"	9	21'-9"	4	16'-4"	4'-4"	25'-10"	9	17'-8"	9'-2"	13'-2"	13'-8"	26'-10"	18'-9"	19'-9"	4	16'-9"	4'-5"	21'-2"	18	4'-9"	6"	8'-3"	#6	18'-7"	8'-8"	5'-3"		

NOTE: REINFORCEMENT BARS BENDING DIMENSIONS ARE OUT TO OUT.








APPROVED..... DATE 6-1-2009...
 CHIEF ENGINEER

Illinois Tollway
 Open Roads for a Faster Future

SAFETY END TREATMENT FOR SINGLE CULVERTS
 0° SKEW 1:4 SLOPE H ≤ 4'




STANDARD B13-02



NOTE:
 BAR F & V TO BE FIELD CUT PER CUTTING DIAGRAM. PLACE BARS WITH DIMENSIONS C₂, C₆ BEGINNING AT HEADWALL & BARS WITH DIMENSIONS C₁, C₅ BEGINNING AT THE TOEWALL END.

NOTE:
 DOWEL BAR J & H NOT REQUIRED WITH EXISTING BOX CULVERTS PROVIDING THE REINFORCING FROM THE EXIST. BOX IS EXTENDED INTO THE NEW CONCRETE A MIN. OF 1'-3".


NOTE:
 PIPE O.D. IS THE PIPE RUNNER OUTSIDE DIAMETER. CONTRACTOR SHALL PROVIDE BARS AS NEEDED TO SUPPORT BAR W ON INSIDE FACE OF WINGWALL.



NOTE:
 * WHERE L₀ OR L₁ EXCEEDS THE FOLLOWING LENGTH THE PIPE RUNNER SHALL BE STRENGTHENED OVER MIDSPAN AS SHOWN.

PIPE	LENGTH
3"Ø, SCH. 40	12'-8"
3 1/2"Ø, SCH. 40	17'-3"
3 1/2"Ø, SCH. 80	22'-1"
4"Ø, SCH. 40	22'-6"
4"Ø, SCH. 80	29'-4"

- GENERAL NOTES:**
- ALL CONCRETE SHALL BE CLASS SI.
 - ALL EXPOSED CONCRETE EDGES SHALL HAVE A 3/4" x 45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW FINISHED GROUND LEVEL. COVER FROM THE FACE OF CONCRETE TO THE FACE OF REINFORCEMENT BARS SHALL BE 2", UNLESS OTHERWISE SHOWN.
 - CONCRETE QUANTITIES SHOWN ON SHEET 2 (OF 2) IN THIS SERIES ARE FOR REINFORCED CONCRETE BOX CULVERT SECTIONS AND ADDITIONAL CONCRETE REQUIRED IN HEADWALLS FOR PIPE OR ARCH CULVERT SECTIONS SHALL BE ADDED TO THESE QUANTITIES.
 - THIS STANDARD MAY BE USED FOR CULVERTS WITH SKEW OF 0° ± 7.5°, AS SHOWN PER CULVERT SKEW ORIENTATION ON THIS SHEET.
 - DESIGN: SAFETY PIPE RUNNERS ARE DESIGNED FOR A TRANSVERSING LOAD OF 1,800 POUNDS AT YIELD AS RECOMMENDED BY RESEARCH REPORT 280-1, SAFETY TREATMENT OF ROADSIDE CROSS DRAINAGE STRUCTURES, TEXAS TRANSPORTATION INSTITUTE, MARCH 1981.
 - ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
 - FOR EROSION PROTECTION SEE SHEET B19.



APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009


DATE	REVISIONS
6-1-2009	ADDED PIPE DIMENSION FORMULA REVISED NOTES
3-1-2010	REVISED EROSION PROTECTION AND NOTES

Illinois Tollway
Open Roads for a Faster Future


SAFETY END TREATMENT FOR SINGLE AND MULTIPLE CULVERTS 0° SKEW 1:4 SLOPE H ≤ 8'

STANDARD B14-02


TABLE OF DIMENSIONS						TABLE OF REINFORCING STEEL FOR 1 END																								
H	L	WF	WW	TF	N	BARS C 2 REOD.		BARS D 8-#4		BARS E #4		BARS F			DOWEL H #5 @ 12"		DOWEL J 4-#6		BARS K 2-#5		BARS U #4 @ 12"			BARS V #4 @ 12" CTS.				BARS W 4 REOD.		
						SIZE	LENGTH	LENGTH	NO.	LENGTH	SIZE	NO.	C ₁	C ₂	LENGTH	NO.	LENGTH	LENGTH	LENGTH	NO.	C ₃	C ₄	LENGTH	NO.	C ₅	C ₆	C ₇	LENGTH	SIZE	LENGTH
3	14'-4"	3"	7"	7"	14'-10 ¹ / ₈ "	#4	15'-2"	17'-2"	4	16'-8"	#4	15	2'-0"	2'-2"	9'-4"	6	3'-0"	4'-6"	4'-0"	3	12'-8"	4'-5"	17'-1"	14	9"	3'-10"	1'-0"	6'-7"	#5	14'-11"
4	18'-4"	9"	7"	8"	18'-11 ³ / ₄ "	#4	19'-4"	21'-4"	4	20'-10"	#4	19	2'-0"	2'-8"	9'-10"	8	3'-0"	4'-6"	4'-6"	4	16'-10"	4'-5"	21'-3"	18	10"	4'-11"	1'-0"	7'-9"	#6	19'-2"
5	22'-4"	1'-3"	7"	8"	23'-1 ¹ / ₂ "	#4	23'-6"	25'-6"	4	25'-0"	#4	23	2'-0"	3'-2"	10'-4"	10	3'-0"	4'-6"	5'-0"	5	20'-11"	4'-5"	25'-4"	22	10"	5'-11"	1'-0"	8'-9"	#6	23'-5"
6	26'-4"	1'-9"	7"	8 ¹ / ₂ "	27'-3 ¹ / ₈ "	#4	27'-7"	29'-4"	6	29'-1"	#5	27	2'-0"	3'-8"	10'-10"	12	3'-0"	4'-6"	5'-6"	6	25'-1"	4'-5"	29'-6"	26	10"	6'-11"	1'-0"	9'-9"	#6	27'-8"
7	30'-4"	2'-3"	7"	9"	31'-4 ¹ / ₈ "	#5	31'-9"	33'-9"	6	33'-3"	#5	31	2'-1"	4'-3"	11'-6"	14	3'-0"	4'-6"	6'-0"	7	29'-2"	4'-5"	33'-7"	30	11"	8'-0"	1'-0"	10'-11"	#6	31'-11"
8	34'-4"	2'-9"	8"	9 ¹ / ₂ "	35'-6 ¹ / ₂ "	#5	35'-10"	37'-10"	6	37'-4"	#6	35	2'-2"	4'-10"	12'-2"	16	3'-0"	4'-6"	6'-6"	8	33'-4"	4'-5"	37'-9"	34	11"	9'-0"	1'-1"	12'-1"	#6	36'-2"



PIPE RUNNERS FOR ONE END							
H	SIZE (DIA)	SCHEDULE	NO WINGWALL PIPES	L ₁	L ₂	L ₃	LENGTH (FT.)
3'	3"	40	2	9'-11"	--	--	19.84
4'	3"	40	2	14'-0"	--	--	28.00
5'	3 ¹ / ₂ "	40	4	18'-1"	8'-6"	--	53.16
6'	3 ¹ / ₂ "	80	4	22'-3"	12'-7"	--	69.66
7'	4"	40	6	26'-4"	16'-9"	7'-2"	100.50
8'	4"	80	6	30'-6"	20'-10"	11'-7"	125.82




BARS D




FOR BOX CULVERTS

DOWEL H




FOR PIPE CULVERTS

DOWEL J



FOR PIPE CULVERTS




DOWEL L


TABLE OF DIMENSIONS			TABLE OF REINFORCING STEEL FOR MINIMUM "S"								HEADWALL PIPE RUNNERS FOR MINIMUM "S"				QUANTITIES FOR MIN. "S" (SINGLE PIPE OR CONC. BOX CULVERT)				INCREASE IN QUANTITIES FOR 1' INCREASE IN "S"								
H	S	W (4)	BARS Y 12-#5		BARS Z #4 @ 12"		BARS R 6-#5		BARS S #4 @ 12"		BARS T #4 @ 12"		BARS P 8-#5		SIZE (DIA.)	SCHEDULE	NO.	L ₀	LENGTH (FT.)	CONCRETE CU. YD.	REIN. BARS LBS.	RIPRAP DUMPED SO. YD.	RIPRAP HAND-LAID SO. YD.	CONCRETE CU. YD.	REIN. BARS LBS.	RIPRAP DUMPED SO. YD.	RIPRAP HAND-LAID SO. YD.
			LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.													
3	≧ 9'	16'-8"	9'-10"	9	5'-4"	15'-10"	16	6'-10"	9	3'-0"	6'-8"	3"	40	4	14'-9"	59.00	6.8	863	16.6	7.4	0.19	29	1.50	0.17			
4	≧ 9'	18'-9"	9'-10"	9	5'-4"	17'-11"	18	6'-10"	9	3'-0"	7'-8"	3"	40	4	18'-10"	75.33	9.1	1078	23.6	8.8	0.19	29	1.94	0.17			
5	≧ 5'	16'-11"	5'-10"	5	5'-4"	16'-1"	16	6'-10"	5	3'-0"	8'-8"	3 ¹ / ₂ "	40	2	23'-0"	46.00	11.1	1163	22.0	9.6	0.19	29	2.39	0.17			
6	≧ 6'	20'-1"	6'-10"	6	5'-4"	19'-3"	19	6'-10"	6	3'-0"	9'-8"	3 ¹ / ₂ "	80	3	27'-2"	81.51	13.9	1551	32.0	11.2	0.19	29	2.83	0.17			
7	≧ 7'	23'-3"	7'-10"	7	5'-4"	22'-5"	22	6'-10"	7	3'-0"	10'-8"	4"	40	3	31'-3"	93.75	17.7	1869	43.8	12.7	0.19	29	3.28	0.17			
8	≧ 8'	26'-4"	9'-10"	8	5'-4"	25'-6"	25	6'-10"	8	3'-0"	11'-8"	4"	80	4	35'-4"	141.33	22.4	2388	57.4	14.3	0.19	29	3.72	0.17			

NUMBER OF HDWL PIPE RUNNERS FOR 1 END			
S	No	S	No
10'	4	23'	10
11'	5	24'	10
12'	5	25'	10
13'	6	26'	11
14'	6	27'	11
15'	6	28'	12
16'	7	29'	12
17'	7	30'	12
18'	8	31'	13
19'	8	32'	13
20'	8	33'	14
21'	9	34'	14
22'	9	35'	14


NOTE:
REINFORCEMENT BARS BENDING DIMENSIONS ARE OUT TO OUT.




BARS F



BARS V




BARS S




FOR BOX CULVERTS

BARS T



FOR PIPE CULVERTS



BARS Z






- NOTES FOR TABLE OF DIMENSIONS:
- THE NUMBER OF BARS S, T AND Z SHALL BE INCREASED BY 1 FOR EACH 1 FOOT OF INCREASE IN DIMENSION "S".
 - THE LENGTH OF BARS R AND Y SHALL BE INCREASED BY 1 FOOT FOR EACH 1 FOOT OF INCREASE IN DIMENSION "S".
 - THE NUMBER OF BARS P SHOWN ARE FOR SINGLE SPAN PIPES OR BOX CULVERTS. THIS NUMBER SHALL BE INCREASED BY 4 FOR EACH MULTIPLE OF PIPE OR BOX ADDED.
 - THIS DIMENSION SHALL BE INCREASED BY 1 FOOT FOR EACH 1 FOOT INCREASE IN DIMENSION "S".
 - THE LENGTH OF THIS BAR INCLUDES ONE 1'-6" MINIMUM LAP.

APPROVED..... DATE 6-1-2009...
Paul Kovacs
CHIEF ENGINEER



SAFETY END TREATMENT FOR
SINGLE AND MULTIPLE CULVERTS
0° SKEW 1:4 SLOPE H ≤ 8'

STANDARD B14-02









NOTES:
 BARS O, V, AND V₁ ARE TO BE FIELD CUT PER CUTTING DIAGRAM. PLACE BARS WITH DIMENSIONS C₂ - C₃, C₉ - C₁₂ BEGINNING AT HEADWALL AND BARS WITH DIMENSIONS C₁ - C₄, C₁₀ - C₁₁ BEGINNING AT THE TOEWALL END

NOTE:
 BARS P₁ ARE TO BE FIELD CUT PER CUTTING DIAGRAM PLACE BARS WITH DIMENSIONS C₆ - C₇ BEGINNING AT TOEWALL END OF 30° WING AND BARS WITH DIMENSIONS C₅ - C₈ BEGINNING PARALLEL THE BARS P.

NOTE:
 DOWEL BAR J & H NOT REQUIRED WITH EXISTING BOX CULVERTS PROVIDING THE REINFORCING FROM THE EXIST. BOX IS EXTENDED INTO THE NEW CONCRETE A MIN. OF 1'-3".


NOTE:
 PIPE O.D. IS THE PIPE RUNNER OUTSIDE DIAMETER



- GENERAL NOTES:**
- ALL CONCRETE SHALL BE CLASS SI.
 - ALL EXPOSED CONCRETE EDGES SHALL HAVE A 3/4" x 45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW FINISHED GROUND LEVEL. COVER FROM THE FACE OF CONCRETE TO THE FACE OF REINFORCEMENT BARS SHALL BE 2", UNLESS OTHERWISE SHOWN.
 - CONCRETE QUANTITIES SHOWN ON SHEET 2 (OF 2) IN THIS SERIES ARE FOR REINFORCED CONCRETE BOX CULVERT SECTIONS AND ADDITIONAL CONCRETE REQUIRED IN HEADWALLS FOR PIPE OR ARCH CULVERT SECTIONS SHALL BE ADDED TO THESE QUANTITIES.
 - THIS STANDARD MAY BE USED FOR CULVERTS WITH SKEW OF 15° ± 7.5°, AS SHOWN PER CULVERT SKEW ORIENTATION ON THIS SHEET.
 - DESIGN: SAFETY PIPE RUNNERS ARE DESIGNED FOR A TRANSVERSING LOAD OF 1,800 POUNDS AT YIELD AS RECOMMENDED BY RESEARCH REPORT 280-1, SAFETY TREATMENT OF ROADSIDE CROSS DRAINAGE STRUCTURES, TEXAS TRANSPORTATION INSTITUTE, MARCH 1981.
 - ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
 - FOR EROSION PROTECTION SEE STANDARD B19.

NOTE:
 * WHERE L₀ OR L₃ EXCEEDS THE FOLLOWING LENGTH, THE PIPE RUNNER SHALL BE STRENGTHENED OVER THE MIDSPAN AS SHOWN.

PIPE	LENGTH
3"Ø SCH 40	12'-8"
3"Ø SCH 80	15'-4"



APPROVED.....
 CHIEF ENGINEER
 DATE 6-1-2009..

DATE	REVISIONS
6-1-2009	REVISED NOTES
3-1-2010	MODIFIED CULVERT SKEW DETAIL, REVISED EROSION PROTECTION AND NOTES

Illinois Tollway
 Open Roads for a Faster Future

SAFETY END TREATMENT FOR SINGLE CULVERTS 15° SKEW 1:4 SLOPE H ≤ 4'


STANDARD B15-02

CULVERT SIZE (FEET)	TABLE OF DIMENSIONS								PIPE RUNNERS FOR ONE END SIZE 3" DIA.																TABLE OF REINFORCING STEEL FOR ONE END											
	S X H	L	NR	V	W ₁	W ₂	WR	TA	HEADWALL PIPE				WINGWALL PIPE - ONE PER EACH LENGTH SHOWN				DOWELS H #4 @ 12"				DOWELS J 2-#6 EACH WALL				BARS P #4 - EQUALLY SPACED				BARS P1 #4 @ 12"							
									SCH.	NO.	LENGTH	L ₀	L ₁	L ₂	L ₃	L ₄	NO.	LENGTH	NO.	LENGTH	LENGTH	LENGTH	NO.	LENGTH	NO.	C ₅	C ₆	C ₇	C ₈	LENGTH	NO.	C ₉	C ₁₀	C ₁₁	C ₁₂	LENGTH
3 x 2	10'-10"	12'-6 1/8"	7"	3'-1 1/4"	9'-4 1/4"	6'-3"	6"	40	2	11'-5"	6'-3"	-	7'-0"	-	3	2'-6"	3	2'-6"	4'-0"	4'-0"	4	13'-9"	3	10'-2"	1'-6"	5'-0"	6'-8"	16'-10"								
3 x 3	14'-10"	17'-1 1/2"	7"	3'-1 1/4"	11'-8"	8'-6 3/4"	6"	40	2	15'-8"	10'-6"	-	11'-3"	-	4	2'-6"	4	2'-6"	4'-0"	4'-0"	4	17'-9"	4	14'-2"	2'-0"	7'-3"	8'-11"	21'-4"								
4 x 2	10'-10"	12'-6 1/8"	7"	4'-1 3/4"	10'-4 3/4"	6'-3"	6"	40	2	11'-5"	6'-3"	-	7'-0"	-	3	2'-6"	3	2'-6"	4'-0"	4'-0"	5	13'-9"	3	10'-2"	1'-6"	5'-0"	6'-8"	16'-10"								
4 x 3	14'-10"	17'-1 1/2"	7"	4'-1 3/4"	12'-8 1/2"	8'-6 3/4"	6"	40	2	15'-8"	10'-6"	-	11'-3"	-	4	2'-6"	4	2'-6"	4'-0"	4'-0"	5	17'-9"	4	14'-2"	2'-0"	7'-3"	8'-11"	21'-4"								
4 x 4	18'-10"	21'-9"	7"	4'-1 3/4"	15'-0 1/4"	10'-10 1/2"	6"	80	2	19'-11"	14'-9"	4'-6"	15'-6"	6'-7"	5	2'-6"	5	2'-6"	4'-0"	4'-0"	5	21'-9"	5	18'-2"	2'-5"	9'-5"	11'-2"	25'-9"								
5 x 2	10'-10"	12'-6 1/8"	7"	5'-2 1/8"	11'-5 1/8"	6'-3"	6"	40	2	11'-5"	6'-3"	-	7'-0"	-	3	2'-6"	3	2'-6"	4'-0"	4'-0"	6	13'-9"	3	10'-2"	1'-6"	5'-0"	6'-8"	16'-10"								
5 x 3	14'-10"	17'-1 1/2"	7"	5'-2 1/8"	13'-8 7/8"	8'-6 3/4"	6"	40	2	15'-8"	10'-6"	-	11'-3"	-	4	2'-6"	4	2'-6"	4'-0"	4'-0"	6	17'-9"	4	14'-2"	2'-0"	7'-3"	8'-11"	21'-4"								
5 x 4	18'-10"	21'-9"	7"	5'-2 1/8"	16'-0 3/8"	10'-10 1/2"	6"	80	2	19'-11"	14'-9"	4'-6"	15'-6"	6'-7"	5	2'-6"	5	2'-6"	4'-0"	4'-0"	6	21'-9"	5	18'-2"	2'-5"	9'-5"	11'-2"	25'-9"								
6 x 3	14'-10"	17'-1 1/2"	7"	6'-2 1/2"	14'-9 1/4"	8'-6 3/4"	6"	40	3	15'-8"	10'-6"	-	11'-3"	-	4	2'-6"	4	2'-6"	4'-0"	4'-0"	7	17'-9"	4	14'-2"	2'-0"	7'-3"	8'-11"	21'-4"								
6 x 4	18'-10"	21'-9"	7"	6'-2 1/2"	17'-1"	10'-10 1/2"	6"	80	3	19'-11"	14'-9"	4'-6"	15'-6"	6'-7"	5	2'-6"	5	2'-6"	4'-0"	4'-0"	7	21'-9"	5	18'-2"	2'-5"	9'-5"	11'-2"	25'-9"								
7 x 3	14'-10"	17'-1 1/2"	7"	7'-3"	15'-9 3/4"	8'-6 3/4"	6 1/2"	40	3	15'-8"	10'-6"	-	11'-3"	-	4	2'-6"	4	2'-6"	4'-0"	4'-0"	8	17'-9"	4	14'-2"	2'-0"	7'-3"	8'-11"	21'-4"								
7 x 4	18'-10"	21'-9"	7"	7'-3"	18'-1 1/2"	10'-10 1/2"	6 1/2"	80	3	19'-11"	14'-9"	4'-6"	15'-6"	6'-7"	5	2'-6"	5	2'-6"	4'-0"	4'-0"	8	21'-9"	5	18'-2"	2'-5"	9'-5"	11'-2"	25'-9"								
8 x 4	18'-10"	21'-9"	7"	8'-3 3/8"	19'-1 1/8"	10'-10 1/2"	7"	80	4	19'-11"	14'-9"	4'-6"	15'-6"	6'-7"	5	2'-6"	5	2'-6"	4'-0"	4'-0"	9	21'-9"	5	18'-2"	2'-5"	9'-5"	11'-2"	25'-9"								

CULVERT SIZE (FEET)	TABLE OF REINFORCING STEEL FOR ONE END																															
	BARS O #4 @ 12"				BARS R 3-#4	BARS S 30° WALL 2-#4	BARS S1 0° WALL 2-#4	BARS T 8-#5	BARS U-ONE PER EACH LENGTH SHOWN #4 @ 12"								BARS U1 ONE PER EACH LENGTH SHOWN #4 @ 12"				BARS V #4 - EQUALLY SPACED								BARS V1 #4 - EQUALLY SPACED			
	S X H	NO.	C ₁	C ₂					C ₃	C ₄	LENGTH	LENGTH	LENGTH	LENGTH	LENGTH	C ₅	C ₆	C ₇	C ₈	C ₅	C ₆	C ₇	C ₈	NO.	C ₉	C ₁₀	C ₁₁	C ₁₂	LENGTH	NO.	C ₉	C ₁₀
3 x 2	5	9'-7"	4'-4"	6'-8"	7'-3"	13'-11"	9'-10"	12'-8"	11'-4"	3'-3"	5'-0"	9'-8"	-	-	4'-4"	8'-4"	-	-	6	2'-9"	6"	1'-6"	1'-9"	6'-3"	5	2'-9"	6"	1'-6"	1'-9"	6'-3"		
3 x 3	7	11'-10"	4'-4"	7'-9"	8'-5"	16'-2"	12'-2"	17'-4"	15'-4"	4'-3"	5'-0"	9'-8"	14'-3"	-	4'-4"	8'-4"	12'-4"	-	8	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"		
4 x 2	5	10'-7"	5'-5"	7'-8"	8'-4"	16'-0"	10'-10"	12'-8"	11'-4"	3'-3"	5'-0"	9'-8"	14'-3"	-	4'-4"	8'-4"	-	-	6	2'-9"	6"	1'-6"	1'-9"	6'-3"	5	2'-9"	6"	1'-6"	1'-9"	6'-3"		
4 x 3	7	12'-11"	5'-5"	8'-10"	9'-6"	18'-4"	13'-2"	17'-4"	15'-4"	4'-3"	5'-0"	9'-8"	-	-	4'-4"	8'-4"	12'-4"	-	8	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"		
4 x 4	9	15'-2"	5'-5"	10'-0"	10'-7"	20'-7"	15'-6"	21'-11"	19'-4"	5'-3"	5'-0"	9'-8"	14'-3"	18'-10"	4'-4"	8'-4"	12'-4"	16'-4"	10	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"		
5 x 2	5	11'-8"	6'-5"	8'-7"	9'-3"	18'-1"	11'-11"	12'-8"	11'-4"	3'-3"	5'-0"	9'-8"	-	-	4'-4"	8'-4"	-	-	6	2'-9"	6"	1'-6"	1'-9"	6'-3"	5	2'-9"	6"	1'-6"	1'-9"	6'-3"		
5 x 3	7	13'-11"	6'-5"	9'-10"	10'-6"	20'-4"	14'-2"	17'-4"	15'-4"	4'-3"	5'-0"	9'-8"	14'-3"	-	4'-4"	8'-4"	12'-4"	-	8	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"		
5 x 4	9	16'-3"	6'-5"	11'-0"	11'-8"	22'-8"	16'-6"	21'-11"	19'-4"	5'-3"	5'-0"	9'-8"	14'-3"	18'-10"	4'-4"	8'-4"	12'-4"	16'-4"	10	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"		
6 x 3	7	14'-11"	7'-5"	10'-10"	11'-6"	22'-4"	15'-3"	17'-4"	15'-4"	4'-3"	5'-0"	9'-8"	14'-3"	-	4'-4"	8'-4"	12'-4"	-	8	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"		
6 x 4	9	17'-3"	7'-5"	12'-0"	12'-8"	24'-8"	17'-6"	21'-11"	19'-4"	5'-3"	5'-0"	9'-8"	14'-3"	18'-10"	4'-4"	8'-4"	12'-4"	16'-4"	10	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"		
7 x 3	7	16'-0"	8'-6"	11'-11"	12'-1"	24'-6"	16'-3"	17'-4"	15'-4"	4'-3"	5'-0"	9'-8"	14'-3"	-	4'-4"	8'-4"	12'-4"	-	8	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"		
7 x 4	9	18'-4"	8'-6"	13'-1"	13'-9"	26'-10"	18'-7"	21'-11"	19'-4"	5'-3"	5'-0"	9'-8"	14'-3"	18'-10"	4'-4"	8'-4"	12'-4"	16'-4"	10	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"		
8 x 4	9	19'-4"	9'-6"	14'-1"	14'-9"	28'-10"	19'-7"	21'-11"	19'-4"	5'-3"	5'-0"	9'-8"	14'-3"	18'-10"	4'-4"	8'-4"	12'-4"	16'-4"	10	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"		


CULVERT SIZE (FEET)	TABLE OF REINFORCING STEEL FOR ONE END				
	2 BARS W		2 BARS W ₁		BARS Y 8-#5
	30° WALL	0° WALL	30° WALL	0° WALL	
3 x 2	#5	11'-6"	#5	10'-4"	3'-11"
3 x 3	#5	16'-2"	#5	14'-5"	3'-11"
4 x 2	#5	11'-6"	#5	10'-4"	4'-11"
4 x 3	#5	16'-2"	#5	14'-5"	4'-11"
4 x 4	#6	20'-11"	#6	18'-7"	4'-11"
5 x 2	#5	11'-6"	#5	10'-4"	6'-0"
5 x 3	#5	16'-2"	#5	14'-5"	6'-0"
5 x 4	#6	20'-11"	#6	18'-7"	6'-0"
6 x 3	#5	16'-2"	#5	14'-5"	7'-0"
6 x 4	#6	20'-11"	#6	18'-7"	7'-0"
7 x 3	#5	16'-2"	#5	14'-5"	8'-1"
7 x 4	#6	20'-11"	#6	18'-7"	8'-1"
8 x 4	#6	20'-11"	#6	18'-7"	9'-1"

TOTAL QUANTITIES ONE END			
CONC.	RE-BARS	PIPE RUNNERS	RIPRAP HAND-LAID
CUL. YD.	LB.	FT.	SQ. YD.
3.1	373	36.09	5.3
4.7	526	53.08	6.8
3.4	399	36.09	5.5
5.1	558	53.08	7.0
7.2	779	81.17	8.5
3.7	426	36.09	5.7
5.5	589	53.08	7.1
7.6	816	81.17	8.6
5.9	621	53.08	7.3
8.1	853	81.17	8.8
6.5	655	53.08	7.5
8.9	892	81.17	9.0
9.8	929	81.17	9.1











NOTE:
REINFORCEMENT BARS BENDING DIMENSIONS ARE OUT TO OUT.

PIPE ARCH AND ELLIPTICAL PIPE CULVERTS



FOR PIPE OR ELLIPTICAL PIPE CULVERTS SELECT APPROPRIATE "S" & "H" FROM SIZES SHOWN. ADD THE FOLLOWING ADDITIONAL BARS:
(a) 1 ADDITIONAL Y BAR
(b) #4-T1 BARS @ APPROX. 12" CTS. (NO. = S + 2)

THE WEIGHT OF THE ADDITIONAL BARS AND THE ADDITIONAL QUANTITY OF CONCRETE IN THE HEADWALL SHALL BE ADDED TO THE QUANTITIES SHOWN.








APPROVED..... DATE 6-1-2009.....
CHIEF ENGINEER





Illinois Tollway
Open Roads for a Faster Future

SAFETY END TREATMENT FOR SINGLE CULVERTS
15° SKEW 1:4 SLOPE H ≤ 4'

STANDARD B15-02



FOR PIPE AND PIPE-ARCH CULVERTS



FOR BOX CULVERTS

GENERAL NOTES:

- ALL CONCRETE SHALL BE CLASS SI.
- ALL EXPOSED CONCRETE EDGES SHALL HAVE A 3/4" x 45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW FINISHED GROUND LEVEL. COVER FROM THE FACE OF CONCRETE TO THE FACE OF REINFORCEMENT BARS SHALL BE 2", UNLESS OTHERWISE SHOWN.
- CONCRETE QUANTITIES SHOWN ON SHEET 2 (OF 2) IN THIS SERIES ARE FOR REINFORCED CONCRETE BOX CULVERT SECTIONS AND ADDITIONAL CONCRETE REQUIRED IN HEADWALLS FOR PIPE OR ARCH CULVERT SECTIONS SHALL BE ADDED TO THESE QUANTITIES.
- THIS STANDARD MAY BE USED FOR CULVERTS WITH SKEW OF 15° ± 7.5%, AS SHOWN PER CULVERT SKEW ORIENTATION ON THIS SHEET.
- DESIGN: SAFETY PIPE RUNNERS ARE DESIGNED FOR A TRANSVERSING LOAD OF 1,800 POUNDS AT YIELD AS RECOMMENDED BY RESEARCH REPORT 280-1. SAFETY TREATMENT OF ROADSIDE CROSS DRAINAGE STRUCTURES, TEXAS TRANSPORTATION INSTITUTE, MARCH 1981.
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
- FOR EROSION PROTECTION SEE STANDARD B19.

*** NOTE:**
 WHERE L₀, L₁ OR L₄ EXCEEDS THE FOLLOWING LENGTH THE PIPE RUNNER SHALL BE STRENGTHENED OVER MIDSPAN AS SHOWN.

PIPE	LENGTH
3"Ø, SCH. 40	12'-8"
3 1/2"Ø, SCH. 40	17'-3"
3 1/2"Ø, SCH. 80	22'-1"
4"Ø, SCH. 40	22'-6"
4"Ø, SCH. 80	29'-4"

APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009



DATE	REVISIONS
6-1-2009	REVISED NOTES
3-1-2010	MODIFIED CULVERT SKEW DETAIL, REVISED EROSION PROTECTION AND NOTES

SAFETY END TREATMENT FOR SINGLE AND MULTIPLE CULVERTS 15° SKEW 1:4 SLOPE H ≤ 8'

STANDARD B16-02

TABLE OF DIMENSIONS										
H	S	L	NL	NR	WW	W ₁ ④	W ₂ ④	WR	WF	TF
3'	9'	14'-4"	14'-4"	16'-6 1/2"	7"	9'-3 3/4"	17'-7"	8'-3 1/4"	3"	7"
4'	9'	18'-4"	18'-4"	21'-2"	7"	9'-3 3/4"	19'-10 1/4"	10'-7"	9"	8"
5'	5'	22'-4"	22'-4"	25'-9 1/2"	7"	5'-2"	18'-0 3/4"	12'-10 3/4"	1'-3"	8"
6'	6'	26'-4"	26'-4"	30'-4 1/8"	7"	6'-2 1/2"	21'-5"	15'-2 1/2"	1'-9"	8 1/2"
7'	7'	30'-4"	30'-4"	35'-0 1/4"	7"	7'-3"	24'-9"	17'-6"	2'-3"	9"
8'	8'	34'-4"	34'-4"	39'-7 1/4"	8"	8'-3 1/2"	28'-1 1/4"	19'-9 3/4"	2'-9"	9 1/2"

PIPE RUNNERS FOR ONE END													
H	SIZE (DIA.)	SCHEDULE	WINGWALL PIPES - ONE PER EACH LENGTH SHOWN						HEADWALL PIPE				
			0° WALL			30° WALL			S	NO.	Lo	TOTAL LENGTH	
			L ₁	L ₂	L ₃	L ₄	L ₅	L ₆					
3'	3"	40	10'-0"	-	-	10'-8"	-	-	9'	4	15'-1"	81.00	
4'	3"	40	14'-3"	-	-	14'-11"	-	-	9'	4	19'-4"	112.50	
5'	3 1/2"	40	18'-6"	8'-3"	-	19'-2"	10'-5"	-	5'	2	23'-7"	103.33	
6'	3 1/2"	80	22'-9"	12'-6"	-	23'-5"	14'-8"	5'-9"	6'	3	28'-0"	162.25	
7'	4"	40	27'-0"	16'-9"	6'-7"	27'-8"	18'-11"	10'-0"	7'	3	32'-3"	202.67	
8'	4"	80	31'-3"	21'-0"	10'-10"	31'-11"	23'-2"	14'-3"	8'	4	36'-6"	277.25	




TABLE OF REINFORCING STEEL FOR ONE END										
H	SIZE	1-BAR C 30° WALL		1-BAR C1 0° WALL		BAR D 4-#4 30° WALL	BAR D1 4-#4 0° WALL	#4-BARS E 30° WALL ⑥		#4-BARS E1 0° WALL ⑥
		LENGTH	LENGTH	LENGTH	LENGTH	NO.	LENGTH	NO.	LENGTH	
3'	#4	16'-11"	#4 14'-8"	18'-10"	16'-7"	2	16'-0"	2	16'-2"	
4'	#4	21'-7"	#4 18'-8"	23'-6"	20'-7"	2	20'-4"	2	20'-2"	
5'	#4	22'-2"	#4 22'-8"	24'-1"	24'-7"	2	24'-8"	2	24'-2"	
6'	#4	30'-9"	#4 26'-8"	32'-8"	28'-7"	3	29'-0"	3	28'-2"	
7'	#5	35'-5"	#5 30'-8"	37'-4"	32'-7"	3	33'-4"	3	32'-2"	
8'	#5	40'-0"	#5 34'-8"	41'-11"	36'-7"	3	37'-8"	3	36'-2"	

TOTAL QUANTITIES ONE END MINIMUM "S"						INCREASE IN QUANTITIES FOR 1' INCREASE IN "S"					
H	S	CONC. CU. YD.	RE-BARS LBS.	RIPRAP DUMPED SQ. YD.	RIPRAP HAND-LAID SQ. YD.	CONC. CU. YD.	RE-BARS LBS.	RIPRAP DUMPED SQ. YD.	RIPRAP HAND-LAID SQ. YD.		
3'	9'	7.4	904	17.4	7.6	0.20	30	1.56	0.17		
4'	9'	9.9	1132	24.8	9.1	0.20	30	2.03	0.17		
5'	5'	11.7	1179	23.3	9.9	0.20	30	2.49	0.17		
6'	6'	15.0	1587	33.9	11.6	0.20	30	2.95	0.17		
7'	7'	18.7	1909	46.4	13.2	0.20	30	3.41	0.17		
8'	8'	24.0	2441	60.8	14.9	0.20	30	3.88	0.17		

TABLE OF REINFORCING STEEL FOR ONE END																													
BARS F EQUALLY SPACED 30° WALL						BARS F1 EQUALLY SPACED 0° WALL						DOWELS H #5 @ 12" 30° WALL	DOWELS H1 #5 @ 12" 0° WALL	DOWELS J 4-#6 ⑤	1-BAR K 30° WALL		1-BAR K1 0° WALL		2-BARS W 30° WALL		2-BARS W1 0° WALL								
H	SIZE	NO.	C ₁	C ₂	C ₃	C ₄	LENGTH	SIZE	NO.	C ₁	C ₂	C ₃	C ₄	LENGTH	NO.	LENGTH	NO.	LENGTH	LENGTH	SIZE	C ₅	LENGTH	SIZE	C ₆	LENGTH	SIZE	LENGTH	SIZE	LENGTH
3'	#4	7	1'-11"	2'-1"	2'-0"	2'-0"	9'-2"	#4	7	1'-11"	2'-1"	2'-0"	2'-0"	9'-2"	3	3'-0"	3	3'-0"	4'-6"	#5	2'-4"	3'-10"	#5	2'-3"	3'-9"	#5	16'-4"	#5	14'-6"
4'	#4	9	1'-11"	2'-7"	2'-3"	2'-3"	9'-8"	#4	9	1'-11"	2'-7"	2'-3"	2'-3"	9'-8"	4	3'-0"	4	3'-0"	4'-6"	#5	2'-11"	4'-5"	#5	2'-9"	4'-3"	#6	21'-1"	#6	18'-7"
5'	#4	11	1'-11"	3'-1"	2'-6"	2'-6"	10'-2"	#4	11	1'-11"	3'-1"	2'-6"	2'-6"	10'-2"	5	3'-0"	5	3'-0"	4'-6"	#5	3'-6"	5'-0"	#5	3'-3"	4'-9"	#6	25'-10"	#6	22'-9"
6'	#5	13	1'-11"	3'-8"	2'-9"	2'-10"	10'-9"	#5	13	1'-11"	3'-6"	2'-8"	2'-8"	10'-7"	6	3'-0"	6	3'-0"	4'-6"	#5	4'-1"	5'-7"	#5	3'-9"	5'-3"	#6	30'-7"	#6	26'-11"
7'	#5	15	2'-0"	4'-3"	3'-1"	3'-2"	11'-5"	#5	15	2'-0"	4'-1"	3'-0"	3'-1"	11'-3"	7	3'-0"	7	3'-0"	4'-6"	#5	4'-10"	6'-4"	#5	4'-4"	5'-10"	#6	35'-3"	#6	31'-0"
8'	#6	18	2'-1"	4'-10"	3'-5"	3'-6"	12'-1"	#6	17	2'-1"	4'-8"	3'-4"	3'-5"	11'-11"	8	3'-0"	8	3'-0"	4'-6"	#5	5'-6"	7'-0"	#5	4'-11"	6'-5"	#6	40'-0"	#6	35'-2"










TABLE OF REINFORCING STEEL FOR ONE END																														
BARS U- ONE PER EACH LENGTH SHOWN #4 @ 12" 30° WALL								BARS UI - ONE PER EACH LENGTH SHOWN #4 @ 12" 0° WALL								BARS V #4-EQUALLY SPACED 30° WALL								BARS V1 #4-EQUALLY SPACED 0° WALL						
H	C ₇	C ₈	C ₉	C ₁₀	C ₁₁	C ₁₂	C ₁₃	C ₁₄	C ₇	C ₈	C ₉	C ₁₀	C ₁₁	C ₁₂	C ₁₃	C ₁₄	NO.	C ₁₅	C ₁₆	C ₁₇	C ₁₈	C ₁₉	LENGTH	NO.	C ₁₅	C ₁₆	C ₁₇	C ₁₈	C ₁₉	LENGTH
3'	5'-1"	9'-8"	14'-3"	-	-	-	-	-	4'-4"	8'-4"	12'-4"	-	-	-	-	-	8	3'-10"	9"	2'-2"	2'-5"	1'-0"	6'-7"	7	3'-10"	9"	2'-2"	2'-5"	1'-0"	6'-7"
4'	5'-1"	9'-8"	14'-3"	18'-11"	-	-	-	-	4'-4"	8'-4"	12'-4"	16'-4"	-	-	-	-	11	4'-11"	10"	2'-9"	3'-0"	1'-0"	7'-9"	9	4'-11"	10"	2'-9"	3'-0"	1'-0"	7'-9"
5'	5'-1"	9'-8"	14'-3"	18'-11"	23'-6"	-	-	-	4'-4"	8'-4"	12'-4"	16'-4"	20'-4"	-	-	-	13	5'-11"	10"	3'-3"	3'-6"	1'-0"	8'-9"	11	5'-11"	10"	3'-3"	3'-6"	1'-0"	8'-9"
6'	5'-1"	9'-8"	14'-3"	18'-11"	23'-6"	28'-1"	-	-	4'-4"	8'-4"	12'-4"	16'-4"	20'-4"	24'-4"	-	-	15	6'-11"	10"	3'-9"	4'-0"	1'-0"	9'-9"	13	6'-11"	10"	3'-9"	4'-0"	1'-0"	9'-9"
7'	5'-1"	9'-8"	14'-3"	18'-11"	23'-6"	28'-1"	32'-9"	-	4'-4"	8'-4"	12'-4"	16'-4"	20'-4"	24'-4"	28'-4"	-	17	8'-0"	11"	4'-4"	4'-7"	1'-0"	10'-11"	15	8'-0"	11"	4'-4"	4'-7"	1'-0"	10'-11"
8'	5'-1"	9'-8"	14'-3"	18'-11"	23'-6"	28'-1"	32'-9"	37'-4"	4'-4"	8'-4"	12'-4"	16'-4"	20'-4"	24'-4"	28'-4"	32'-4"	20	9'-0"	11"	4'-10"	5'-1"	1'-1"	12'-1"	17	9'-0"	11"	4'-10"	5'-1"	1'-1"	12'-1"

TABLE OF REINFORCING STEEL FOR MINIMUM "S" - ONE END										
H	S	BARS Y 12-#5 ②	BARS R 6-#5 ②	BARS Z #4 @ 12" ①	BARS S #4 @ 12" ①	BARS T #4 @ 12" ①	BARS P 8-#5 ③			
		LENGTH	LENGTH	NO.	LENGTH	NO.	LENGTH	LENGTH		
3'	9'	12'-2"	16'-8"	10	5'-4"	16	6'-10"	10	3'-0"	6'-8"
4'	9'	12'-2"	19'-0"	10	5'-4"	18	6'-10"	10	3'-0"	7'-8"
5'	5'	6'-0"	17'-2"	6	5'-4"	16	6'-10"	6	3'-0"	8'-8"
6'	6'	7'-0"	20'-6"	7	5'-4"	20	6'-10"	7	3'-0"	9'-8"
7'	7'	7'-11"	23'-10"	8	5'-4"	23	6'-10"	8	3'-0"	10'-8"
8'	8'	8'-11"	27'-3"	9	5'-4"	26	6'-10"	9	3'-0"	11'-8"



NUMBER OF HEADWALL PIPE RUNNERS FOR 1 END			
S	NO.	S	NO.
10'	4	23'	10
11'	5	24'	10
12'	5	25'	10
13'	6	26'	11
14'	6	27'	11
15'	6	28'	12
16'	7	29'	12
17'	7	30'	12
18'	8	31'	13
19'	8	32'	13
20'	8	33'	14
21'	9	34'	14
22'	9	35'	14

- NOTES FOR TABLES:**
- ① THE NUMBER OF BARS S, T AND Z SHALL BE INCREASED BY 1 FOR EACH 1 FOOT OF INCREASE IN DIMENSION "W₁".
 - ② THE LENGTH OF BARS R AND Y SHALL BE INCREASED BY 1'-1/2" FOR EACH 1 FOOT OF INCREASE IN DIMENSION "S".
 - ③ THE NUMBER OF BARS P SHOWN ARE FOR SINGLE SPAN PIPES OR BOX CULVERTS. THIS NUMBER SHALL BE INCREASED BY 4 FOR EACH MULTIPLE OF PIPE OR BOX ADDED.
 - ④ THIS DIMENSION SHALL BE INCREASED BY 1'-1/2" INCHES FOR EACH 1 FOOT INCREASE IN DIMENSION "S".
 - ⑤ 2 BARS FOR 30° WALL, 2 BARS FOR 0° WALL
 - ⑥ THE LENGTH OF THIS BAR INCLUDES ONE 1'-6" MINIMUM LAP.




Paul Kovacs
APPROVED..... CHIEF ENGINEER..... DATE 6-1-2009...

Illinois Tollway
Open Roads for a Faster Future

SAFETY END TREATMENT FOR SINGLE AND MULTIPLE CULVERTS
15° SKEW 1:4 SLOPE H ≤ 8'

STANDARD B16-02




HALF PLAN SHOWING REINFORCING BARS
 HALF PLAN SHOWING DIMENSIONS

NOTE:


BARS O, V AND V_1 ARE TO BE FIELD CUT PER CUTTING DIAGRAM. PLACE BARS WITH DIMENSIONS C_2-C_3 AND C_9-C_{12} BEGINNING AT HEADWALL AND BARS WITH DIMENSIONS C_1-C_4 AND $C_{10}-C_{11}$ BEGINNING AT THE TOEWALL END.

NOTE:

BARS P1 ARE TO BE FIELD CUT PER CUTTING DIAGRAM. PLACE BARS WITH DIMENSIONS C_6-C_7 BEGINNING AT THE TOEWALL END OF 45° WINGWALL AND BARS WITH DIMENSIONS C_5-C_8 BEGINNING PARALLEL TO THE P BARS. PLACE BARS P2 PARALLEL TO THE P BARS BEGINNING WITH THE SHORTEST BARS AT THE HEADWALL END OF THE 15° WINGWALL.




ELEVATION PIPE ARCH DETAILS




SECTION B-B

NOTE:

DOWEL BAR J & H NOT REQUIRED WITH EXISTING BOX CULVERTS PROVIDING THE REINFORCING FROM THE EXIST. BOX IS EXTENDED INTO THE NEW CONCRETE A MIN. OF 1'-3".




SECTION AT WING



ELEVATION AT WING

NOTE:


PIPE O.D. IS THE PIPE RUNNER OUTSIDE DIAMETER




PLAN AT HEADWALL

NOTE:

A 3/4" x 9/2" BOLT WITH ADDITIONAL WASHER PLACED IN A 7/8" HOLE DRILLED THROUGH THE HEADWALL OR A 3/4" x 8" THREADED ROD EPOXY GROUTED IN A 7/8" HOLE WITH A MIN. EMBEDMENT OF 6" MAY BE USED IN LIEU OF CAST-IN-PLACE BOLT SHOWN.



ELEVATION AT HEADWALL



HALF PLAN SHOWING REINFORCING BARS

HALF PLAN SHOWING DIMENSIONS


** DOWEL BARS EXTENDING INTO THE CONCRETE BOX CULVERT ARE INCLUDED IN THE QUANTITIES.

BOX CULVERT DETAILS


S = DESIGN SPAN
 H = DESIGN HEIGHT

GENERAL NOTES:


- ALL CONCRETE SHALL BE CLASS S1.
- ALL EXPOSED CONCRETE EDGES SHALL HAVE A 3/4" x 45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW FINISHED GROUND LEVEL. COVER FROM THE FACE OF CONCRETE TO THE FACE OF REINFORCEMENT BARS SHALL BE 2", UNLESS OTHERWISE SHOWN.
- CONCRETE QUANTITIES SHOWN ON SHEET 2 (OF 2) IN THIS SERIES ARE FOR REINFORCED CONCRETE BOX CULVERT SECTIONS AND ADDITIONAL CONCRETE REQUIRED IN HEADWALLS FOR PIPE OR ARCH CULVERT SECTIONS SHALL BE ADDED TO THESE QUANTITIES.
- THIS STANDARD MAY BE USED FOR CULVERTS WITH SKEW OF 30° ± 7.5%, AS SHOWN PER CULVERT SKEW ORIENTATION ON THIS SHEET.
- DESIGN: SAFETY PIPE RUNNERS ARE DESIGNED FOR A TRANSVERSING LOAD OF 1,800 POUNDS AT YIELD AS RECOMMENDED BY RESEARCH REPORT 280-1, SAFETY TREATMENT OF ROADSIDE CROSS DRAINAGE STRUCTURES, TEXAS TRANSPORTATION INSTITUTE, MARCH 1981.
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
- FOR EROSION PROTECTION SEE STANDARD B19.



ELEVATION C-C



SECTION THRU TOEWALL




SECTION D - D


NOTE:

WHERE L_0, L_1, L_2 EXCEEDS THE FOLLOWING LENGTH, THE PIPE RUNNER SHALL BE STRENGTHENED OVER THE MIDSPAN AS SHOWN.


PIPE	LENGTH
3" Ø SCH 40	12'-8"
3" Ø SCH 80	15'-4"




SECTION A - A



CULVERT SKEW ORIENTATION



DETAIL A



ANCHOR BARS

CONTRACTOR SHALL PROVIDE 2-#3 ANCHOR BARS PER SIDEWALL BOLT.

DETAIL B

PIPE RUNNER DETAILS



DATE	REVISIONS
6-1-2009	REVISED NOTES
3-1-2010	MODIFIED CULVERT SKEW DETAIL, REVISED EROSION PROTECTION AND NOTES


SAFETY END TREATMENT FOR SINGLE CULVERTS 30° SKEW 1:4 SLOPE H ≤ 4'

STANDARD B17-02

APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009

CULVERT SIZE (FEET)	TABLE OF DIMENSIONS									
	S X H	L	NL	NR	V	W 1	W 2	WL	WR	TA
3 x 2	10'-10"	11'-2 5/8"	15'-3 3/8"	7"	3'-5 5/8"	11'-4 3/4"	2'-10 7/8"	10'-10"	6"	
3 x 3	14'-10"	15'-4 1/4"	20'-11 3/4"	7"	3'-5 5/8"	14'-3 7/8"	3'-11 3/4"	14'-10"	6"	
4 x 2	10'-10"	11'-2 5/8"	15'-3 3/8"	7"	4'-7 3/8"	12'-6 1/2"	2'-10 7/8"	10'-10"	6"	
4 x 3	14'-10"	15'-4 1/4"	20'-11 3/4"	7"	4'-7 3/8"	15'-5 5/8"	3'-11 3/4"	14'-10"	6"	
4 x 4	18'-10"	19'-6"	26'-7 5/8"	7"	4'-7 3/8"	18'-4 7/8"	5'-0 1/2"	18'-10"	6"	
5 x 2	10'-10"	11'-2 5/8"	15'-3 3/8"	7"	5'-9 1/4"	13'-8 3/8"	2'-10 7/8"	10'-10"	6"	
5 x 3	14'-10"	15'-4 1/4"	20'-11 3/4"	7"	5'-9 1/4"	16'-7 1/2"	3'-11 3/4"	14'-10"	6"	
5 x 4	18'-10"	19'-6"	26'-7 5/8"	7"	5'-9 1/4"	19'-6 3/4"	5'-0 1/2"	18'-10"	6"	
6 x 3	14'-10"	15'-4 1/4"	20'-11 3/4"	7"	6'-11 1/8"	17'-9 3/4"	3'-11 3/4"	14'-10"	6"	
6 x 4	18'-10"	19'-6"	26'-7 5/8"	7"	6'-11 1/8"	20'-8 3/8"	5'-0 1/2"	18'-10"	6"	
7 x 3	14'-10"	15'-4 1/4"	20'-11 3/4"	7"	8'-1"	18'-11 1/4"	3'-11 3/4"	14'-10"	6 1/2"	
7 x 4	18'-10"	19'-6"	26'-7 5/8"	7"	8'-1"	21'-10 1/2"	5'-0 1/2"	18'-10"	6 1/2"	
8 x 4	18'-10"	19'-6"	26'-7 5/8"	7"	9'-2 7/8"	23'-0 3/8"	5'-0 1/2"	18'-10"	7"	

SCHEDULE	PIPE RUNNERS FOR ONE END SIZE 3"*					
	HEADWALL PIPE	WINGWALL PIPE - ONE PER EACH LENGTH SHOWN				
		NO.	L ₀	15° WALL		45° WALL
40	2	12'-9"	7'-10"	-	9'-1"	-
40	2	17'-5"	12'-6"	-	13'-10"	6'-7"
40	2	12'-9"	7'-8"	-	9'-1"	-
40	2	17'-5"	12'-5"	-	13'-10"	6'-7"
80	2	22'-2"	17'-3"	7'-4"	18'-9"	11'-4"
40	3	12'-9"	7'-8"	-	9'-0"	-
40	3	17'-9"	12'-5"	-	13'-9"	6'-6"
80	3	22'-2"	17'-1"	7'-4"	18'-7"	11'-4"
40	3	17'-5"	12'-5"	-	13'-9"	6'-6"
80	3	22'-2"	17'-1"	7'-2"	18'-5"	11'-2"
40	4	17'-5"	12'-5"	-	13'-9"	6'-6"
80	4	22'-2"	17'-1"	7'-2"	18'-5"	11'-2"
80	4	22'-2"	17'-1"	7'-2"	18'-5"	11'-2"



CULVERT SIZE (FEET)	TABLE OF REINFORCING STEEL FOR ONE END																													
	DOWELS H #4 @ 12" 2'-6" LG.		DOWELS J #4 @ 12" 2'-6" LG.		BARS P #4 @ 12"		BARS P1 #4 @ 12"					BARS P2 - ONE PER EACH LENGTH SHOWN #4 @ 12"					BARS Q #4 @ 12"				BARS R 3-#4	BARS S 45° WALL 2-#4	BARS S1 15° WALL 2-#4	BARS U - ONE PER EACH LENGTH SHOWN #4 @ 12"						
	S X H	NO. *	NO. **	NO. *	NO. **	NO.	LENGTH	NO.	C ₅	C ₆	C ₇	C ₈	LENGTH	α ₁	α ₂	α ₃	α ₄	α ₅	NO.	C ₁	C ₂	C ₃	C ₄	LENGTH	LENGTH	LENGTH	LENGTH	α ₆	α ₇	α ₈
3 x 2	3	3	2	2	1	13'-9"	5	10'-6"	1'-6"	5'-6"	6'-6"	17'-2"	5'-4"	9'-1"	-	-	-	5	11'-6"	4'-11"	7'-10"	8'-7"	16'-5"	11'-10"	14'-10"	11'-0"	6'-2"	11'-10"	-	-
3 x 3	4	4	2	2	0	-	7	14'-6"	1'-6"	7'-6"	8'-6"	21'-2"	5'-4"	9'-1"	12'-10"	-	-	7	14'-5"	4'-11"	9'-4"	10'-0"	19'-4"	20'-6"	20'-6"	11'-0"	6'-2"	11'-10"	17'-6"	-
4 x 2	3	3	2	2	2	13'-9"	5	10'-6"	1'-6"	5'-6"	6'-6"	17'-2"	2'-3"	6'-0"	9'-9"	-	-	5	12'-8"	6'-1"	9'-0"	9'-9"	18'-9"	13'-0"	14'-10"	11'-0"	6'-2"	11'-10"	-	-
4 x 3	4	4	2	2	1	17'-9"	7	14'-6"	1'-6"	7'-6"	8'-6"	21'-2"	2'-3"	6'-0"	9'-9"	13'-6"	-	7	15'-7"	6'-1"	10'-6"	11'-2"	21'-8"	15'-11"	20'-6"	15'-2"	6'-2"	11'-10"	17'-6"	-
4 x 4	5	5	2	2	0	-	9	18'-6"	1'-6"	9'-6"	10'-6"	25'-2"	2'-3"	6'-0"	9'-9"	13'-6"	17'-3"	9	18'-6"	6'-1"	11'-11"	12'-8"	24'-7"	18'-10"	26'-2"	6'-2"	11'-10"	17'-6"	23'-1"	-
5 x 2	3	3	2	2	3	13'-9"	5	10'-6"	1'-6"	5'-6"	6'-6"	17'-2"	2'-10"	6'-7"	10'-4"	-	-	5	13'-10"	7'-3"	10'-2"	10'-11"	21'-1"	14'-2"	14'-10"	11'-0"	6'-2"	11'-10"	-	-
5 x 3	4	4	2	2	2	17'-9"	7	14'-6"	1'-6"	7'-6"	8'-6"	21'-2"	2'-10"	6'-7"	10'-4"	14'-0"	-	7	16'-9"	7'-3"	11'-8"	12'-4"	24'-0"	20'-6"	20'-6"	15'-2"	6'-2"	11'-10"	17'-6"	-
5 x 4	5	5	2	2	1	21'-9"	9	18'-6"	1'-6"	9'-6"	10'-6"	25'-2"	2'-10"	6'-7"	10'-4"	14'-0"	17'-9"	9	19'-8"	7'-3"	13'-1"	13'-10"	26'-11"	20'-0"	26'-2"	19'-4"	6'-2"	11'-10"	17'-6"	23'-1"
6 x 3	4	4	2	2	3	17'-9"	7	14'-6"	1'-6"	7'-6"	8'-6"	21'-2"	3'-4"	7'-1"	10'-10"	14'-7"	-	7	17'-11"	8'-4"	12'-9"	13'-6"	26'-3"	18'-3"	20'-6"	15'-2"	6'-2"	11'-10"	17'-6"	-
6 x 4	5	5	2	2	2	21'-9"	9	18'-6"	1'-6"	9'-6"	10'-6"	25'-2"	3'-4"	7'-1"	10'-10"	14'-7"	18'-3"	9	20'-10"	8'-4"	14'-3"	14'-11"	29'-2"	21'-2"	26'-2"	6'-2"	11'-10"	17'-6"	23'-1"	-
7 x 3	4	4	2	2	4	17'-9"	7	14'-6"	1'-6"	7'-6"	8'-6"	21'-2"	4'-0"	7'-9"	11'-5"	15'-2"	-	7	19'-1"	9'-6"	13'-11"	14'-8"	28'-7"	19'-5"	20'-6"	15'-2"	6'-2"	11'-10"	17'-6"	-
7 x 4	5	5	2	2	3	21'-9"	9	18'-6"	1'-6"	9'-6"	10'-6"	25'-2"	4'-0"	7'-9"	11'-5"	15'-2"	19'-0"	9	22'-0"	9'-6"	15'-5"	16'-1"	31'-6"	22'-4"	26'-2"	19'-4"	6'-2"	11'-10"	17'-6"	23'-1"
8 x 4	5	5	2	2	5	21'-9"	9	18'-6"	1'-6"	9'-6"	10'-6"	25'-2"	4'-6"	8'-3"	12'-0"	15'-9"	-	9	23'-1"	10'-8"	16'-6"	17'-3"	33'-9"	23'-6"	26'-2"	19'-4"	6'-2"	11'-10"	17'-6"	23'-1"


CULVERT SIZE (FEET)	TABLE OF REINFORCING STEEL FOR ONE END																					
	BARS U1 - ONE PER EACH LENGTH SHOWN #4 @ 12"				BARS V #4 @ 12"				BARS V1 #4 @ 12"				2 BARS W 45° WALL		2 BARS W1 15° WALL		BARS Y 8-#5	BARS T 8-#5				
	15° WALL				45° WALL				15° WALL				SIZE	LENGTH	SIZE	LENGTH	LENGTH	LENGTH				
3 x 2	4'-6"	8'-7"	-	-	7	2'-9"	6"	1'-6"	1'-9"	6'-3"	5	2'-9"	6"	1'-6"	1'-9"	6'-3"	#5	14'-5"	#5	10'-8"	4'-4"	3'-2"
3 x 3	4'-6"	8'-7"	12'-9"	-	10	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"	#5	20'-2"	#5	14'-11"	4'-4"	4'-2"
4 x 2	4'-6"	8'-7"	-	-	7	2'-9"	6"	1'-6"	1'-9"	6'-3"	5	2'-9"	6"	1'-6"	1'-9"	6'-3"	#5	14'-5"	#5	10'-8"	5'-6"	3'-2"
4 x 3	4'-6"	8'-7"	12'-9"	-	10	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"	#5	20'-2"	#5	14'-11"	5'-6"	4'-2"
4 x 4	4'-6"	8'-7"	12'-9"	16'-11"	13	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"	#6	25'-11"	#6	19'-1"	5'-6"	5'-2"
5 x 2	4'-6"	8'-7"	-	-	7	2'-9"	6"	1'-6"	1'-9"	6'-3"	5	2'-9"	6"	1'-6"	1'-9"	6'-3"	#5	14'-5"	#5	10'-8"	6'-8"	3'-2"
5 x 3	4'-6"	8'-7"	12'-9"	-	10	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"	#5	20'-2"	#5	14'-11"	6'-8"	4'-2"
5 x 4	4'-6"	8'-7"	12'-9"	16'-11"	13	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"	#6	25'-11"	#6	19'-1"	6'-8"	5'-2"
6 x 3	4'-6"	8'-7"	12'-9"	-	10	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"	#5	20'-2"	#5	14'-11"	7'-10"	4'-2"
6 x 4	4'-6"	8'-7"	12'-9"	16'-11"	13	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"	#6	25'-11"	#6	19'-1"	7'-10"	5'-2"
7 x 3	4'-6"	8'-7"	12'-9"	-	10	3'-9"	6"	2'-0"	2'-3"	7'-3"	7	3'-9"	6"	2'-0"	2'-3"	7'-3"	#5	20'-2"	#5	14'-11"	9'-0"	4'-2"
7 x 4	4'-6"	8'-7"	12'-9"	16'-11"	13	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"	#6	25'-11"	#6	19'-1"	9'-0"	5'-2"
8 x 4	4'-6"	9'-0"	12'-9"	16'-11"	13	4'-9"	6"	2'-6"	2'-9"	8'-3"	9	4'-9"	6"	2'-6"	2'-9"	8'-3"	#6	25'-11"	#6	19'-1"	10'-2"	5'-2"

TOTAL QUANTITIES ONE END			
CONC.	RE-BARS	PIPE RUNNERS	RIPRAP HAND-LAID
CU. YD.	LB.	FT.	SQ. YD.
3.4	391	41.67	5.9
5.4	573	67.17	7.6
3.8	423	41.67	6.1
5.8	610	67.17	7.8
8.3	867	97.83	9.5
4.1	453	54.17	6.3
6.2	646	84.42	8.0
8.8	909	119.83	9.7
6.6	682	84.42	8.2
9.2	951	119.83	9.9
7.4	719	101.67	8.4
10.2	995	141.84	10.1
11.2	1038	141.84	10.3

NOTE:
REINFORCEMENT BAR BENDING DIMENSIONS ARE OUT TO OUT.


* 45° WALL
** 15° WALL

PIPE ARCH AND ELLIPTICAL PIPE CULVERTS



T1 BARS

THE WEIGHT OF THE ADDITIONAL BARS AND THE ADDITIONAL QUANTITY OF CONCRETE IN THE HEADWALL SHALL BE ADDED TO THE QUANTITIES SHOWN.








APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009

SHEET 2 OF 2

Illinois Tollway
Open Roads for a Faster Future

SAFETY END TREATMENT
FOR SINGLE CULVERTS
30° SKEW 1:4 SLOPE H ≤ 4'

STANDARD B17-02









NOTE:
 BARS F, F1, V & V1 ARE TO BE FIELD CUT PER CUTTING DIAGRAM. PLACE BARS WITH DIMENSIONS C₂ - C₄, C₁₅ - C₁₈ BEGINNING AT HEADWALL & BARS WITH DIMENSIONS C₁ - C₃, C₁₆ - C₁₇ BEGINNING AT THE TOEWALL END.

NOTE:
 DOWEL BAR J & H NOT REQUIRED WITH EXISTING BOX CULVERTS PROVIDING THE REINFORCING FROM THE EXIST. BOX IS EXTENDED INTO THE NEW CONCRETE A MIN. OF 1'-3".

NOTE:
 PIPE O.D. IS THE PIPE RUNNER OUTSIDE DIAMETER.

NOTE:
 A 3/4" x 9/16" BOLT WITH ADDITIONAL P WASHER PLACED IN A 1/8" x 1/8" HOLE DRILLED THROUGH THE HEADWALL OR A 3/4" x 8" THREADED ROD EPOXY GROUTED IN A 1/8" HOLE WITH A MINIMUM EMBEDMENT OF 6 3/8" MAY BE USED IN LIEU OF CAST-IN-PLACE BOLT SHOWN.



** DOWEL BARS EXTENDING INTO THE CONCRETE BOX CULVERT ARE INCLUDED IN THE QUANTITIES.

FOR BOX CULVERTS S = DESIGN SPAN H = DESIGN HEIGHT

- GENERAL NOTES:**
- ALL CONCRETE SHALL BE CLASS SI.
 - ALL EXPOSED CONCRETE EDGES SHALL HAVE A 3/4" x 45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW FINISHED GROUND LEVEL. COVER FROM THE FACE OF CONCRETE TO THE FACE OF REINFORCEMENT BARS SHALL BE 2", UNLESS OTHERWISE SHOWN.
 - CONCRETE QUANTITIES SHOWN ON SHEET 2 (OF 2) IN THIS SERIES ARE FOR REINFORCED CONCRETE BOX CULVERT SECTIONS AND ADDITIONAL CONCRETE REQUIRED IN HEADWALLS FOR PIPE OR ARCH CULVERT SECTIONS SHALL BE ADDED TO THESE QUANTITIES.
 - THIS STANDARD MAY BE USED FOR CULVERTS WITH SKEW OF 30° ± 7.5°, AS SHOWN PER CULVERT SKEW ORIENTATION ON THIS SHEET.
 - DESIGN: SAFETY PIPE RUNNERS ARE DESIGNED FOR A TRANSVERSING LOAD OF 1,800 POUNDS AT YIELD AS RECOMMENDED BY RESEARCH REPORT 280-1, SAFETY TREATMENT OF ROADSIDE CROSS DRAINAGE STRUCTURES, TEXAS TRANSPORTATION INSTITUTE, MARCH 1981.
 - ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
 - FOR EROSION PROTECTION SEE STANDARD B19.

PIPE	LENGTH
3'-0", SCH. 40	12'-8"
3'-0", SCH. 80	15'-4"
3 1/2'-0", SCH. 80	22'-1"
4'-0", SCH. 80	29'-4"

NOTE:
 WHERE L₀, L₁, L₄ OR L₅ EXCEEDS THE FOLLOWING LENGTH THE PIPE RUNNER SHALL BE STRENGTHENED OVER MIDSPAN AS SHOWN.

APPROVED: *Paul Kovacs* DATE 6-1-2009
 CHIEF ENGINEER



DATE	REVISIONS
6-1-2009	REVISED NOTES
3-1-2010	MODIFIED CULVERT SKEW DETAIL, REVISED EROSION PROTECTION AND NOTES

SAFETY END TREATMENT FOR SINGLE AND MULTIPLE CULVERTS 30° SKEW, 1:4 H ≤ 8' & S=VARIES
 STANDARD B18-02

H	S	L	NL	NR	WW	W ₁ (4)	W ₂ (4)	WL	WR	WF	TF
3'	9"	14'-4"	14'-10 ¹ / ₈ "	20'-3 ¹ / ₄ "	7"	10'-4 ³ / ₄ "	20'-10 ³ / ₈ "	3'-10 ¹ / ₈ "	14'-4"	3"	7"
4'	9"	18'-4"	18'-11 ³ / ₈ "	25'-11 ¹ / ₈ "	7"	10'-4 ³ / ₄ "	23'-9 ³ / ₄ "	4'-11"	18'-4"	9"	8"
5'	5'	22'-4"	23'-1 ¹ / ₂ "	31'-7"	7"	5'-9 ¹ / ₄ "	22'-1 ¹ / ₂ "	5'-11 ³ / ₄ "	22'-4"	1'-3"	8"
6'	6'	26'-4"	27'-3 ¹ / ₈ "	37'-2 ¹ / ₈ "	7"	6'-11 ¹ / ₈ "	26'-2 ¹ / ₈ "	7'- ⁵ / ₈ "	26'-4"	1'-9"	8 ¹ / ₂ "
7'	7'	30'-4"	31'-4 ¹ / ₈ "	42'-10 ³ / ₄ "	7"	8'-1"	30'-3 ¹ / ₂ "	8'-1 ¹ / ₂ "	30'-4"	2'-3"	9"
8'	8'	34'-4"	35'-6 ¹ / ₂ "	48'-6 ¹ / ₂ "	8"	9'-2 ¹ / ₈ "	34'-4 ¹ / ₂ "	9'-2 ¹ / ₈ "	34'-4"	2'-9"	9 ¹ / ₂ "

TOTAL QUANTITIES ONE END MINIMUM "S"				INCREASE IN QUANTITIES FOR 1' INCREASE IN "S"			
CONC. CU. YD.	RE-BARS LBS.	RIPRAP DUMPED SO. YD.	RIPRAP HAND-LAID SO. YD.	CONC. CU. YD.	RE-BARS LBS.	RIPRAP DUMPED SO. YD.	RIPRAP HAND-LAID SO. YD.
7.5	1006	20.3	8.6	0.22	33	1.73	0.19
10.3	1265	29.1	10.2	0.22	33	2.25	0.19
12.2	1373	28.2	11.2	0.22	33	2.76	0.19
15.8	1851	40.9	13.0	0.22	33	3.28	0.19
20.7	2326	55.9	14.9	0.22	33	3.79	0.19
36.7	2953	73.2	16.8	0.22	33	4.30	0.19

NOTE:

REINFORCEMENT BARS BENDING DIMENSIONS ARE OUT TO OUT.





H	SIZE (DIA.)	SCHEDULE	WINGWALL PIPES - ONE PER EACH LENGTH SHOWN								HEADWALL PIPES				TOTAL LENGTH	1-BAR C 45° WALL		1-BAR C1 15° WALL		BAR D 4-#4 45° WALL		BAR D1 4-#4 15° WALL		*4-BARS E 45° WALL (6)		*4-BARS E1 15° WALL (6)	
			15° WALL				45° WALL				S	No.	L ₀	SIZE		LENGTH	SIZE	LENGTH	LENGTH	LENGTH	NO.	LENGTH	NO.	LENGTH			
			L ₁	L ₂	L ₃	L ₄	L ₅	L ₆	L ₇	L ₈																	
3'	3"	40	11'-11"	-	-	13'-3"	6'-0"	-	-	9'	4	16'-10"	#4	20'-8"	#4	15'-3"	22'-9"	17'-2"	2	17'-0"	2	21'-4"					
4'	3"	80	16'-8"	-	-	18'-0"	10'-9"	-	-	9'	4	21'-7"	#4	26'-4"	#4	19'-5"	28'-5"	21'-4"	2	21'-1"	2	27'-0"					
5'	3 ¹ / ₂ "	80	21'-4"	11'-6"	-	22'-8"	15'-5"	8'-2"	-	5'	3	26'-4"	#4	32'-0"	#4	23'-7"	34'-1"	25'-6"	2	25'-3"	2	32'-8"					
6'	3 ¹ / ₂ "	80	26'-1"	16'-2"	-	27'-9"	20'-2"	12'-11"	5'-8"	6'	3	31'-0"	#4	37'-8"	#4	27'-8"	39'-9"	29'-7"	3	29'-4"	3	38'-4"					
7'	4"	80	30'-10"	20'-11"	11'-0"	32'-2"	24'-9"	17'-8"	10'-9"	7'	4	35'-9"	#5	44'-10"	#5	31'-10"	46'-11"	33'-9"	3	33'-6"	3	44'-0"					
8'	4"	80	35'-9"	25'-8"	15'-9"	36'-10"	29'-7"	22'-4"	15'-1"	8'	4	40'-6"	#5	50'-6"	#5	36'-0"	52'-6"	37'-10"	3	37'-7"	3	49'-8"					

H	BARS F EQUALLY SPACED 45° WALL							BARS L 45° WALL			BARS F1 EQUALLY SPACED 15° WALL					DOWELS H #5 @ 12" 45° WALL	DOWELS H #5 @ 12" 15° WALL	DOWELS J 4-#6 (5)	1-BAR K 45° WALL		1-BAR K1 15° WALL		2-BARS W 45° WALL		2-BARS W1 15° WALL								
	SIZE	NO.	C ₁	C ₂	C ₃	C ₄	LENGTH	SIZE	NO.	C ₀	LENGTH	SIZE	NO.	C ₁	C ₂	C ₃	C ₄	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH			
3'	#4	10	1'-11"	2'-2"	2'-0"	2'-1"	9'-3"	#4	-	-	-	#4	8	1'-11"	2'-2"	2'-0"	2'-1"	9'-3"	3	3'-0"	3	3'-0"	4'-6"	#5	3'-1"	4'-7"	#5	2'-3"	3'-9"	#5	19'-11"	#5	14'-11"
4'	#4	12	1'-11"	2'-8"	2'-3"	2'-4"	9'-9"	#4	1	3'-10"	6'-5"	#4	10	1'-11"	2'-8"	2'-3"	2'-4"	9'-9"	4	3'-0"	4	3'-0"	4'-6"	#5	3'-10"	5'-4"	#5	2'-10"	4'-4"	#6	25'-8"	#6	19'-2"
5'	#4	15	1'-11"	3'-2"	2'-6"	2'-7"	10'-3"	#4	2	4'-6"	7'-1"	#4	12	1'-11"	3'-2"	2'-6"	2'-7"	10'-3"	5	3'-0"	5	3'-0"	4'-6"	#5	4'-6"	6'-0"	#5	3'-4"	4'-10"	#6	31'-5"	#6	23'-5"
6'	#5	18	1'-11"	3'-8"	2'-9"	2'-10"	10'-9"	#5	2	5'-3"	7'-10"	#5	14	1'-11"	3'-8"	2'-9"	2'-10"	10'-9"	6	3'-0"	6	3'-0"	4'-6"	#5	5'-3"	6'-9"	#5	3'-11"	5'-5"	#6	37'-2"	#6	27'-8"
7'	#5	20	2'-0"	4'-3"	3'-1"	3'-2"	11'-5"	#5	3	6'-0"	8'-7"	#5	16	2'-0"	4'-2"	3'-1"	3'-1"	11'-4"	7	3'-0"	7	3'-0"	4'-6"	#5	6'-0"	7'-6"	#5	4'-5"	5'-11"	#7	44'-2"	#7	31'-11"
8'	#6	23	2'-1"	4'-10"	3'-5"	3'-6"	12'-1"	#6	3	6'-9"	9'-4"	#6	18	2'-1"	4'-8"	3'-4"	3'-5"	11'-11"	8	3'-0"	8	3'-0"	4'-6"	#5	6'-9"	8'-3"	#5	5'-0"	6'-6"	#7	50'-0"	#7	36'-2"

S	NO.	S	NO.
10'	5	23'	11
11'	5	24'	11
12'	6	25'	12
13'	6	26'	12
14'	7	27'	12
15'	7	28'	13
16'	8	29'	13
17'	8	30'	14
18'	8	31'	14
19'	9	32'	15
20'	9	33'	15
21'	10	34'	16
22'	10	35'	16

H	BARS U- ONE PER EACH LENGTH SHOWN #4 @ 12" 45° WALL							BARS U1 - ONE PER EACH LENGTH SHOWN #4 @ 12" 15° WALL							BARS V #4-EQUALLY SPACED 45° WALL					BARS V1 #4-EQUALLY SPACED 15° WALL										
	C ₇	C ₈	C ₉	C ₁₀	C ₁₁	C ₁₂	C ₁₃	C ₁₄ (6)	C ₇	C ₈	C ₉	C ₁₀	C ₁₁	C ₁₂	C ₁₃	C ₁₄	NO.	C ₁₅	C ₁₆	C ₁₇	C ₁₈	C ₁₉	LENGTH	NO.	C ₁₅	C ₁₆	C ₁₇	C ₁₈	C ₁₉	LENGTH
3'	6'-2"	11'-9"	17'-5"	--	--	--	--	--	4'-6"	8'-7"	12'-9"	--	--	--	--	--	10	3'-11"	9"	2'-3"	2'-5"	1'-0"	6'-8"	7	3'-11"	9"	2'-3"	2'-5"	1'-0"	6'-8"
4'	6'-2"	11'-9"	17'-5"	23'-1"	--	--	--	--	4'-6"	8'-7"	12'-9"	16'-11"	--	--	--	--	13	5'-0"	10"	2'-10"	3'-0"	1'-0"	7'-10"	9	5'-0"	10"	2'-10"	3'-0"	1'-0"	7'-10"
5'	6'-2"	11'-9"	17'-5"	23'-1"	28'-9"	--	--	--	4'-6"	8'-7"	12'-9"	16'-11"	21'-0"	--	--	--	15	6'-0"	10"	3'-4"	3'-6"	1'-0"	8'-10"	11	6'-0"	10"	3'-4"	3'-6"	1'-0"	8'-10"
6'	6'-2"	11'-9"	17'-5"	23'-1"	28'-9"	34'-5"	--	--	4'-6"	8'-7"	12'-9"	16'-11"	21'-0"	25'-2"	--	--	18	7'-0"	10"	3'-10"	4'-0"	1'-0"	9'-10"	14	7'-0"	10"	3'-10"	4'-0"	1'-0"	9'-10"
7'	6'-2"	11'-9"	17'-5"	23'-1"	28'-9"	34'-5"	40'-0"	--	4'-6"	8'-7"	12'-9"	16'-11"	21'-0"	25'-2"	29'-4"	--	21	8'-1"	11"	4'-5"	4'-7"	1'-0"	11'-0"	16	8'-1"	11"	4'-5"	4'-7"	1'-0"	11'-0"
8'	6'-2"	11'-9"	17'-5"	23'-1"	28'-9"	34'-5"	47'-3"	4'-6"	8'-7"	12'-9"	16'-11"	21'-0"	25'-2"	29'-4"	33'-5"	24	9'-1"	11"	4'-11"	5'-1"	1'-1"	12'-2"	18	9'-1"	11"	4'-11"	5'-1"	1'-1"	12'-2"	

H	S	BARS Y 12-#5 (2)		BARS R 6-#5 (2)		BARS Z #4@12" (1)		BARS S #4@12" (1)		BARS T #4@12" (1)		BARS P 8-#5 (3)	
		LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.	LENGTH	NO.
3'	≥9"	11'-4"	19'-10"	10	5'-4"	20	6'-10"	10	3'-0"	6'-8"			
4'	≥9"	11'-4"	22'-10"	10	5'-4"	23	6'-10"	10	3'-0"	7'-8"			
5'	≥5'	6'-9"	21'-1"	6	5'-4"	21	6'-10"	6	3'-0"	8'-8"			
6'	≥6'	7'-10"	25'-2"	7	5'-4"	25	6'-10"	7	3'-0"	9'-8"			
7'	≥7'	9'-1"	29'-3"	8	5'-4"	30	6'-10"	8	3'-0"	10'-8"			
8'	≥8'	10'-4"	33'-4"	9	5'-4"	34	6'-10"	9	3'-0"	11'-8"			



NOTES FOR TABLES:


1. THE NUMBER OF BARS S, T AND Z SHALL BE INCREASED BY 1 FOR EACH 1 FOOT OF INCREASE IN DIMENSION "W".
2. THE LENGTH OF BARS R AND Y SHALL BE INCREASED BY 1'-1¹/₈" FOR EACH 1 IF INCREASE IN DIMENSION "S".
3. THE NUMBER OF BARS P SHOWN ARE FOR SINGLE SPAN PIPES OR BOX CULVERTS. THIS NUMBER SHALL BE INCREASED BY 4 FOR EACH MULTIPLE OF PIPE OR BOX ADDED.
4. THIS DIMENSION SHALL BE INCREASED BY 1'-1¹/₈" INCHES FOR EACH 1 FOOT INCREASE IN DIMENSION "S".
5. 2 BARS FOR 15° WALL, 2 BARS FOR 45° WALL.
6. THE LENGTH OF THIS BAR INCLUDES ONE 1'-6" MINIMUM LAP.

Illinois Tollway
Open Roads for a Faster Future


SAFETY END TREATMENT FOR SINGLE AND MULTIPLE CULVERTS 30° SKEW 1:4 H ≤ 8' & S=VARIES

STANDARD B18-02


Paul Kovacs
APPROVED..... CHIEF ENGINEER..... DATE 6-1-2009.....




PLAN-0° SKEW, H ≤ 4'




PLAN-0° SKEW, H ≤ 8'



SECTION A-A





SECTION AT HEADWALL




SECTION B-B

NOTES:


1. THE PREFERRED METHOD FOR ACHIEVING EROSION PROTECTION AT END SECTIONS SHOULD BE THROUGH THE USE OF PRODUCTS THAT PROMOTE REVEGETATION WITHIN THE AREA OF CONCERN.
2. THICKNESS "t" WILL BE DETERMINED BY THE MANUFACTURE'S RECOMMENDATION FOR THE PRODUCT USED. STONE RIPRAP SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.
3. EROSION PROTECTION PLACEMENT SHALL BE INSTALLED FLUSH WITH ADJACENT GRADE.
4. FOR USE WITH STANDARDS B10 TO B18.



PLAN-SKEW, H ≤ 4'



PLAN-SKEW, H ≤ 8'



 APPROVED..... CHIEF ENGINEER DATE 3-1-2010...

DATE	REVISIONS
3-1-2010	REVISED EROSION PROTECTION AND NOTES



EROSION PROTECTION

STANDARD B19-01



DIMENSIONS AND QUANTITIES IN TWO WINGWALLS 1:4 SLOPE

CULVERT HEIGHT	DIMENSIONS								NO. OF SPACES			CONC. HDWLS CLASS SI CY*	REINF. STEEL LBS.*
	H	L	S	T	U	A	E	B	C	D			
36"	3'-8"	14'-0"	14'-5/8"	2"	2'-8"	2'-2"	2'-2"	-	4	-	1.33	211	
42"	4'-3"	16'-4"	16'-10"	2"	3'-2"	2'-8"	2'-2"	4	-	-	1.78	285	
48"	4'-9"	18'-4"	18'-10 3/4"	2"	3'-2"	2'-2"	2'-2"	-	6	-	2.23	333	
54"	5'-3"	20'-4"	20'-11 1/2"	2"	3'-6"	2'-2"	2'-2"	4	2	-	2.72	411	
60"	5'-10"	22'-8"	23'-4 3/8"	2"	3'-6"	2'-2"	2'-2"	-	8	-	3.36	504	





TABLE OF BARS IN ONE WINGWALL 1:4 SLOPE


CULVERT HEIGHT	NO. 4 REINFORCING BARS					
	MARK	TYPE	NO. REQ'D	LENGTH	a	b
36"	4 h 36	STR.	4	13'-8"	-	-
	3/4" EXP BLT	---	3	---	-	-
	4 v 36	---	7	5'-6"	2'-0"	3'-6"
	4 x 36	---	15	4'-4"	2'-2"	2'-2"
42"	4 h 42	STR.	5	16'-0"	-	-
	3/4" EXP BLT	---	4	---	-	-
	4 v 42	---	10	6'-0"	1'-11"	4'-1"
	4 x 42	---	17	4'-4"	2'-2"	2'-2"
48"	4 h 48	STR.	5	18'-0"	-	-
	3/4" EXP BLT	---	4	---	-	-
	4 v 48	---	12	6'-5"	1'-10"	4'-7"
	4 x 48	---	19	4'-4"	2'-2"	2'-2"
54"	4 h 54	STR.	6	20'-0"	-	-
	3/4" EXP BLT	---	4	---	-	-
	4 v 54	---	14	6'-11"	1'-10"	5'-1"
	4 x 54	---	21	4'-4"	2'-2"	2'-2"
60"	4 h 60	STR.	7	22'-4"	-	-
	3/4" EXP BLT	---	5	---	-	-
	4 v 60	---	16	7'-7"	1'-11"	5'-8"
	4 x 60	---	23	4'-4"	2'-2"	2'-2"

TABLE OF BARS IN SLAB 1:4 SLOPE (PER FT. OF FLOOR SLAB WIDTH)

CULVERT HEIGHT	MARK	TYPE	NO. REQ'D	LENGTH	a	b	REINF. LBS. *	CY. CONC. *
36"	4 n 36	1	1	4'-1"	2'-1"	2'-0"	27	.45
	4 w 36	STR.	1	13'-8"	-	-	-	-
	4 t 36	STR.	18	W-(0'-4")	-	-	-	-
	3/4" EXP BLT	---	0.67	---	-	-	-	-
42"	4 n 42	1	1	4'-7"	2'-7"	2'-0"	32	.53
	4 w 42	STR.	1	16'-0"	-	-	-	-
	4 t 42	STR.	20	W-(0'-4")	-	-	-	-
	3/4" EXP BLT	---	0.67	---	-	-	-	-
48"	4 n 48	1	1	4'-7"	2'-7"	2'-0"	33	.58
	4 w 48	STR.	1	18'-0"	-	-	-	-
	4 t 48	STR.	22	W-(0'-4")	-	-	-	-
	3/4" EXP BLT	---	0.67	---	-	-	-	-
54"	4 n 54	1	1	4'-11"	2'-11"	2'-0"	37	.64
	4 w 54	STR.	1	20'-0"	-	-	-	-
	4 t 54	STR.	24	W-(0'-4")	-	-	-	-
	3/4" EXP BLT	---	0.67	---	-	-	-	-
60"	4 n 60	1	1	4'-11"	2'-11"	2'-0"	39	.70
	4 w 60	STR.	1	22'-4"	-	-	-	-
	4 t 60	STR.	26	W-(0'-4")	-	-	-	-
	3/4" EXP BLT	---	0.67	---	-	-	-	-

GENERAL NOTES:

- ALL EXPOSED CONCRETE EDGES SHALL HAVE A 3/4" X 45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW FINISHED GROUND LEVEL. COVER FROM THE FACE OF CONCRETE TO FACE OF REINFORCEMENT BARS SHALL BE 2" UNLESS OTHERWISE SHOWN.
- CONCRETE QUANTITIES SHOWN ARE FOR REINFORCED CONCRETE BOX CULVERT HEADWALLS.
- PAY ITEMS ARE IDENTIFIED BY AN ASTERISK (*).
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).



NOTES:

- TYPE 2 "v" BARS SHALL BE ORDERED FULL LENGTH AND CUT IN THE FIELD. THE REMAINING PORTION OF THE "v" BARS SHALL BE USED IN THE OTHER WALL.
- THE LONG LEG OF THE "n" BAR SHALL BE VERTICAL.
- SEE STANDARD B23 FOR GRATING DETAILS.


DATE	REVISIONS
6-1-2009	REVISED NOTES
1-1-2011	REVISED NOTES




HEADWALL TYPE IV BOX CULVERT ≤ 84" WIDTH

STANDARD B20-02


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009



PLAN VIEW (NO SKEW)
SINGLE BOX CULVERT ≤ 84" WIDE




SECTION A-A
END TREATMENT - MULTIPLE OR SINGLE
BOX CULVERT




NOTE:
REINFORCEMENT BARS AND GRATE SPACING ARE
SIMILAR TO BOX CULVERT AT NORMAL (NO SKEW).


PLAN VIEW
SKEW ORIENTATION




GRATE DETAILS
(NO SKEW)



GRATE DETAILS
(WITH SKEW)



SECTION C-C



SECTION B-B
SINGLE BOX ≤ 84"

GRATE DIMENSIONS AND QUANTITIES
IN ONE HEADWALL TYPE IV
BASED ON A 1 FOOT WIDTH, 1:4 SLOPE, AND NO SKEW

CULVERT HEIGHT	GRATES		BARS FOR ONE GRATE				HEADWALL GRATES (LBS.) *
	NUMBER REQUIRED	TYPE REQ'D.	BAR NO. 1		BAR NO. 2		
			BARS REQ'D.	LENGTH	BARS REQ'D.	LENGTH	
36"	6	B	2	W-0.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
42"	5	A	2	W-0.75	W-1.33 0.5 -1	2'-4 1/2"	18.3W - 22.4
	1	B	2	W-0.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
48"	8	B	2	W-0.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
54"	4	A	2	W-0.75	W-1.33 0.5 -1	2'-4 1/2"	18.3W - 22.4
	4	B	2	W-0.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
60"	10	B	2	W-0.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3

DIMENSIONS FOR "S" -- SLOPE 1:4
FOR VARIOUS CULVERT SIZES AND SKEWS

CULVERT HEIGHT	NO SKEW	≤ 10°	10° ≤ 20°	20° ≤ 30°
36"	14'-5 1/8"	14'-7 3/4"	15'-4 1/4"	16'-8"
42"	16'-10"	17'-1"	17'-11"	19'-5 1/4"
48"	18'-10 3/4"	19'-2 1/4"	20'-1 1/4"	21'-10"
54"	20'-11 1/2"	21'-3 3/8"	22'-3 3/8"	24'-2 3/8"
60"	23'-4 3/8"	23'-8 3/4"	24'-10 3/8"	26'-11 3/4"

GENERAL NOTES:

1. ALL TABLE DIMENSIONS AND QUANTITIES ARE FOR SINGLE BOX CULVERT HEADWALLS. TO ADAPT ANY OF THESE TABLES FOR DOUBLE BOX CULVERTS, DOUBLE THE NUMBER OF GRATES REQUIRED AND ADD AN ADDITIONAL WALL. (WALL THICKNESS SHALL BE SAME AS THE CENTER WALL THICKNESS OF THE BOX CULVERT)
2. FOR QUANTITY CALCULATIONS DIMENSION "W" SHALL BE MEASURED IN FEET.
3. QUANTITIES FOR SKEWED HEADWALLS NOT SHOWN.
4. PAY ITEMS ARE IDENTIFIED BY AN ASTERISK (*).
5. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).


APPROVED: *Paul Kovacs*
CHIEF ENGINEER DATE 6-1-2009

DATE	REVISIONS
6-1-2009	CHANGED SECTION B-B DIMENSION REVISED NOTES




STEEL GRATE FOR
HEADWALL TYPE IV
BOX CULVERT ≤ 84" WIDTH

STANDARD B21-01



DIMENSIONS AND QUANTITIES IN TWO WINGWALLS 1:4 SLOPE

PIPE-ARCH ELLIPTICAL PIPE (SPAN ≤ 77")	CIRCULAR PIPE (DIAMETER)	DIMENSIONS										CONC. HDWLS. CLASS SI CY. *	REINF. STEEL LBS. *
		H	L	S	T	U	A	E	B	C	D		
RISE ≤ 30"		3'-2"	12'-0"	12'-4 1/2"	2"	2'-8"	2'-2"	2'-2"	-	3	-	.98	171
RISE ≤ 36"		3'-8"	14'-0"	14'-5 1/8"	2"	2'-8"	2'-2"	2'-2"	-	4	-	1.33	211
RISE ≤ 42"		4'-3"	16'-4"	16'-10"	2"	3'-2"	2'-8"	2'-2"	4	-	-	1.78	285
RISE ≤ 48"		4'-9"	18'-4"	18'-10 3/4"	2"	3'-2"	2'-2"	2'-2"	-	6	-	2.23	333
RISE ≤ 54"	54"	5'-3"	20'-4"	20'-11 1/2"	2"	3'-6"	2'-2"	2'-2"	4	2	-	2.72	411
RISE ≤ 60"	60"	5'-10"	22'-8"	23'-4 3/4"	2"	3'-6"	2'-2"	2'-2"	-	8	-	3.36	504
	66"	6'-4"	24'-8"	25'-5 1/8"	2"	3'-6"	2'-2"	2'-2"	4	4	-	3.96	561



NOTE:
v BARS ARE TO BEGIN AT THE CULVERT END OF THE SLOPE HEADWALL





TABLE OF BARS IN ONE WINGWALL 1:4 SLOPE

NO. 4 REINFORCING BARS

H	MARK	TYPE	NO. REQ'D	LENGTH	a	b
3'-2"	4 h	STR.	4	11'-8"		
	4 v	2	5	5'-0"	2'-0"	3'-0"
	4 x	1	13	4'-4"	2'-2"	2'-2"
	4 w	1	1	4'-4"	2'-2"	2'-2"
3'-8"	4 h	STR.	4	13'-8"		
	4 v	2	7	5'-6"	2'-0"	3'-6"
	4 x	1	15	4'-4"	2'-2"	2'-2"
	4 w	1	1	4'-4"	2'-2"	2'-2"
4'-3"	4 h	STR.	5	16'-0"		
	4 v	2	10	6'-0"	1'-11"	4'-1"
	4 x	1	17	4'-4"	2'-2"	2'-2"
	4 w	1	1	4'-4"	2'-2"	2'-2"
4'-9"	4 h	STR.	5	18'-0"		
	4 v	2	12	6'-5"	1'-10"	4'-7"
	4 x	1	19	4'-4"	2'-2"	2'-2"
	4 w	1	1	4'-4"	2'-2"	2'-2"
5'-3"	4 h	STR.	6	20'-0"		
	4 v	2	14	6'-11"	1'-10"	5'-1"
	4 x	1	21	4'-4"	2'-2"	2'-2"
	4 w	1	1	4'-4"	2'-2"	2'-2"
5'-10"	4 h	STR.	7	22'-4"		
	4 v	2	16	7'-7"	1'-11"	5'-8"
	4 x	1	23	4'-4"	2'-2"	2'-2"
	4 w	1	1	4'-4"	2'-2"	2'-2"
6'-4"	4 h	STR.	7	24'-4"		
	4 v	2	18	8'-1"	1'-11"	6'-2"
	4 x	1	25	4'-4"	2'-2"	2'-2"
	4 w	1	1	4'-4"	2'-2"	2'-2"

TABLE OF BARS IN SLAB 1:4 SLOPE (PER FT. OF FLOOR SLAB WIDTH)

H	MARK	TYPE	NO. REQ'D	LENGTH	a	b	REINF. LBS. *	CY. CONC. *
3'-2"	4 h1	STR.	4	W-(0'-4")				
	4 v1	1	8	5'-0"	4'-4"	8"	52	.38
	4 n	1	1	4'-1"	2'-1"	2'-0"		
	4 w	STR.	1	12'-1"				
	4 t	STR.	14	W-(0'-4")				
3'-8"	4 h1	STR.	4	W-(0'-4")				
	4 v1	1	8	5'-6"	4'-10"	8"	58	.43
	4 n	1	1	4'-1"	2'-1"	2'-0"		
	4 w	STR.	1	13'-8"				
	4 t	STR.	18	W-(0'-4")				
4'-3"	4 h1	STR.	4	W-(0'-4")				
	4 v1	1	8	6'-1"	5'-5"	8"	65	.50
	4 n	1	1	4'-7"	2'-7"	2'-0"		
	4 w	STR.	1	16'-0"				
	4 t	STR.	20	W-(0'-4")				
4'-9"	4 h1	STR.	4	W-(0'-4")				
	4 v1	1	8	6'-7"	5'-11"	8"	88	.55
	4 n	1	1	4'-7"	2'-7"	2'-0"		
	4 w	STR.	1	18'-0"				
	4 t	STR.	22	W-(0'-4")				
5'-3"	4 h1	STR.	4	W-(0'-4")				
	4 v1	1	8	7'-1"	6'-5"	8"	76	.60
	4 n	1	1	4'-11"	2'-11"	2'-0"		
	4 w	STR.	1	20'-0"				
	4 t	STR.	24	W-(0'-4")				
5'-10"	4 h1	STR.	4	W-(0'-4")				
	4 v1	1	8	7'-8"	7'-0"	8"	82	.66
	4 n	1	1	4'-11"	2'-11"	2'-0"		
	4 w	STR.	1	22'-4"				
	4 t	STR.	26	W-(0'-4")				
6'-4"	4 h1	STR.	4	W-(0'-4")				
	4 v1	1	8	8'-2"	7'-6"	8"	87	.71
	4 n	1	1	4'-11"	2'-11"	2'-0"		
	4 w	STR.	1	24'-4"				
	4 t	STR.	28	W-(0'-4")				



- GENERAL NOTES:**
- TYPE 2 "v" BARS SHALL BE ORDERED FULL LENGTH, AND CUT IN THE FIELD. THE REMAINING PORTION OF THE "v" BARS SHALL BE USED IN THE OTHER WALL.
 - THE LONG LEG OF THE "n" BARS SHALL BE VERTICAL.
 - PAY ITEMS ARE IDENTIFIED BY AN ASTERISK (*).
 - SEE STANDARD B23 FOR GRATING DETAILS.
 - ALL CONCRETE SHALL BE CLASS SI.
 - ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).


DATE	REVISIONS
6-1-2009	CHANGED SECTION B-B DIMENSION
	REVISED NOTES




HEADWALL TYPE IV
PIPE & PIPE-ARCH CULVERT

STANDARD B22-01


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE: 6-1-2009



PLAN VIEW (NO SKEW)
SINGLE BOX CULVERT ≤ 84" WIDE




SECTION A-A
END TREATMENT - MULTIPLE OR SINGLE
BOX CULVERT




NOTE:
REINFORCEMENT BARS AND GRATE SPACING ARE
SIMILAR TO BOX CULVERT AT NORMAL (NO SKEW).


PLAN VIEW
SKEW ORIENTATION




GRATE DETAILS
(WITH SKEW)



GRATE DETAILS
(WITH SKEW)



SECTION C-C



SECTION B-B
SINGLE BOX ≤ 84"

GRATE DIMENSIONS AND QUANTITIES IN ONE HEADWALL TYPE IV
BASED ON A 1 FOOT WIDTH, 1:4 SLOPE AND SKEW

H	GRATES		BARS FOR ONE GRATE				HEADWALL GRATES (LBS.) *
	NUMBER REQUIRED	TYPE REQ'D.	BAR NO. 1 BARS REQ'D.	BAR NO. 1 LENGTH	BAR NO. 2 BARS REQ'D.	BAR NO. 2 LENGTH	
3'-2"	5	B	2	W-.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
3'-8"	6	B	2	W-.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
4'-3"	5	A	2	W-.75	W-1.33 0.5 -1	2'-4 1/2"	18.3W - 22.4
	1	B	2	W-.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
4'-9"	8	B	2	W-.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
5'-3"	4	A	2	W-.75	W-1.33 0.5 -1	2'-4 1/2"	18.3W - 22.4
	4	B	2	W-.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
5'-10"	10	B	2	W-.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3
6'-4"	4	A	2	W-.75	W-1.33 0.5 -1	2'-4 1/2"	18.3W - 22.4
	6	B	2	W-.75	W-1.33 0.5 -1	1'-10 1/2"	16.6W - 19.3

DIMENSIONS FOR "S" - SLOPE 1:4
FOR VARIOUS CULVERT SIZES AND SKEWS

H	NO SKEW	≤ 10°	10° ≤ 20°	20° ≤ 30°
3'-2"	12'-4 1/2"	12'-6 3/4"	13'-2"	14'-3 3/8"
3'-8"	14'-5 1/4"	14'-7 3/4"	15'-4 1/4"	16'-8"
4'-3"	16'-10"	17'-1"	17'-11"	19'-5 1/4"
4'-9"	18'-10 3/4"	19'-2 1/4"	20'-1 1/4"	21'-10"
5'-3"	20'-11 1/2"	21'-3 3/8"	22'-3 3/8"	24'-2 3/4"
5'-10"	23'-4 3/8"	23'-8 3/4"	24'-10 3/8"	26'-11 3/4"
6'-4"	25'-5 1/8"	25'-9 3/4"	27'-0 3/8"	29'-4 1/4"

GENERAL NOTES:


- ALL TABLE DIMENSIONS AND QUANTITIES ARE FOR SINGLE CULVERT HEADWALLS. TO ADAPT ANY OF THESE TABLES FOR DOUBLE CULVERTS, DOUBLE THE NUMBER OF GRATES REQUIRED AND ADD AN ADDITIONAL WALL. (WALL THICKNESS SHALL BE SAME AS THE CENTER WALL THICKNESS OF THE CULVERT.)
- FOR QUANTITY CALCULATIONS DIMENSION "W" SHALL BE MEASURED IN FEET.
- QUANTITIES FOR SKEWED HEADWALLS NOT SHOWN.
- PAY ITEMS ARE IDENTIFIED BY AN ASTERISK (*).
- ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).

DATE	REVISIONS
6-1-2009	CHANGED SECTION B-B DIMENSION REVISED NOTES




STEEL GRATE FOR
HEADWALL TYPE IV
PIPE & PIPE-ARCH CULVERTS
STANDARD B23-01


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009



DETAIL OF PIPE UNDERDRAIN, 6"
(NEW CONSTRUCTION OR WIDENING WITHOUT GUTTER)




DETAIL OF PIPE UNDERDRAIN, 6"
(NEW CONSTRUCTION OR WIDENING WITH GUTTER)




DETAIL OF PIPE UNDERDRAIN, 6" (MODIFIED)
(RUBBLIZED CONCRETE PAVEMENT)


MAXIMUM ALLOWABLE DRAINAGE DISTANCE TO OUTLET OR SEPARATION DISTANCE BETWEEN OUTLETS (SEE NOTE 11)	
ROADWAY PROFILE GRADE (%)	DISTANCE
≤ 1	250 FT.
BETWEEN 1 AND 2	375 FT.
≥ 2	500 FT. (NOTE 6)




RODENT SHIELD PLACEMENT




SECTION A-A




DETAIL OF RODENT SHIELD



DETAIL OF PIPE UNDERDRAIN OUTLETS
(SEE NOTE 8)



FILTER FABRIC ENVELOPE
(NEW CONSTRUCTION OR WIDENING)



FILTER FABRIC ENVELOPE
(RUBBLIZED CONCRETE PAVEMENT)

NOTES FOR PIPE UNDERDRAIN

- FOR NEW CONSTRUCTION WITH A GUTTER AT THE EDGE OF SHOULDER THE PROPOSED PIPE UNDERDRAIN SHALL BE LOCATED UNDER THE GUTTER AS SHOWN. FOR NEW CONSTRUCTION WITHOUT A GUTTER THE PROPOSED PIPE UNDERDRAIN SHALL BE AT THE EDGE OF PAVEMENT WITH A DIMENSION OF 6". FOR RUBBLIZED PAVEMENT THE DISTANCE SHALL BE 6".
- FOR NEW CONSTRUCTION OR WIDENING PROJECTS, THE PIPE UNDERDRAIN INSTALLATION SHALL OCCUR AFTER SUBGRADE HAS BEEN PREPARED AND AFTER LIFT OF PGE BASE IS PLACED AND BEFORE 3" AND VARIES CA-6 CAPPING STONE IS PLACED. FOR PAVEMENT RUBBLIZATION PROJECTS, THE PIPE UNDERDRAIN SHALL BE INSTALLED PRIOR TO RUBBLIZATION.
- SUBGRADE AGGREGATE SHALL CONSIST OF A 3" AND VARIES CA-6 CAP ABOVE A PGE BASE, THICKNESS AS NOTED IN THE PLANS.
- ON SUPERELEVATED CURVES PLACE LONGITUDINAL UNDERDRAIN ON LOW SIDE ONLY.
- IN AREAS WHERE ROADWAY LONGITUDINAL GRADE IS LESS THAN 0.3%, DIMENSION WILL INCREASE AS NECESSARY TO MAINTAIN MINIMUM 0.3% SLOPE IN PIPE UNDERDRAIN.
- IF 500' MAXIMUM DISTANCE IS EXCEEDED, PIPE UNDERDRAIN SHALL BE INCREASED TO 8" DIAMETER AND TRENCH WIDTH INCREASED TO 16".
- AT OUTLET LOCATIONS, PIPE UNDERDRAINS SHALL SEPARATE SUFFICIENTLY TO PROVIDE SPACE FOR TWO END SECTIONS, OR TWO PIPES CAN RUN PARALLEL INTO A LARGER HEADWALL.
- IN AREAS WHERE A CLOSED DRAINAGE SYSTEM EXISTS, THE PIPE UNDERDRAIN, 6" (SPECIAL) SHALL DRAIN TO THE NEAREST CATCH BASIN. THE UPPER END OF A RUN ON GRADE SHALL ALSO BE CONNECTED TO A CATCH BASIN TO BE USED AS A CLEANOUT.
- THE OUTLET END OF THE SUBDRAIN SHALL BE PROTECTED BY A PERMANENT RODENT SHIELD. THE RODENT SHIELD SHALL HAVE THE CONFIGURATION SHOWN AND BE CONSTRUCTED FROM HOT DIP GALVANIZED STEEL INDUSTRIAL WIRE CLOTH 3x3 MESH, 0.063"x0.063" WIRE SIZE IN ACCORDANCE WITH AASHTO M232 (ASTM A153). THE COST OF THE RODENT SHIELD IS INCLUDED IN CLASS S1 CONCRETE.
- FOR RUBBLIZATION PROJECTS, ADDITIONAL EROSION CONTROL MEASURES MAY BE NECESSARY AT THE BASE OF THE HEADWALL.
- FOR RUBBLIZATION PROJECTS, MAXIMUM DISTANCE SHALL BE 250 FT. REGARDLESS OF ROADWAY PROFILE.
- TRENCH FOR PIPE UNDERDRAIN 6" (SPECIAL) FOR RUBBLIZATION PROJECTS SHALL BE BACKFILLED WITH CA-6.
- BOTTOM OF SUBGRADE SLOPE SHALL MATCH PAVEMENT SLOPE OF OUTSIDE LANE, BUT SHALL NOT BE LESS THAN 1%.








APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-1-2009

DATE	REVISIONS
6-1-09	CHANGES TO PIPE UNDERDRAIN, 6" (MODIFIED) DETAIL



PIPE UNDERDRAINS

STANDARD B24-01



SECTION A-A
CAST FRAME

SECTION D-D

CAST GRATE

NOTES:

1. ALL FRAMES AND GRATES SHALL CONFORM TO THE REQUIREMENTS OF ART. 1006.14 FOR GRAY IRON CASTINGS AND TO ART. 1006.15 FOR DUCTILE IRON CASTINGS.
2. FRAME AND GRATE TO BE NEENAH FOUNDRY COMPANY, NEENAH NO. R-3528-V OR APPROVED EQUAL.
3. GRATE SHALL NOT BE BOLTED TO FRAME.




APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-30-2008

DATE	REVISIONS

Illinois Tollway
Open Roads for a Faster Future

FRAME AND GRATE
TYPE 20A


STANDARD B25-00




DATE	REVISIONS

FRAME AND GRATE
TYPE 21A


STANDARD B26-00




TOP VIEW




FRONT VIEW




SECTION E-E




DETAIL OF VANES



SECTION C-C



SECTION D-D



TOP VIEW

CAST GRATE

CURB BOX

NOTES:

1. ALL FRAMES AND GRATES SHALL CONFORM TO THE REQUIREMENTS OF ART. 1006.14 FOR GRAY IRON CASTINGS AND TO ART. 1006.15 FOR DUCTILE IRON CASTINGS.
2. FRAME AND GRATE TO BE NEENAH FOUNDRY COMPANY, NEENAH NO. R-3527-VF OR APPROVED EQUAL.
3. GRATE SHALL NOT BE BOLTED TO FRAME.
4. CURB BOX SHALL BE BOLTED TO FRAME WITH 5/8" GALVANIZED HEX. HD. BOLT AND NUT WITH GALV. WASHERS.
5. CURB BOXES SHALL ONLY BE USED AT SAG LOCATIONS.

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-30-2008




FRAME AND GRATE
TYPE 21A

STANDARD B26-00


9/16" X 1"
CORED SLOTS
FOR GRATE
ALIGNMENT
(2 REQ'D
PER FRAME)

22 1/2" X 3/4" X 1" SAFETY BAR
(2 REQ'D) (SHOWN IN TOP
VIEW ONLY)




FRAMES BOLTED TOGETHER w/
(3) 5/8-11 X 3 GALV. HEX. HD.
BOLT AND NUT w/ GALV. WASHERS

TOP VIEW



SECTION B-B



SECTION A-A




DATE	REVISIONS


FRAME AND GRATE
TYPE 22A

STANDARD B27-00


APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-30-2008



DETAIL OF VANES



SECTION C-C



SECTION D-D

TOP VIEW

CAST GRATE
(2 REQ'D)

NOTES:


1. ALL FRAMES AND GRATES SHALL CONFORM TO THE REQUIREMENTS OF ART. 1006.14 FOR GRAY IRON CASTINGS AND TO ART. 1006.15 FOR DUCTILE IRON CASTINGS.
2. FRAME AND GRATE TO BE NEENAH FOUNDRY COMPANY, NEENAH NO. R-3529-V OR APPROVED EQUAL.
3. GRATE SHALL NOT BE BOLTED TO FRAME.

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 6-30-2008


Illinois Tollway
Open Roads for a Faster Future

FRAME AND GRATE
TYPE 22A


STANDARD B27-00



PLAN



SECTION A-A



SECTION B-B

TYPE G-3 GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T1 (SPECIAL)


NOTE:
GUTTER TRANSITIONS WILL BE PAID FOR PER FOOT AS TYPE G-3 GUTTER.




REVISIONS	
1-1-2011	REVISED GUTTER TRANSITION TERMINATION

GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T1 (SPECIAL)
STANDARD B28-01


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 3-1-2010



PLAN



SECTION A-A



SECTION B-B

NOTE:
GUTTER TRANSITIONS WILL BE PAID FOR PER FOOT AS TYPE G-2 GUTTER.









GUTTER TRANSITION AT
TRAFFIC BARRIER TERMINAL,
TYPE T1 (SPECIAL)

STANDARD B28-01

TYPE G-2 GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T1 (SPECIAL)

Paul Kovacs
APPROVED..... CHIEF ENGINEER..... DATE 3-1-2010




NOTE:
GUTTER TRANSITIONS WILL BE PAID FOR PER FOOT AS TYPE G-3 GUTTER.




TYPE G-3 GUTTER TRANSITION TERMINATION AT TRAFFIC BARRIER TERMINAL, TYPE T1 (SPECIAL)

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 3-1-2010


GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T1 (SPECIAL)
STANDARD B28-01



PLAN



SECTION A-A



SECTION B-B

NOTE:
GUTTER TRANSITIONS WILL BE PAID FOR PER FOOT AS TYPE G-2 GUTTER.

TYPE G-2 GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T1-A (SPECIAL)


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 1-1-2011

REVISIONS



Illinois Tollway
Open Roads for a Faster Future

GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T1-A (SPECIAL)


STANDARD B29-00



SECTION B-B



FRONT ELEVATION



PLAN




TABLE OF BARS IN ONE HEADWALL

PIPE DIA.	REINFORCING BARS				
	MARK	NO. & SIZE	LENGTH	a	b
15"	h	1-#4	8'-3"	1'-11"	3'-2"
	v	11-#4	2'-4"	0'-10"	1'-6"
18"	h1	1-#4	8'-6"	2'-2"	3'-2"
	v1	11-#4	2'-7"	1'-1"	1'-6"
24"	h2	1-#4	11'-0"	2'-10"	4'-1"
	v2	14-#4	2'-10"	1'-4"	1'-6"
30"	h3	1-#4	13'-0"	3'-4"	4'-10"
	v3	17-#4	3'-1"	1'-7"	1'-6"
36"	h4	1-#4	15'-6"	4'-0"	5'-9"
	v4	20-#4	3'-4"	1'-10"	1'-6"

TABLE OF DIMENSIONS AND QUANTITIES

DESIGN NO.	INSIDE DIA. OF PIPE	SLOPE OF FILL	DIMENSIONS						CL. SI CONC. 2 HDWLS.	REINF. BARS. 2 HDWLS.
			A	B	C	D	E	F		
D-15-2	15"	Δ1:3	2'-2"	10"	1'-11"	2'-0"	6'-7 1/2"	3'-3 1/4"	1.2 C.Y.	60 #
D-18-2	18"	Δ1:3	2'-2"	1'-1"	2'-2"	2'-3"	6'-10 1/2"	3'-3 1/4"	1.3 C.Y.	60 #
D-24-2	24"	Δ1:3	2'-10"	1'-4"	2'-9"	2'-11"	8'-10 1/2"	4'-2 1/2"	2.0 C.Y.	70 #
D-30-2	30"	Δ1:3	3'-4"	1'-7"	3'-3"	3'-5"	10'-4 1/2"	4'-11"	2.6 C.Y.	80 #
D-36-2	36"	Δ1:3	4'-0"	1'-10"	3'-10"	4'-1"	12'-4 1/2"	5'-10 1/2"	3.5 C.Y.	100 #

NOTES:

1. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
2. BAR BENDING DETAILS ARE DIMENSIONED OUT TO OUT OF BARS.
3. ALL EXPOSED EDGES SHALL HAVE A 3/4"-45° CHAMFER. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW THE FINISHED GROUND LINE.
4. CARE SHALL BE EXERCISED IN REMOVING ANY LENGTH OF EXISTING PIPE SO THE REMAINING PIPE IS UNDAMAGED AND FULLY FUNCTIONING.
5. THE STATION, OFFSET AND INVERT ELEVATION FOR THE HEADWALL SHALL APPLY AT THE END OF THE CONNECTING PIPE OPENING.
6. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT.
7. TYPES I AND II HEADWALLS TO BE USED ONLY IN SLOPE STEEPER THAN 1:3.




DATE	REVISIONS



HEADWALLS
TYPE I AND II
STANDARD B30-00

HEADWALL - TYPE I
(PIPE DIAMETER ≤ 36")

APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE: 1-1-2011



SECTION A-A




FRONT ELEVATION

TABLE OF BARS IN ONE HEADWALL


BAR		42" PIPE				48" PIPE				54" PIPE				60" PIPE			
MARK	TYPE	NO. & SIZE	LENGTH	a	b	NO. & SIZE	LENGTH	a	b	NO. & SIZE	LENGTH	a	b	NO. & SIZE	LENGTH	a	b
b	STRAIGHT	2-#5	6'-3"	---	---	2-#5	6'-9"	---	---	2-#5	7'-3"	---	---	2-#5	8'-0"	---	---
b1	STRAIGHT	2-#4	13'-6"	---	---	2-#4	15'-3"	---	---	2-#4	17'-0"	---	---	2-#4	18'-9"	---	---
b2	STRAIGHT	1-#4	11'-3"	---	---	1-#4	13'-0"	---	---	1-#4	14'-9"	---	---	1-#4	16'-6"	---	---
b3	STRAIGHT	1-#4	8'-3"	---	---	1-#4	10'-0"	---	---	1-#4	11'-9"	---	---	1-#4	13'-6"	---	---
b4	STRAIGHT	---	---	---	---	---	---	---	---	1-#4	8'-9"	---	---	1-#4	10'-6"	---	---
d	1	9-#4	4'-3"	2'-2"	2'-1"	10-#4	4'-3"	2'-2"	2'-1"	12-#4	4'-3"	2'-2"	2'-1"	13-#4	4'-3"	2'-2"	2'-1"
h	2	2-#5	18'-0"	4'-8"	6'-8"	2-#5	20'-3"	5'-3"	7'-6"	2-#5	22'-6"	5'-10"	8'-4"	2-#5	25'-0"	6'-6"	9'-3"
h1	STRAIGHT	4-#4	6'-3"	---	---	4-#4	7'-3"	---	---	4-#4	8'-0"	---	---	4-#4	8'-9"	---	---
v	1	2-#5	6'-6"	4'-6"	2'-0"	2-#5	7'-0"	5'-0"	2'-0"	2-#5	7'-6"	5'-6"	2'-0"	4-#5	8'-0"	6'-0"	2'-0"
v1	1	2-#5	6'-0"	4'-0"	2'-0"	4-#5	6'-6"	4'-6"	2'-0"	4-#5	7'-0"	5'-0"	2'-0"	2-#5	7'-6"	5'-6"	2'-0"
v2	1	4-#5	5'-6"	3'-6"	2'-0"	2-#5	6'-0"	4'-0"	2'-0"	2-#5	6'-6"	4'-6"	2'-0"	2-#5	7'-0"	5'-0"	2'-0"
v3	1	2-#5	5'-0"	3'-0"	2'-0"	2-#5	5'-6"	3'-6"	2'-0"	2-#5	6'-0"	4'-0"	2'-0"	4-#5	6'-6"	4'-6"	2'-0"
v4	1	2-#5	4'-6"	2'-6"	2'-0"	4-#5	5'-0"	3'-0"	2'-0"	4-#5	5'-6"	3'-6"	2'-0"	2-#5	6'-0"	4'-0"	2'-0"
v5	1	---	---	---	---	---	---	---	---	2-#5	5'-0"	3'-0"	2'-0"	4-#5	5'-6"	3'-6"	2'-0"
w	STRAIGHT	2-#4	5'-0"	---	---	2-#4	5'-9"	---	---	2-#4	6'-6"	---	---	2-#4	7'-6"	---	---

TABLE OF DIMENSIONS AND QUANTITIES


DESIGN NO.	INSIDE DIA. OF PIPE	SLOPE OF FILL	DIMENSIONS						CL. SP CONC. 2 HDWLS.	REINF. BARS. 2 HDWLS.
			A	B	C	D	E	F		
D-42-2	42"	Δ1:3	4'-5"	2'-2"	4'-4 1/2"	4'-10"	4'-0 1/2"	6'-8 1/4"	6.2 C.Y.	400 #
D-48-2	48"	Δ1:3	5'-0"	2'-5"	4'-11"	5'-5"	15'-9 1/2"	7'-4 1/4"	7.6 C.Y.	450 #
D-54-2	54"	Δ1:3	5'-7"	2'-8"	5'-5 1/2"	6'-0"	17'-6 1/2"	8'-2"	9.2 C.Y.	550 #
D-60-2	60"	Δ1:3	6'-2"	2'-11"	6'-0"	6'-7"	19'-3 1/2"	9'-0"	10.8 C.Y.	630 #



PLAN



TYPE 1



TYPE 2

HEADWALL - TYPE II

(PIPE DIAMETER > 36")

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 1-1-2011



HEADWALLS TYPE I AND II

STANDARD B30-00