


Illinois Tollway Standard Drawing Revisions
--


Section C		Guardrail / Median Barrier	Effective: 03-31-2016
Standard	Modification Summary		
All	The electronic (pdf) version of the Standard Drawing are now made searchable (text).		
C1	Galvanized Steel Plate Beam Guardrail		
Sheet 1	Notes 5 & 7. Clarified aggregate shoulder width.		
	Revised aggregate shoulder at shoulder point on sections to match base sheets. Added cut section with gutter.		
Sheet 2	Removed Wood Post column in Table 1, since it's not applicable. Corrected equation for > 28 1/8" depth.		
Sheet 3	Included notes into Leave Out details.		
Sheet 4	Clarified notes for use of detail with other underground conflicts.		
	Added Minimum Barrier Clearance Distances (MASH) to be used after 2017 to Table 2.		
C3	Single Face Reinforced Concrete Barrier		
	Added maximum exposure depth for base. Revised expansion joint sealant note to match structure detail.		
	Removed backer rod from sides and beneath base.		
C4	Concrete Shoulder Barrier Transition Type F		
	Revised expansion joint sealant note to match structure detail. Removed backer rod from sides and beneath base.		
	Referenced Standards C3, C9, & C10. Removed expansion joint detail.		
	Note 10. Revised minimum expansion joint spacing from 27' to 25'.		
C5	Concrete Barrier Base, and Concrete Barrier, Double Face, 42" and Variable Height		
	Deleted previous Notes 2. & 5 and renumbered Notes. Re-arranged sections.		
C6	Shoulder Widening for Traffic Barrier Terminal, Type T1 (Special) Tangent		
	Deleted Sheet 3. Incorporated Gutter, Type G-2 into Sheet 2.		
	Note 2. Added reference to minimum offset to rail.		
	Note 6. Incorporated tangent and curved section notes into note 6.		
	Revised Aggregate Shoulder in section to match base sheets. Revised Recovery Area so that 90' starts at Post 1.		
	Removed minimum rail offset dimension in plan view.		
C7	Traffic Barrier Terminal, Type T2		
	Revised Aggregate Shoulder in sections to match base sheets. Added edge of paved shoulder and shoulder point line to plan views.		
Sheet 3	Revised pipe diameter to 2" in Wood Post Detail		
C9	Traffic Barrier Terminal, Type T6		
	Revised Aggregate Shoulder in sections to match base sheets. Added shoulder point line to plan views.		
C10	Traffic Barrier Terminal, Type T6B		
	Revised Aggregate Shoulder in sections to match base sheets. Added shoulder point line to plan view.		
C11	Traffic Barrier Terminal, Type T10		
	Revised Flared Wing angle from 15° to 20° (minimum), deleted note previously associated with it, and deleted 2' dimension		
C12	Shoulder Widening for Traffic Barrier Terminal, Type T1-A (Special) Tangent		
	Note 3. Added reference to minimum offset to rail.		
	Note 7. Incorporated tangent and curved section notes into note 7.		
	Revised Aggregate Shoulder in sections to match base sheets. Revised Recovery Area so 65' starts at Post 1.		
	Removed minimum rail offset dimension in plan views. Removed Gutter, Type G-3 Row in Table 1.		
C13	Concrete Median Barrier Transition, Type V-F at Bridge Piers		
	Combined Notes 1 & 2 and renumbered Notes.		
	Note 3 (former Note 4). Revised expansion joint sealant note to match structure detail.		
	Removed Tie Bars in Section D-D. Removed backer rod from sides and beneath base in Section A-A.		
C14	Concrete Median Barrier Transition, Type V at Bridge Piers		
	Aligned Plan and Elevation views. Added ditch to Elevation view. Re-arranged Notes and Sections.		

 New Sheet


 Retired Standard



FILL SECTION WITH GUTTER



CUT SECTION WITH GUTTER



SECTION WITHOUT GUTTER

GUARDRAIL INSTALLATION DETAILS

NOTES:

1. 1'-0" OFFSET FROM EDGE OF PAVED SHOULDER TO FACE OF RAIL IS TYPICAL FOR ALL INSTALLATIONS WITHOUT GUTTER EXCEPT AS OTHERWISE DETAILED IN THE PLAN DRAWINGS.
2. WHERE GUTTERS SUCH AS TYPE G-2, G-3 ARE REQUIRED IN FRONT OF THE GUARDRAIL, THE POSTS SHALL BE LOCATED 6" BEHIND THE GUTTER, OR AS OTHERWISE DETAILED IN THE PLANS. THE OFFSET FROM THE EDGE OF SHOULDER TO THE FACE OF THE GUARDRAIL SHALL BE AS SHOWN ON STANDARD B28.
3. THE 24 7/8" TYPICAL RAIL HEIGHT IS MEASURED FROM EXISTING SURFACE 1'-0" IN FRONT OF RAIL, OR FROM EDGE OF SHOULDER/EDGE OF GUTTER WHEN EDGE IS MORE THAN 1'-0" IN FRONT OF RAIL TO CENTER OF RAIL.
4. AGGREGATE SHOULDERS SPECIAL, TYPE C SHALL COMPLY WITH THE REQUIREMENTS OF THE ILLINOIS TOLLWAY RECURRING SPECIAL PROVISION. WHERE GUTTER IS PROPOSED WITH GUARDRAIL, A 6" MINIMUM THICKNESS OF AGGREGATE SHOULDERS SPECIAL, TYPE C SHALL BE PLACED BEHIND GUTTER. FOR GUARDRAIL WITHOUT GUTTER, AGGREGATE SHOULDER, TYPE C, OF THE SAME THICKNESS AS PAVED SHOULDER SHALL BE PLACED FROM THE EDGE OF PAVED SHOULDER SLOPING AWAY TO A 6" MIN. THICKNESS.
5. AGGREGATE SHOULDERS SPECIAL, TYPE C SHALL EXTEND A MINIMUM OF 1'-0" BEHIND GUARDRAIL POST, EXCEPT AS DETAILED ELSEWHERE IN THE PLANS.
6. PLASTIC BLOCK-OUTS SHALL NOT BE ALLOWED AS A SUBSTITUTE FOR WOOD BLOCK-OUTS ON NEW INSTALLATIONS.
7. WHEN $S \leq 3$ AND 3'-0" MIN. AGGREGATE SHOULDER WIDTH CANNOT BE MET, THE POST LENGTH SHALL BE 9'-0" AND THE AGGREGATE SHOULDER WIDTH SHALL BE 1'-0" MIN. BEHIND THE POST TO THE SHOULDER POINT.
8. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENTS (V:H).
9. UNDER NO CIRCUMSTANCES SHALL AN EXISTING GUARDRAIL, THAT WAS DESIGNED USING A PREVIOUS STANDARD, BE EXTENDED, ATTACHED TO OR MODIFIED IN ANYWAY FROM ITS ORIGINAL DESIGN. IF ANY MODIFICATION IS REQUIRED AND A PROPER BARRIER WARRANT HAS BEEN COMPLETED, THE ENTIRE BARRIER INSTALLATION SHALL BE COMPLETELY REMOVED AND REPLACED WITH A NEW SYSTEM THAT CONFORMS TO THE CURRENT STANDARD.
10. WHEN $S \leq 3$, THE POST LENGTH SHALL BE 9'-0" AND 4'-0" AGGREGATE SHOULDER WIDTH MAINTAINED.
11. THE GUARDRAIL SYSTEM HAS BEEN PERFORMANCE-TESTED FOR CRASHWORTHINESS UNDER PROCEDURES DEFINED IN THE NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM (NCHRP) REPORT 350. NO MODIFICATION TO THIS STANDARD DRAWING SHALL BE PERMITTED.
12. GUARDRAIL POSTS SHALL NOT BE INSTALLED IN CONCRETE OR ASPHALT PAVEMENT. WHEN NECESSARY USE LEAVE-OUT DETAIL ON SHEET 4 OF 4 OF THIS SERIES.
13. GUARDRAIL POSTS SHALL NOT BE ATTACHED TO ANY STRUCTURE.




GALVANIZED STEEL PLATE
BEAM GUARDRAIL

DATE	REVISIONS
11-01-12	MODIFIED AGGREGATE SHOULDERS
03-31-14	REMOVED SECONDARY HOLE FROM POST AND UPDATED NOTES.
03-31-16	ADDED SECTION, REV'D SHLDR

STANDARD C1-08


APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 5-1-2009



ELEVATION

TYPE A


6'-3" TYPICAL POST SPACING



ELEVATION

TYPE B

3'-1 1/2" 1/2 POST SPACING




ELEVATION

TYPE C


1'-6 3/4" 1/4 POST SPACING

TABLE 1		
V	W	L
0 - 16 1/8"	24"	21"
> 16 1/8" - 28 1/8"	12"	8"
> 28 1/8" - 40 1/8"	12" - 0 (*)	8"

* V + W = 40 1/8"




PLAN




ELEVATION

FOOTING FOR POST WHEN IMPERVIOUS MATERIAL IS ENCOUNTERED




NOTES:
ALL HOLES 3/4" DIA.

WOOD BLOCK-OUT AND STEEL POST DETAILS




APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 5-1-2009


GALVANIZED STEEL PLATE BEAM GUARDRAIL
STANDARD C1-08




RAIL ELEMENT SPLICE




POST OR SPLICE BOLT & NUT



STEEL POST CONSTRUCTION



PLAN




ELEVATION

LEAVE-OUTS


† THE AREA AROUND THE POST THAT IS EITHER OMITTED FROM THE NEW CONSTRUCTION OR REMOVED FROM THE EXISTING CONCRETE OR ASPHALT.



TABLE 2			
BARRIER CLEARANCE DISTANCE			
GUARDRAIL SYSTEM	POST SPACING	MINIMUM BARRIER CLEARANCE DISTANCE	
		CURRENT	CONST. AFTER 2017
TYPE A	6'-3"	28"	39"
TYPE B 1/2 POST SPACING	3'-1 1/2"	23"	34"
TYPE C 1/4 POST SPACING	1'-6 3/4"	14"	26"



TRANSITION TO 1/2-POST SPACING




TRANSITION TO 1/4-POST SPACING

** WHEN LENGTH OF OBSTACLES IS 1'-3" OR LESS, THE DOWNSTREAM TRANSITION SHALL BE OMITTED.


POST SPACING TRANSITIONS

NOTE: NO MODIFICATIONS OF ANY KIND TO THE TRANSITION POST SPACING ARE ALLOWED.

APPROVED: *Paul Kovacs* DATE 5-1-2009
CHIEF ENGINEER



TYPE A GUARDRAIL-DRAINAGE STRUCTURE CONFLICT
ONE POST



TYPE A GUARDRAIL - DRAINAGE STRUCTURE CONFLICT
TWO POSTS

DRAINAGE STRUCTURE CONFLICTS

NOTES:

- GUARDRAIL POSTS SHALL NOT BE ELIMINATED; ALL POSTS MUST BE USED. POSTS ADJACENT TO REPOSITIONED POSTS MAY NEED TO BE MOVED TO KEEP 3'-1 1/2" MINIMUM SPACING.
- GUARDRAIL POSTS SHALL NOT BE SET BACK TO AVOID CONFLICTS WITH A DRAINAGE STRUCTURE.
- THIS DETAIL ALSO APPLIES TO OTHER UNDERGROUND CONFLICTS.



RESERVED



APPROVED CHIEF ENGINEER DATE

DATE	REVISIONS




RESERVED


STANDARD C2-00




PLAN
REINFORCEMENT AROUND
DRAINAGE STRUCTURE




TYPE F BARRIER
SECTION A-A



TYPE F BARRIER
EXPANSION JOINT
SECTION B-B



BENDING DIAGRAMS



EXPANSION JOINT

NOTES:

- TOP SHOULDER EDGE OF BARRIER BASE GUTTER SHALL MATCH THE TOP OF SHOULDER ELEVATION.
- 1" DEEP CONTRACTION JOINTS SHALL BE CONSTRUCTED IN BOTH THE REINFORCED CONCRETE BARRIER WALL AND BASE. CONTRACTION JOINTS SHALL ALSO BE CONSTRUCTED AT BOTH SIDES OF ALL DRAINAGE STRUCTURES. MAXIMUM CONTRACTION JOINT SPACING SHALL BE 30'-0".
- THE FORMING OF CONTRACTION JOINTS SHALL BE DONE WITH AN APPROVED FINISHING TOOL OR BY SAWING SUBJECT TO THE SATISFACTORY CONTROL OF CRACKING.
- REINFORCEMENT BARS DESIGNATED "(E)" SHALL BE EPOXY COATED.
- REINFORCEMENT BARS BENDING DETAILS SHALL BE IN ACCORDANCE WITH THE "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES", ACI 315, LATEST EDITION.
- REINFORCEMENT BARS BENDING DIMENSIONS ARE OUT TO OUT.
- AT DRAINAGE STRUCTURES, CUT FOOTING BARS TO FIT. ADD AN ADDITIONAL SET OF d, d1, t, AND +1 BARS ON EACH SIDE OF THE DRAINAGE STRUCTURE.
- EXPANSION JOINTS SHALL BE CONSTRUCTED IN BARRIER WALL AT MAXIMUM JOINT SPACING OF 90'-0". SEE SECTION B-B FOR DETAILS.
- MINIMUM LENGTH OF INSTALLATION SHALL BE 25'-0".
- MINIMUM EXPANSION JOINT SPACING SHALL BE 25'-0".


DATE	REVISIONS
11-01-12	GUTTER TRANS. TAPER DET. NEW JOINT DET., REV. NOTES
10-01-13	REVISED REINFORCEMENT BARS AND GUTTER WIDTH
03-31-14	REDESIGNED FOR TL-4 LOADING
3-11-2015	REVISED BENDING DIAGRAM
3-31-2016	ADDED MAX. EXPOSED BASE, REVISED EXP. JT. NOTE




SINGLE FACE REINFORCED CONCRETE BARRIER

STANDARD C3-06


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 2-7-2012



SECTION C-C



SECTION B-B



SECTION A-A

** CUT TO FIT IN FIELD
2" VERTICAL CLR.

BENDING DIAGRAMS


#6 d(E) BAR

#6 + (E) BARS @ 6"


#4 d1(E) BAR

NOTES:

1. TAPER LENGTH REQUIRED FOR THE WIDTH TRANSITION WILL BE 25'-0" MINIMUM. INCREASE TAPER RATE AS REQUIRED TO OBTAIN THE LENGTH OF 25'-0".
2. TOP SHOULDER EDGE OF BARRIER BASE GUTTER SHALL MATCH THE TOP OF SHOULDER ELEVATION.
3. 1" DEEP CONTRACTION JOINTS SHALL BE CONSTRUCTED IN BOTH THE REINFORCED CONCRETE BARRIER WALL AND BASE. CONTRACTION JOINTS SHALL ALSO BE CONSTRUCTED AT BOTH SIDES OF ALL DRAINAGE STRUCTURES. MAXIMUM CONTRACTION JOINT SPACING SHALL BE 30'-0".
4. THE FORMING OF CONTRACTION JOINTS SHALL BE DONE WITH AN APPROVED FINISHING TOOL OR BY SAWING SUBJECT TO THE SATISFACTORY CONTROL OF CRACKING.
5. REINFORCEMENT BARS DESIGNATED "E" SHALL BE EPOXY COATED.
6. REINFORCEMENT BARS BENDING DETAILS SHALL BE IN ACCORDANCE WITH THE "MANUAL OF STANDARD PRACTICES FOR DETAILING REINFORCED CONCRETE STRUCTURES", ACI 315, LATEST EDITION.
7. REINFORCEMENT BARS BENDING DIMENSIONS ARE OUT TO OUT.
8. TYPE F BARRIER SHALL BE USED WITH ALL NEW CONSTRUCTION, OR RECONSTRUCTION OF EXISTING BARRIERS.
9. E.F. DENOTES EACH FACE
10. MINIMUM EXPANSION JOINT SPACING SHALL BE 25'-0".




PLAN



ELEVATION

CONCRETE SHOULDER BARRIER TRANSITION, TYPE F



SECTION D-D


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 2-7-2012

DATE	REVISIONS
11-01-12	GUTTER TRANS. TAPER DET. NEW JOINT DET., REV. NOTES
10-01-13	REVISED REINFORCEMENT BARS AND GUTTER WIDTH
3-31-14	REDESIGNED FOR TL-4 LOADING
3-11-2015	MODIFIED PREFORMED JOINT FILLER DETAIL
3-31-2016	REVISED SECT. B-B TO D-D




CONCRETE SHOULDER BARRIER TRANSITION TYPE F


STANDARD C4-06



CONCRETE BARRIER, DOUBLE FACE, 42"
CONCRETE BARRIER BASE, 7'-0"



CONCRETE BARRIER, DOUBLE FACE, VARIABLE HEIGHT
CONCRETE BARRIER BASE, VARIABLE HEIGHT, 7'-0"
(BARRIER HEIGHT VERTICAL DIFFERENTIAL VARIES 0" TO 3")



CONCRETE BARRIER, DOUBLE FACE, VARIABLE HEIGHT
CONCRETE BARRIER BASE, 5'-0"
(BARRIER HEIGHT VERTICAL DIFFERENTIAL VARIES 3" TO 9")
* WHEN 6" OR GREATER ADD TOP TIE BAR.

NOTES:

- 2" DEEP CONTRACTION JOINTS SHALL BE DONE BY SAWING AND SHALL BE CONSTRUCTED IN THE CONCRETE BARRIER WALL, CONCRETE BARRIER BASE, AND CONCRETE GUTTER (SPECIAL). CONTRACTION JOINTS SHALL ALSO BE CONSTRUCTED AT BOTH SIDES OF ALL DRAINAGE STRUCTURES. MAXIMUM CONTRACTION JOINT SPACING SHALL BE 30'-0". THE MINIMUM DISTANCE BETWEEN CONTRACTION JOINTS IN THE MEDIAN BARRIER WALL SHALL BE 2'-0". WHEN A DRAINAGE STRUCTURE FALLS WITHIN 2'-0" FROM AN EXPANSION JOINT (OR) CONTRACTION JOINT, THE NEAREST CONTRACTION JOINT SHALL BE OMITTED.
- GUTTER PROFILE IN THE VICINITY OF SAG VERTICAL CURVES, ALONG FLAT GRADES AND AT THE MEETING OF PROPOSED AND EXISTING GUTTER, SHALL BE CAREFULLY CONTROLLED AND FIELD ADJUSTED IF NECESSARY TO ENSURE POSITIVE DRAINAGE AND AVOID PONDING.
- IN AREAS OF RELATIVELY FLAT LONGITUDINAL PROFILE GRADES, THE 3" VERTICAL DIMENSION AT THE BOTTOM OF THE BARRIER CAN VARY FROM 2" TO 3 1/4" TO CREATE AN ACCEPTABLE LONGITUDINAL GRADE IN THE GUTTER.
- REFERENCE PLAN SHEET FOR TYPE, SIZE AND NUMBER OF CONDUITS. PROVIDE 1/2" (MIN.) CLEARANCE TO THE TOP OF CONDUIT AND 2" (MIN.) CLEARANCE TO THE BOTTOM OF THE CONDUIT.
- WHEN VARIABLE HEIGHT VERTICAL DIFFERENTIAL EXCEEDS 9" SEE STRUCTURAL PLANS FOR DETAILS.
- GUTTER SLOPE SHALL BE 4.17% SLOPED TOWARD THE MEDIAN UNLESS OTHERWISE NOTED. GUTTER SLOPE IS REVERSE PITCHED IN SUPERELEVATED SECTIONS. TRANSITION GUTTER SLOPE OVER 30'-0". GUTTER SLOPE TRANSITIONS ARE INCLUDED IN THE COST OF CONCRETE BASE AND/OR CONCRETE GUTTER (SPECIAL). SEE ROADWAY PLANS FOR LIMITS OF REVERSE PITCHED GUTTER AND TRANSITIONS.


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE: 2-7-2012

DATE	REVISIONS
2-07-2012	ADDED CONDUITS TO BARRIER BASE
11-01-2012	ADDED GUTTER TRANSITION TAPER DETAIL AND NEW JOINT DETAIL
3-31-2014	MODIFIED BARRIER BASE
3-11-2015	REVISED NOTES
3-31-2016	REVISED NOTES

Illinois Tollway

CONCRETE BARRIER BASE, AND CONCRETE BARRIER, DOUBLE FACE, 42" AND VARIABLE HEIGHT


STANDARD C5-05



SHOULDER WIDENING TRANSITION-WITHOUT GUTTER FOR TRAFFIC BARRIER TERMINAL, TYPE T1 (SPECIAL) TANGENT

GENERAL NOTES:

1. ALL SLOPE RATIOS ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
2. REFERENCE ILLINOIS TOLLWAY STANDARD DRAWING B28 FOR GUTTER TRANSITION, AND MINIMUM DISTANCE FROM EDGE OF PAVED SHOULDER TO FACE OF RAIL.
3. UNDER NO CIRCUMSTANCES SHALL AN EXISTING TERMINAL, THAT WAS DESIGNED USING A PREVIOUS STANDARD, BE ATTACHED TO OR MODIFIED IN ANY WAY FROM ITS ORIGINAL DESIGN. IF ANY MODIFICATION IS REQUIRED AND A PROPER BARRIER WARRANT HAS BEEN COMPLETED, THE ENTIRE BARRIER INSTALLATION SHALL BE COMPLETELY REMOVED AND REPLACED WITH A NEW SYSTEM THAT CONFORMS TO THE CURRENT STANDARD.
4. TRAFFIC BARRIER TERMINAL SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S DETAILS AND SPECIFICATIONS.
5. NO ROADSIDE OBSTACLE OF ANY TYPE-FIXED OR BREAKAWAY, EITHER TEMPORARY OR PERMANENT SHALL BE ALLOWED WITHIN THIS RECOVERY AREA.
6. ON TANGENT ROADWAY: TRAFFIC BARRIER TERMINAL SHALL BE INSTALLED AT A 50:1 TAPER MEASURED FROM EDGE OF TRAVELED WAY.
ON CURVED ROADWAY: THE EDGE OF THE TERMINAL EXTRUDER HEAD SHALL BE OFFSET A DISTANCE FROM A POINT ON THE BACK OF THE CURVED EDGE OF PAVED SHOULDER AS SHOWN IN TABLE 1. NO CURVED W-BEAM SECTIONS ARE PERMITTED WITHIN THE TERMINAL PAY LIMITS. THE TERMINAL SHALL BE LAID OUT IN A STRAIGHT LINE.
7. TERMINAL POSTS SHALL NOT BE INSTALLED IN CONCRETE OR HMA. WHEN NECESSARY USE LEAVE-OUT DETAIL SHOWN ON ILLINOIS TOLLWAY STANDARD DRAWING C1.
8. THE TERMINAL SYSTEM HAS BEEN PERFORMANCE-TESTED FOR CRASHWORTHINESS UNDER PROCEDURES DEFINED IN THE NATIONAL COOPERATIVE HIGHWAY RESEARCH REPORT (NCHRP) REPORT 350. NO MODIFICATION TO THIS STANDARD DRAWING SHALL BE PERMITTED.




SECTION A-A
(EXTRUDER HEAD OMITTED FOR CLARITY)




SHOULDER WIDENING FOR TRAFFIC BARRIER TERMINAL, TYPE T1 (SPECIAL) TANGENT


STANDARD C6-08

DATE	REVISIONS
03-01-13	TERMINAL CHANGED TO ALL STEEL POST SYSTEM, REVISED TERMINAL PAY LIMITS
03-31-14	REVISED RECOVERY AREA DIMENSION
3-11-2015	REVISED NOTES
3-31-2016	COMBINED G-3 & G-2



 APPROVED..... CHIEF ENGINEER..... DATE 7-1-2009



SHOULDER WIDENING TRANSITION-WITH GUTTER, TYPE G-3 OR TYPE G-2 FOR TRAFFIC BARRIER TERMINAL, TYPE T1 (SPECIAL) TANGENT



CURVED ROADWAY TRAFFIC BARRIER TERMINAL PLACEMENT




SECTION A-A (EXTRUDER HEAD OMITTED FOR CLARITY)

TABLE 1 LATERAL OFFSET DIMENSION TO EDGE OF TERMINAL EXTRUDER HEAD		
	INSIDE RADIUS OF CURVE	OUTSIDE RADIUS OF CURVE
NO GUTTER	1'-0"	1'-0" MIN. *
GUTTER, TYPE G-2	1'-2 3/4"	1'-2 3/4" MIN. *
GUTTER, TYPE G-3	2'-2 3/4"	2'-2 3/4" MIN. *


(*) OFFSET DISTANCE WILL VARY BASED ON RADIUS OF HORIZONTAL CURVE AND THE TERMINAL BEING INSTALLED IN A STRAIGHT LINE.

NOTES:
SEE SHEET 1 OF THIS SERIES FOR NOTES.

Paul Kovacs
APPROVED... CHIEF ENGINEER... DATE 7-1-2009




PLAN



ELEVATION

TRAFFIC BARRIER TERMINAL, TYPE T2-WITHOUT GUTTER



SECTION A-A

NOTES:

1. SEE ILLINOIS TOLLWAY STANDARD DRAWING C1 FOR DETAILS OF GUARDRAIL NOT SHOWN.
2. THE BEARING PLATE K SHALL BE HELD IN POSITION BY TWO 8D NAILS DRIVEN INTO THE POST AND BENT OVER THE TOP OF THE PLATE.
3. THE TRAFFIC BARRIER TERMINAL, TYPE T2 IS TYPICALLY UTILIZED FOR THE DEPARTING END SECTION OF A GALVANIZED STEEL PLATE BEAM GUARDRAIL BARRIER SYSTEM.
4. UNDER NO CIRCUMSTANCES SHALL AN EXISTING TERMINAL, THAT WAS DESIGNED USING A PREVIOUS STANDARD, BE ATTACHED TO OR MODIFIED IN ANYWAY FROM ITS ORIGINAL DESIGN. IF ANY MODIFICATION IS REQUIRED AND A PROPER BARRIER WARRANT HAS BEEN COMPLETED, THE ENTIRE BARRIER INSTALLATION SHALL BE COMPLETELY REMOVED AND REPLACED WITH A NEW SYSTEM THAT CONFORMS TO THE CURRENT STANDARD.
5. TRAFFIC BARRIER TERMINAL SHALL BE IN ACCORDANCE WITH THE ILLINOIS TOLLWAY'S DETAILS AND SPECIFICATIONS. NO MODIFICATIONS SHALL BE PERMITTED.
6. TERMINAL POSTS SHALL NOT BE INSTALLED IN CONCRETE OR ASPHALT PAVEMENT. WHEN NECESSARY USE LEAVE-OUT DETAIL PER ILLINOIS TOLLWAY STANDARD DRAWING C1.
7. WHERE GUTTER, TYPE G-2 OR GUTTER, TYPE G-3 ARE REQUIRED IN FRONT OF THE GUARDRAIL, THE POSTS SHALL BE LOCATED 6" BEHIND THE GUTTER, OR AS OTHERWISE DETAILED IN THE PLANS. THE OFFSET FROM THE EDGE OF SHOULDER TO THE FACE OF THE GUARDRAIL SHALL BE AS SHOWN ON ILLINOIS TOLLWAY STANDARD DRAWING B28.





TRAFFIC BARRIER TERMINAL, TYPE T2


STANDARD C7-07

DATE	REVISIONS
2-07-2012	REVISED DIMENSIONS OF BEARING PLATE, POST, CABLE STRUT AND TUBE AND NOTES
11-01-2012	MODIFIED AGGREGATE SHOULDERS, REVISED WOOD POST DIMENSION
3-31-2014	REVISED NOTES
3-11-2015	REVISED NOTES
3-31-2016	REVISED SECTION A-A SHOULDER

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 7-1-2009




TRAFFIC BARRIER TERMINAL, TYPE T2-WITH GUTTER




NOTE:
SEE SHEET 1 OF THIS SERIES FOR NOTES.


APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 7-1-2009



BEARING PLATE K




CABLE STRUT




NOTE:
ANCHOR PLATE T SHALL BE USED TO ATTACH CABLE ASSEMBLY TO GUARDRAIL WHEN REQUIRED ON TRAFFIC BARRIER TERMINALS.


ANCHOR PLATE T DETAILS




WOOD POST




END SECTION



YOKE
3/16" THICK STEEL



STEEL TUBE



CABLE ASSEMBLY
(40,000 LBS.) MIN. BREAKING STRENGTH)
TIGHTEN TO TAUT TENSION

NOTE:
SEE SHEET 1 OF THIS SERIES FOR NOTES.

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 7-1-2009






RESERVED

APPROVED CHIEF ENGINEER DATE

DATE	REVISIONS


RESERVED
STANDARD C8-00

*GUTTER LINES OMITTED FOR CLARITY



WITH GUTTER, TYPE G-3
SECTION A-A

NOTES:

1. SEE ILLINOIS TOLLWAY STANDARD DRAWING C1 FOR DETAILS OF GUARDRAIL NOT SHOWN.
2. THRIE BEAM RAIL SHALL BE BOLTED TO BLOCK-OUT AT ALL POSTS.
3. ALL SLOPE RATIOS ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
4. THE TRAFFIC BARRIER TERMINAL, TYPE T6 IS TYPICALLY UTILIZED TO ATTACH GALVANIZED STEEL PLATE BEAM GUARDRAIL AT THE UPSTREAM END OF THE BRIDGES CONCRETE PARAPET, WHERE A ROADSIDE GUTTER IS TO BE INSTALLED.
5. SEE ILLINOIS TOLLWAY STANDARD DRAWING B3 FOR GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T6.
6. UNDER NO CIRCUMSTANCES SHALL AN EXISTING TERMINAL, THAT WAS DESIGNED USING A PREVIOUS STANDARD, BE ATTACHED TO OR MODIFIED IN ANYWAY FROM ITS ORIGINAL DESIGN. IF ANY MODIFICATION IS REQUIRED AND A PROPER WARRANT HAS BEEN COMPLETED, THE ENTIRE BARRIER INSTALLATION SHALL BE COMPLETELY REMOVED AND REPLACED WITH A NEW SYSTEM THAT CONFORMS TO THE CURRENT STANDARD.
7. TRAFFIC BARRIER TERMINAL, TYPE T6 SHALL BE IN ACCORDANCE WITH THE ILLINOIS TOLLWAY'S DETAILS AND SPECIFICATIONS. NO MODIFICATIONS SHALL BE PERMITTED.
8. TERMINAL POSTS SHALL NOT BE INSTALLED IN CONCRETE OR ASPHALT PAVEMENTS. WHEN NECESSARY USE LEAVE-OUT DETAIL PER ILLINOIS TOLLWAY STANDARD DRAWING C1.
9. TERMINAL POSTS TO BE INSTALLED PERPENDICULAR TO BACK OF GUTTER.
10. THE TERMINAL SYSTEM HAS BEEN PERFORMANCE-TESTED FOR CRASHWORTHINESS UNDER PROCEDURES DEFINED IN THE NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM (NCHRP) REPORT 350. NO MODIFICATION TO THIS STANDARD DRAWING SHALL BE PERMITTED.
11. TERMINAL BARRIER CLEARANCE DISTANCE SHALL CONFORM WITH TABLE 2 ON ILLINOIS TOLLWAY STANDARD DRAWING C1.
12. LEAVE-OUT DIMENSION BEHIND POSTS 1-6, SHALL BE A MINIMUM OF 4".

Paul Kovacs
APPROVED..... CHIEF ENGINEER..... DATE 7-1-2009

FOR PARAPET (SAFETY FACE)
WITH GUTTER, TYPE G-3



DATE	REVISIONS
2-07-2012	REVISED BOLT NOTES, ANCHORAGE ADHESIVE AND REVISED NOTES.
11-01-2012	MODIFIED AGGREGATE SHOULDERS, REVISED NOTES.
3-31-2014	REVISED NOTES.
3-11-2015	REVISED NOTES AND ADDED DETAIL.
3-31-2016	REVISED SHOULDER SECTION



TRAFFIC BARRIER TERMINAL,
TYPE T6

STANDARD C9-07

*GUTTER LINES OMITTED FOR CLARITY



FOR OTHER CONCRETE STRUCTURE (VERTICAL FACE) WITH GUTTER






TRAFFIC BARRIER TERMINAL, TYPE T6

STANDARD C9-07

NOTE: SEE SHEET 1 OF THIS SERIES FOR NOTES AND SECTION A-A.

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 7-1-2009





SECTION B-B
WITH GUTTER, TYPE G-2

FOR PARAPET (SAFETY FACE)
WITH GUTTER, TYPE G-2

NOTE:
SEE SHEET 1 OF THIS SERIES FOR NOTES.



* GUTTER LINES OMITTED FOR CLARITY



FOR CONCRETE BARRIER, SINGLE-FACE W/ GUTTER, TYPE G-3




TRAFFIC BARRIER TERMINAL, TYPE T6

STANDARD C9-07


NOTE:

SEE SHEET 1 OF THIS SERIES FOR GUTTER TRANSITION NOTES AND SECTION A-A.


APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 2-7-2012




THRIE BEAM END SHOE DETAIL




POSTS 1-11 WOOD BLOCK-OUT DETAIL




POST 12 WOOD BLOCK-OUT DETAIL
(SEE ILLINOIS TOLLWAY STANDARD DRAWING C1 FOR POST 13-17 BLOCKOUTS)



TRANSITION SECTION
(10 GAUGE RAIL ELEMENT)



PARAPET WOOD BLOCK-OUT DETAIL




PARAPET STEEL BEARING PLATE DETAIL



(5 EACH INDIVIDUAL 5"x5"x5/8" STEEL PLATES WITH CENTERED 1" HOLES MAY BE SUBSTITUTED FOR THE PLATE SHOWN.)

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 7-1-2009

NOTE:
SEE SHEET 1 OF THIS SERIES FOR NOTES.




* WITH STANDARD WASHERS. AFTER TIGHTENING, CUT THE ANCHOR BOLTS FLUSH WITH THE NUTS AND DAMAGE THE NUTS TO PREVENT THEM FROM LOOSENING. BOLTS SHALL BE ANCHORED INTO DRILLED HOLES USING A CHEMICAL ADHESIVE RESIN SYSTEM. MINIMUM EMBEDMENT 10".



SECTION A-A

NOTES:

1. SEE ILLINOIS TOLLWAY STANDARD DRAWING C1 FOR DETAILS OF GUARDRAIL NOT SHOWN.
2. THRIE BEAM RAIL SHALL BE BOLTED TO BLOCK-OUT AT ALL POSTS.
3. ALL SLOPE RATIOS ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
4. THE TRAFFIC BARRIER TERMINAL, TYPE T6B IS TYPICALLY UTILIZED TO ATTACH GALVANIZED STEEL PLATE BEAM GUARDRAIL AT THE UPSTREAM END OF THE BRIDGE CONCRETE PARAPET, WHERE A ROADSIDE GUTTER IS NOT TO BE INSTALLED.
5. UNDER NO CIRCUMSTANCES SHALL EXISTING TERMINAL, THAT WAS DESIGNED USING A PREVIOUS STANDARD, BE ATTACHED TO OR MODIFIED IN ANYWAY FROM ITS ORIGINAL DESIGN. IF ANY MODIFICATION IS REQUIRED AND A PROPER BARRIER WARRANT HAS BEEN COMPLETED, THE ENTIRE BARRIER INSTALLATION SHALL BE COMPLETELY REMOVED AND REPLACED WITH A NEW SYSTEM THAT CONFORMS TO THE CURRENT STANDARD.
6. TRAFFIC BARRIER TERMINAL SHALL BE IN ACCORDANCE WITH THE ILLINOIS TOLLWAY'S DETAILS AND SPECIFICATIONS. NO MODIFICATIONS SHALL BE PERMITTED.
7. TERMINAL POSTS SHALL NOT BE INSTALLED IN CONCRETE OR ASPHALT PAVEMENTS. WHEN NECESSARY USE LEAVE-OUT DETAIL PER ILLINOIS TOLLWAY STANDARD DRAWING C1, SHEET 4 OF 4.
8. TERMINAL BARRIER CLEARANCE DISTANCE SHALL CONFORM WITH TABLE 2 ON ILLINOIS TOLLWAY STANDARD DRAWING C1.
9. LEAVE-OUT DIMENSION BEHIND POSTS 1-6, SHALL BE A MINIMUM OF 4".



TRANSITION SECTION
(10 GAUGE RAIL ELEMENT)


APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 7-1-2009

DATE	REVISIONS
2-07-2012	REVISED WOOD BLOCK-OUT DIMENSION ADHESIVE AND REVISED NOTES
11-01-2012	MODIFIED AGGREGATE SHOULDERS, REVISED NOTES
3-31-2014	REVISED WOOD BLOCKS AND NOTES
3-11-2015	REVISED NOTES
3-31-2016	REVISED SECTION A-A SHOULDER




TRAFFIC BARRIER TERMINAL, TYPE T6B


STANDARD C10-07




POSTS 1-11 WOOD BLOCK-OUT DETAIL




POST 12 WOOD BLOCK-OUT DETAIL
(SEE ILLINOIS TOLLWAY STANDARD DRAWING C1 FOR POST 13-17 BLOCKOUTS)




THRIE BEAM END SHOE DETAIL




MODIFIED THICKNESS DETAIL
WOOD BLOCK-OUTS A, B, C, & D



WOOD BLOCK-OUT D



WOOD BLOCK-OUT C



WOOD BLOCK-OUT A & B

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 7-1-2009




NOTE:
SEE SHEET 1 OF THIS SERIES FOR NOTES.

SHEET 2 OF 2



TRAFFIC BARRIER
TERMINAL, TYPE T6B





STANDARD C10-07



(4 EACH INDIVIDUAL 5"x5"x5/8" STEEL PLATES WITH CENTERED HOLES MAY BE SUBSTITUTED FOR THE PLATE SHOWN)


NOTES:

- SEE ILLINOIS TOLLWAY STANDARD DRAWING C1 FOR DETAILS OF GUARDRAIL NOT SHOWN.
- THE 24 7/8" TYPICAL RAIL HEIGHT IS MEASURED FROM EXISTING SURFACE 1'-0" IN FRONT OF RAIL, OR FROM EDGE OF SHOULDER/EDGE OF GUTTER WHEN EDGE IS MORE THAN 1'-0" IN FRONT OF RAIL TO CENTER OF RAIL.
- THE TRAFFIC BARRIER TERMINAL, TYPE T10 IS TYPICALLY UTILIZED TO CONNECT GALVANIZED STEEL PLATE BEAM GUARDRAIL TO THE DEPARTING END OF AN EXISTING BRIDGE CONCRETE WING WALL OR PARAPET.
- UNDER NO CIRCUMSTANCES SHALL AN EXISTING TERMINAL, THAT WAS DESIGNED USING A PREVIOUS STANDARD, BE ATTACHED TO OR MODIFIED IN ANYWAY FROM ITS ORIGINAL DESIGN. IF ANY MODIFICATION IS REQUIRED AND A PROPER BARRIER WARRANT HAS BEEN COMPLETED, THE ENTIRE BARRIER INSTALLATION SHALL BE COMPLETELY REMOVED AND REPLACED WITH A NEW SYSTEM THAT CONFORMS TO THE CURRENT STANDARD.
- TRAFFIC BARRIER TERMINAL SHALL BE IN ACCORDANCE WITH THE ILLINOIS TOLLWAY'S DETAILS AND SPECIFICATIONS. NO MODIFICATIONS SHALL BE PERMITTED.
- WHEN END SHOE IS ATTACHED TO A BRIDGE PARAPET WHICH HAS AN EXPANSION JOINT, THE BOLTS SHALL BE PROVIDED WITH A LOCKNUT OR DOUBLE NUT AND SHALL BE TIGHTENED ONLY TO A POINT THAT WILL ALLOW GUARDRAIL MOVEMENT.
- THE ANCHOR CONE SHALL BE SET FLUSH WITH THE SURFACE OF THE CONCRETE.
- EXTERNALLY THREADED STUDS PROTRUDING FROM THE SURFACE OF THE CONCRETE SHALL NOT BE PERMITTED.
- WHEN WING WALL THICKNESS IS GREATER THAN 18" OR NOT ACCESSIBLE TO THE BACK SIDE, 4-3/4" BOLTS SHALL BE ANCHORED INTO DRILLED HOLES, USING A CHEMICAL ADHESIVE. MINIMUM EMBEDMENT SHALL BE 10". ANCHOR BOLTS WITH STANDARD WASHER SHALL BE USED. AFTER TIGHTENING, CUT THE ANCHOR BOLTS FLUSH WITH THE NUTS, AND DAMAGE THE NUTS TO PREVENT THEM FROM LOOSENING.



GENERAL NOTE:

* HEAD OF BOLT TO BE ON TRAFFIC SIDE. SEE DETAIL "A"




APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE: 7-1-2009

DATE	REVISIONS
3-01-2010	REVISED NOTES, ADDED END SHOE AND PARAPET BEARING PLATE DETAIL.
1-01-2011	REVISED END SHOE HEIGHT ATTACHMENT
2-07-2012	REVISED BOLT NOTE, ADDED DETAIL "A" AND REVISED NOTES.
3-31-2014	REVISED NOTES.
3-11-2015	REVISED NOTES.
3-31-2016	REVISED FLARED WING ANGLE.

TRAFFIC BARRIER TERMINAL, TYPE T10


STANDARD C11-06



**SHOULDER WIDENING TRANSITION-WITHOUT GUTTER
FOR TRAFFIC BARRIER TERMINAL, TYPE T1-A (SPECIAL)**

GENERAL NOTES:

1. ALL SLOPE RATIOS ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
2. THE TRAFFIC BARRIER TERMINAL, TYPE T1-A (SPECIAL) IS THE UPSTREAM END SECTION OF A GALVANIZED STEEL PLATE BEAM GUARDRAIL BARRIER SYSTEM, FOR RAMP INSTALLATION WITH DESIGN SPEED LIMIT OF 40 MPH OR LESS, NCHRP 350, TEST LEVEL (TL-2).
3. REFERENCE ILLINOIS TOLLWAY STANDARD DRAWING B29 FOR GUTTER TRANSITION AT TRAFFIC BARRIER TERMINAL, TYPE T1-A (SPECIAL), AND MINIMUM DISTANCE FROM EDGE OF PAVED SHOULDER TO FACE OF RAIL.
4. UNDER NO CIRCUMSTANCES SHALL AN EXISTING TERMINAL, THAT WAS DESIGNED USING A PREVIOUS STANDARD, BE ATTACHED TO OR MODIFIED IN ANYWAY FROM ITS ORIGINAL DESIGN. IF ANY MODIFICATION IS REQUIRED AND A PROPER BARRIER WARRANT HAS BEEN COMPLETED, THE ENTIRE BARRIER INSTALLATION SHALL BE COMPLETELY REMOVED AND REPLACED WITH A NEW SYSTEM THAT CONFORMS TO THE CURRENT STANDARD.
5. TRAFFIC BARRIER TERMINAL SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S DETAILS AND SPECIFICATIONS.
6. NO ROADSIDE OBSTRUCTION OF ANY TYPE-FIXED OR BREAKAWAY, EITHER TEMPORARY OR PERMANENT SHALL BE ALLOWED WITHIN THIS RECOVERY AREA.
7. ON TANGENT ROADWAY: TRAFFIC BARRIER TERMINAL SHALL BE INSTALLED AT A 25:1 TAPER MEASURED FROM EDGE OF TRAVELED WAY.
ON CURVED ROADWAY: THE EDGE OF THE TERMINAL EXTRUDER HEAD SHALL BE OFFSET A DISTANCE FROM A POINT ON THE BACK OF THE CURVED EDGE OF PAVED SHOULDER AS SHOWN IN TABLE 1. NO CURVED W-BEAM SECTIONS ARE PERMITTED WITHIN THE TERMINAL PAY LIMITS. THE TRAFFIC BARRIER TERMINAL, TYPE T1-A (SPECIAL) SHALL BE LAID OUT IN A STRAIGHT LINE.
8. TERMINAL POSTS SHALL NOT BE INSTALLED IN CONCRETE OR HMA. WHEN NECESSARY USE LEAVE-OUT DETAIL SHOWN ON ILLINOIS TOLLWAY STANDARD DRAWING C1.
9. THE TERMINAL SYSTEM HAS BEEN PERFORMANCE-TESTED FOR CRASHWORTHINESS UNDER PROCEDURES DEFINED IN THE NATIONAL COOPERATIVE HIGHWAY RESEARCH REPORT (NCHRP) REPORT 350. NO MODIFICATION TO THIS STANDARD DRAWING SHALL BE PERMITTED.



SECTION A-A
(EXTRUDER HEAD OMITTED FOR CLARITY)


Paul Kovacs
APPROVED..... CHIEF ENGINEER..... DATE 1-1-2011.....

DATE	REVISIONS
2-07-2012	REVISED SLOPE NOTE.
11-01-2012	MODIFIED AGGREGATE SHOULDER
3-01-2013	TERMINAL CHANGED TO ALL STEEL POST, REVISED TERMINAL PAY LIMITS
3-31-2014	REVISED RECOVERY AREA DIMENSION.
3-11-2015	REVISED NOTES
3-31-2016	ADDED INSTALLATION NOTES IN NOTE 7 AND REVISED SECTION A-A SHOULDER




SHOULDER WIDENING FOR
TRAFFIC BARRIER TERMINAL,
TYPE T1-A (SPECIAL)


STANDARD C12-06



SHOULDER WIDENING TRANSITION-WITH GUTTER, TYPE G-2
FOR TRAFFIC BARRIER TERMINAL, TYPE T1-A (SPECIAL)



CURVED ROADWAY
TRAFFIC BARRIER TERMINAL PLACEMENT
(SEE NOTE 7)



SECTION B-B
(EXTRUDER HEAD OMITTED FOR CLARITY)

NOTES:
SEE SHEET 1 OF THIS SERIES FOR NOTES.

TABLE 1		
LATERAL OFFSET DIMENSION TO EDGE OF TERMINAL EXTRUDER HEAD		
	INSIDE RADIUS OF CURVE	OUTSIDE RADIUS OF CURVE
NO GUTTER	1'-0"	1'-0" MIN. *
GUTTER, TYPE G-2	1'-2 3/4"	1'-2 3/4" MIN. *


(*) OFFSET DISTANCE WILL VARY BASED ON RADIUS OF HORIZONTAL CURVE AND THE TERMINAL BEING INSTALLED IN A STRAIGHT LINE.

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 1-1-2011


SHEET 2 OF 2

SHOULDER WIDENING FOR TRAFFIC BARRIER TERMINAL, TYPE T1-A (SPECIAL)


STANDARD C12-06




PLAN 1



PLAN 2



ELEVATION 1



ELEVATION 2

CONCRETE MEDIAN BARRIER TRANSITION, TYPE V-F
AT BRIDGE PIERS (FOR W ≤ 4'-0'')

CONCRETE MEDIAN BARRIER TRANSITION, TYPE V-F
AT BRIDGE PIERS (FOR W > 4'-0'')

		TABLE OF VARIABLES			
		W	L	V	G
PLAN 1	3'-0"	31'-3"	10'-0"	2'-0"	
	3'-6"	31'-3"	10'-0"	1'-9"	
	4'-0"	36'-3"	15'-0"	1'-6"	
PLAN 2	4'-6"	46'-3"	10'-0"	1'-3"	
	5'-0"	51'-3"	15'-0"	1'-0"	
	5'-6"	58'-9"	22'-6"	9"	
	6'-0"	66'-3"	30'-0"	6"	

NOTES:

- 2" DEEP CONTRACTION JOINTS SHALL BE DONE BY SAWING AND SHALL BE CONSTRUCTED IN THE CONCRETE BARRIER WALL, CONCRETE BARRIER BASE, AND CONCRETE GUTTER (SPECIAL). CONTRACTION JOINTS SHALL ALSO BE CONSTRUCTED AT BOTH SIDES OF ALL DRAINAGE STRUCTURES. MAXIMUM CONTRACTION JOINT SPACING SHALL BE 30'-0". THE MINIMUM DISTANCE BETWEEN CONTRACTION JOINTS IN THE MEDIAN BARRIER WALL SHALL BE 2'-0". WHEN A DRAINAGE STRUCTURE FALLS WITHIN 2'-0" FROM AN EXPANSION JOINT (OR) CONTRACTION JOINT, THE NEAREST CONTRACTION JOINT SHALL BE OMITTED.
- GUTTER PROFILE IN THE VICINITY OF SAG VERTICAL CURVES, ALONG FLAT GRADES AND AT THE MEETING OF PROPOSED AND EXISTING GUTTER, SHALL BE CAREFULLY CONTROLLED AND FIELD ADJUSTED IF NECESSARY TO ENSURE POSITIVE DRAINAGE AND AVOID PONDING.
- NON-STAINING GRAY ONE COMPONENT NON-SAG ELASTOMERIC GUN GRADE POLYURETHANE SEALANT MEETING THE REQUIREMENTS OF ASTM C-920, TYPE S, GRADE NS, CLASS 25, USE T WITH A BACKER ROD.


APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 2-7-2012

DATE	REVISIONS
11-01-2012	MODIFIED MEDIAN BARRIER TRANSITION.
3-31-2014	MODIFIED BARRIER BASE.
3-11-2015	MODIFIED MEDIAN BARRIER TRANSITION.
3-31-2016	MODIFIED NOTES


SHEET 1 OF 2




CONCRETE MEDIAN BARRIER
TRANSITION, TYPE V-F
AT BRIDGE PIERS
STANDARD C13-04




SECTION A-A




SECTION B-B




SECTION C-C




SECTION D-D



SECTION E-E



SECTION F-F



SECTION G-G

Paul Kovacs
 APPROVED... CHIEF ENGINEER... DATE 2-7-2012

NOTES:
 SEE SHEET 1 OF THIS SERIES FOR NOTES.

CONCRETE MEDIAN BARRIER
 TRANSITION, TYPE V-F
 AT BRIDGE PIERS
 STANDARD C13-04









TABLE A	
Wc	L (MIN.)
Wc < 35"	20'-0"
35" < Wc < 43"	30'-0"
43" < Wc < 51"	40'-0"
51" < Wc < 59"	50'-0"
59" < Wc < 67"	60'-0"
67" < Wc < 72"	70'-0"

Wc=PIER CRASH WALL WIDTH



- NOTES:**
1. SLOPE RATIOS ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT (V:H).
 2. ENERGY ATTENUATOR AND PAD SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S DETAILS AND SPECIFICATIONS.
 3. 2" DEEP CONTRACTION JOINTS SHALL BE DONE BY SAWING AND SHALL BE CONSTRUCTED IN THE CONCRETE BARRIER WALL, AND CONCRETE BARRIER BASE. MAXIMUM CONTRACTION JOINT SPACING SHALL BE 30'-0". THE MINIMUM DISTANCE BETWEEN CONTRACTION JOINTS IN THE MEDIAN BARRIER WALL SHALL BE 2'-0".

APPROVED: *Paul Kovacs* CHIEF ENGINEER DATE 3-31-2014

DATE	REVISIONS
3-11-2015	REVISED NOTES
3-31-2016	ADDED SEC. B-B TOP, DITCH ELEV. VIEW AND REVISED NOTE 3

CONCRETE MEDIAN BARRIER TRANSITION, TYPE V AT BRIDGE PIERS
STANDARD C14-02