Illinois Tollway Standard Drawing Revisions

Section D	Roadway Appurtenances	
	Standard	**Modification Summary** **Effective: 03-31-2016**
	All	**The electronic (pdf) version of the Standard Drawings are now made searchable (text).**
	D2	**Symbols and Patterns**
	Sheet 1	Ditch check symbol was revised to match IDOT and Section K revision.
	D4	**Roadway Delineators and Reflectors**
	All	Title changed to match 2016 IDOT Standard Specifications.
	Sheet 2	Revised detail of roadway delineator circular reflectors attachment to post to match IDOT Standard.
		Circular Reflectors: Single unit installation changed from 1" to 2" from top of post.
		Circular Reflectors: Double unit spacing changed from 4" to 5".
		New detail of roadway delineator rectangular reflector to post per Tollway Maintenance.
	D5	**Permanent Pavement Markings**
		Revised note 4 to clarify that "permanent" lane lines and edge lines to be grooved, unless otherwise noted.
		Added note 8 concerning grooving restrictions at toll plazas and ORT sections.
	D6	**Pavement Marking and Shoulder Rumble Strip Details**
	Sheet 1	Theoretical gore information has been detailed in the Roadway Design Criteria.
		Added rumble strip to lane drop detail.
	Sheet 2	Theoretical gore information has been detailed in the Roadway Design Criteria.
	Sheet 3	Added IPO lane pavement marking.
	D7	**Landscape Planting Details**
		Note 3. Increased minimum distance of trees to fences from 5' to 6'.
		Note 7. Added "tree and shrub" descriptions to plantings.
		Reduced mulch layer for shrub planting from 5" to 4".
	D8	**Raised Pavement Lane Marker**
		Added guidance to Detail C when raised pavement markers are to be placed in auxiliary lanes.
		Revised note 1 collector-distributor (C-D) notation per MUTCD.

New Sheet Retired Standard



PEDESTRIAN GATE



VEHICULAR GATE



PULL POST

* ON UNEVEN GROUND THIS DIMENSION MAY VARY BETWEEN 1" MIN. TO 6" MAX. FOR A MAX. DISTANCE OF 8'-0".



LINE POST

CORNER OR END POST

RIGHT OF WAY FENCE, TYPE 1, 6'



PEDESTRIAN GATE



VEHICULAR GATE



PULL POST

LINE POST



CORNER OR END POST

* ON UNEVEN GROUND THIS DIMENSION MAY VARY BETWEEN 1" MIN. TO 6" MAX. FOR A MAX. DISTANCE OF 8'-0".

RIGHT OF WAY FENCE, TYPE 2, 4'

GENERAL NOTES

1. ON STRAIGHT RUNS OF FENCE, PULL POSTS SHALL BE USED AT 500' CENTERS FOR TYPE 1 AND 330' CENTERS FOR TYPE 2.
2. WHERE R.O.W. FENCE FOLLOWS R.O.W. LINE IT SHALL BE INSTALLED PARALLEL TO AND 6" INSIDE THE R.O.W. LINE ON ILLINOIS TOLLWAY PROPERTY.
3. LINE POSTS AND BRACES SHALL BE ON ILLINOIS TOLLWAY SIDE OF FENCE FABRIC.
4. WHEN THE TENSION OF THE FENCE TENDS TO PULL THE POSTS FROM THE GROUND, THE LINE POSTS SHALL BE ANCHORED WITH ANCHORAGE SPECIFIED FOR CORNER POSTS.
5. AT LOCATION WHERE THE PROPOSED FENCE IS TO BE CONNECTED TO AN EXISTING POST, THE REQUIRED CONNECTIONS AND BRACING INCLUDING ALL NECESSARY HARDWARE SHALL BE CONSIDERED INCIDENTAL TO THE FENCE OF THE TYPE SPECIFIED.
6. WHEN THE FENCE LINE HAS A CHANGE IN DIRECTION OF 10° OR MORE, A CORNER POST SHALL BE PLACED AT THE POINT OF CHANGE. WHERE THE ANGLE OF CHANGE IS LESS THAN 10° A PULL POST SHALL BE USED.
7. WHERE GRADE LINE HAS A CHANGE IN SLOPE OF 10° OR MORE, A CORNER POST WITH BRACING AS REQUIRED SHALL BE PLACED. WHERE ANGLE IS LESS THAN 10° LINE POST MAY BE USED.
8. WHERE RIGHT-OF-WAY FENCE, TYPE 1 IS USED, THE FABRIC SHALL BE KNUCKLED SELVAGE ON TOP AND TWISTED AND BARBED SELVAGE ON BOTTOM.
9. PLACEMENT OF BRACED END POSTS OR CORNER POSTS WITHIN THE CLEAR ZONE SHALL BE AVOIDED.

APPROVED Paul Kovacs CHIEF ENGINEER DATE 7-1-2009

Illinois Tollway

DATE	REVISIONS
7-01-2009	R.O.W. FENCE TYPES 1 AND 2
	FENCE DETAILS
11-01-2012	REVISED NOTES
3-31-2014	REVISED ROLLED FORM SECTIONS
3-11-2015	REVISED NOTES

RIGHT OF WAY FENCE

STANDARD D1-04



STRETCHER BARS SHALL BE GALVANIZED FLAT STEEL BAR NOT LESS THAN 1/4'' x 3/4'' AND THE STRETCHER BAR BANDS SHALL BE GALVANIZED FLAT STEEL BAR NOT LESS THAN 1/8''x 1'' WITH A 3/8'' GALVANIZED CARRIAGE BOLT.

METHOD OF FASTENING STRETCHER BAR TO POST



BRACE SECTION
1.25 LBS/LF



HEAVY ''C'' - 2.70 LBS/LF
A x B = 2.250'' x 1.625''

LINE POST ''C'' SECTION



TERMINAL POST SECTION
5.10 LBS/LF

DETAILS OF ROLL FORMED SECTIONS



METHOD OF TYING FABRIC TO TENSION WIRES



ABUTMENT CONNECTION DETAIL

NOTES FOR ABUTMENT CONNECTION:

1. WHEN ROLL FORMED SECTION IS USED IN LIEU OF PIPE AS END POST, THE POST SHALL BE BOLTED DIRECTLY TO THE ABUTMENT WALL WITH 2 1/2'' x 5'' BOLTS WITH STANDARD WASHERS MEETING THE APPROVAL OF THE ENGINEER.



STANDARD GROUND — COUNTERPOISE GROUND (ALTERNATE)

NOTES FOR STANDARD AND COUNTERPOISE GROUND:

1. THE INTERVALS FOR GROUNDING CONTINUOUS FENCING SHALL NOT EXCEED 500 FEET IN URBAN AREAS AND 1000 FEET IN RURAL AREAS. FENCE ADJACENT TO A GATE SHALL BE GROUNDED A MAXIMUM DISTANCE 100 FEET EACH SIDE OF THE GATE.
2. FENCE CROSSING UNDER A POWER LINE SHALL BE GROUNDED, ONCE DIRECTLY UNDER THE CROSSING AND ONE ON EACH SIDE AT 25 TO 50 FEET AWAY. FENCE LOCATED DIRECTLY UNDER A TELEPHONE WIRE OR CABLE CROSSING SHALL HAVE A SINGLE GROUND.
3. COUNTERPOISE GROUNDS SHALL BE USED AT LOCATIONS WHERE GROUND RODS CAN NOT BE DRIVEN DUE TO IMPERVIOUS EARTH MATERIALS.
4. THE GROUND WIRES SHALL BE CONNECTED TO FENCE FABRIC AND GROUND ROD BY STAINLESS STEEL BOLTS AND WASHERS. THE LOWER CONNECTION OF THE GROUND WIRE SHALL BE MADE TO THE BOTTOM TENSION WIRE.

ELECTRICAL GROUNDING DETAILS

ALTERNATE
DRIVEN LINE POST ANCHORAGE
WITH OR WITHOUT DRIVE ANCHORS

NOTE FOR FENCE POST:

ALTERNATE DRIVEN LINE POST ANCHORAGE IS OPTIONAL. DRIVEN LINE POST ANCHORAGE WITHOUT DRIVE ANCHORS MAY BE USED IN AVERAGE TO GOOD SOIL CONDITIONS. WHEN SOIL IS WEAKER (Qu < 1.25 TONS/ SQ. FT.) AND STABILITY OF THE POST IS QUESTIONABLE, DRIVE ANCHORS SHALL BE USED. TYPES, SHAPES, DIMENSIONS AND COATING REQUIREMENTS OF DRIVE ANCHORS (ANCHOR BLADES AND COLLARS) FOR DIFFERENT TYPE OF POSTS SHALL BE AS RECOMMENDED BY THE MANUFACTURER.

Paul Kovacs
APPROVED ..... DATE 7-1-2009
CHIEF ENGINEER

Illinois Tollway

RIGHT OF WAY FENCE

STANDARD D1-04



NORMAL FLOW: NONE.
MAY BE VARIED FOR STEEPER BANKS TO FIT VARIOUS CHANNEL SECTIONS.

STREAM CROSSING, TYPE 1



FENCE INSTALLATION OVER DITCH



NOTE:

"X" + "Y" SHALL NOT EXCEED 30" WHEN "X" IS 0" TO 15" "Y" =15", AND THE POST SHALL BE SHORTENED AS REQUIRED. WHEN "X" EXCEEDS 15" "Y" SHALL BE DECREASED ACCORDINGLY.

FOOTING FOR POST WHEN ROCK LEDGE IS ENCOUNTERED



STREAM CROSSING, TYPE 2



NOTES FOR STREAM CROSSING TYPE 1 AND TYPE 2:

1. THESE INSTALLATION CONDITIONS ARE TYPICAL AND ARE NOT TO BE CONSTRUED AS REPRESENTATIVE OF ALL CONDITIONS WHICH WILL BE ENCOUNTERED. CONSTRUCTION WILL BE VARIED AS REQUIRED OR DIRECTED TO MEET FIELD CONDITIONS.
2. FOR STREAM CROSSING OF THE TYPE REQUIRED THE BOTTOM BARBED WIRE SHALL BE ANCHORED TO CONCRETE FOOTING OR TO HOLES DRILLED IN POSTS, AND INTERMEDIATE WIRES SHALL BE TIED TO THE BOTTOM WIRE AND TO POSTS IN AN EVENLY SPACED FASHION TO PREVENT SLIPPAGE.
3. CONCRETE AND FITTINGS FOR ALL TYPES OF FENCE SHALL BE AS DETAILED FOR SIMILAR CONDITIONS PER STANDARD DRAWING.

THE FENCE FABRIC SHALL BE REPLACED BY BARBED WIRE STRANDS AT 12" MAXIMUM CENTERS BETWEEN THE END POSTS WHEN SHOWN ON THE PLANS THE BARBED WIRE STRANDS, IF REQUIRED, SHALL BE INCIDENTAL TO THE VARIOUS TYPES OF STREAM CROSSING REQUIRED.

DETAIL A



PLAN AT HEADWALL



ELEVATION

NOTES FOR INSTALLATION AROUND HEADWALL:

1. THIS TYPE OF INSTALLATION IS TO BE USED ONLY WHEN SPECIFICALLY CALLED FOR IN THE CONTRACT PLANS.
2. WHEN THE WIDTH OF THE CULVERT MAKES NECESSARY TO ANCHOR A POST TO THE TOP OF THE CULVERT, A CAST IRON SHOE OR OTHER DEVICE APPROVED BY THE ENGINEER SHALL BE USED. THE COST OF ANCHORING THE POST SHALL BE INCIDENTAL TO THE TYPE OF FENCE REQUIRED.

INSTALLATION AROUND HEADWALL

Paul Kovacs
APPROVED ..... CHIEF ENGINEER
DATE 7-1-2009

Illinois Tollway

RIGHT OF WAY FENCE

STANDARD D1-04

SURVEY AND ROADWAY ITEMS

EXISTING	PROPOSED	
		CONSTRUCTION JOINT W/DOWEL BARS
		BENCHMARK
		CANTILEVER SIGN STRUCTURE
		BUTTERFLY SIGN STRUCTURE
		DOUBLE COLUMN GROUND MOUNTED SIGN
		SINGLE COLUMN GROUND MOUNTED SIGN
		SPAN TYPE SIGN STRUCTURE
		TRIPLE COLUMN GROUND MOUNTED SIGN
		RUMBLE STRIP

DRAINAGE AND UTILITY ITEMS; ROADWAY LIGHTING AND SIGNS

EXISTING	PROPOSED	
		BOX CULVERT WITH HEADWALL
		CABLE IN DUCT W/O GROUND
		LOW POINT
P		OVERHEAD ELECTRICAL
T		OVERHEAD TELEPHONE
		PIPE CULVERT
		LAKE OR POND
		QUARRY
		STREAM
		SWAMP
	A	CABLE OR CONDUIT TAG
E	E	ELECTRICAL MANHOLE
LD	LD	LIGHT-DUTY BOX
		ROADWAY LUMINAIRE
		STEEL TOWER
T	T	TELEPHONE MANHOLE
		UNDERPASS LUMINAIRE
		WATER POINT
W	W	WATERMAIN VALVE VAULT
W	W	WATER WELL
		WOOD POLE

EROSION & SEDIMENT CONTROL, LANDSCAPING ITEMS

EXISTING	PROPOSED	
		CLEARING & GRADING LIMITS (LIMITS OF CONSTRUCTION)
		DIVERSION DIKE
		DRAINAGE DIVIDE
		DRAINAGE PATH
		SEDIMENT BASIN AGGREGATE BERM
	CIP	CULVERT INLET PROTECTION-STONE
		CULVERT INLET PROTECTION-FENCE
	DB	DEWATERING BASIN
	FIPB	FILTER FABRIC INLET PROTECTION, BASKET TYPE
	FIPC	FILTER FABRIC INLET PROTECTION, COVER TYPE
	FB FB	FLOTATION BOOM
	IC	INITIAL CONSTRUCTION ITEM
	RIP	RECTANGULAR INLET PROTECTION
		TEMPORARY ROCK CHECK DAM
	T	TEMPORARY DITCH CHECK
		SEDIMENT BASIN
		SILT FENCE
	SSF	SUPER SILT FENCE
		STABILIZED CONSTRUCTION ENTRANCE
		STONE OUTLET STRUCTURE SEDIMENT TRAP
		STREAM DIVERSION
		TEMPORARY PIPE SLOPE DRAIN
		TEMPORARY RIPRAP
	TS	TEMPORARY SWALE
		TREES AND STUMP
	TP	TREE PROTECTION
		TEMPORARY STREAM CROSSING

EXISTING	PROPOSED	
		EROSION CONTROL BLANKET
		OVER SEEDING CLASS B1
		OVER SEEDING CLASS B2
		SEEDING CLASS A1
		SEEDING CLASS A2
		SEEDING CLASS A3
		SEEDING CLASS A4
		SEEDING CLASS A5
		SEEDING CLASS A6
		SEEDING CLASS D1
		SODDING (SALT TOLERANT)
		TEMPORARY GROUND COVER
		TURF REINFORCEMENT MAT

Paul Kovacs
APPROVED ..... DATE 7-1-2009
CHIEF ENGINEER

Illinois Tollway

DATE	REVISIONS
7-01-2009	REVISED SYMBOL & PATTERNS
11-01-2012	ADDED NEW SYMBOLS
3-11-2015	ADDED NEW SYMBOL
3-31-2016	UPDATED DITCH CHECK SYMBOL

SYMBOLS AND PATTERNS

STANDARD D2-04

ELECTRICAL AND MECHANICAL ITEMS

HOME RUN TO PANEL AS NOTED

INDICATES CIRCUIT TURNING DOWN

INDICATES CIRCUIT TURNING UP

GROUND ROD

GROUNDING TRIAD



TRANSFORMER

MOTOR

AUTOMATIC TRANSFER SWITCH (ATS)

JB OR J — JUNCTION BOX

DISCONNECT SWITCH

CIRCUIT BREAKER

MANUAL TRANSFER SWITCH



SELF CONTAINED UTILITY METERING

G — STANDBY GENERATOR

--A / -P — PANEL CIRCUIT BREAKER

C — MECHANICALLY HELD LIGHTING COIL

CR — CONTROL RELAY COIL

$ — SINGLE-POLE SWITCH

DUPLEX RECEPTACLE

C — 4P, 4W, WEATHERPROOF RECEPTACLE WITH SPRING DOOR, BACK BOX, & ANGLE ADAPTER

B — 4P, 4W, WEATHERPROOF RECEPTACLE WITH SPRING DOOR & BACK BOX

GFI — DUPLEX RECEPTACLE WITH GROUND FAULT PROTECTION

A — CONTROL BUILDING LIGHTING
1' X 4' INDUSTRIAL FLUORESCENT FIXTURE, PORCELAIN REFLECTOR, ELECTRONIC BALLAST.

B — COMPACT WALL-MOUNTED LOW WATTAGE HPS FIXTURE WITH WIRE GUARD & SINGLE FACTORY INSTALLED FUSE

C — EMERGENCY LIGHT UNIT WITH 2-6 VOLT, 12 WATT SEALED BEAM HALOGEN LAMPS WITH WALL MOUNTING BRACKET

D — LANE LIGHTING - HEAVY DUTY ALUMINUM HOUSING WITH ENCLOSED REFLECTOR & TEMPERED GLASS LENS W/AUTO REGULATOR BALLAST. ASYMMETRIC PATTERN

WIRE

CONDUIT

	EXISTING	PROPOSED	
	A	**A**	COMPRESSED AIR (A)
	AR	**AR**	ACID RESISTANT WASTE OR DRAIN
	ARV	**ARV**	ACID RESISTANT VENT
	DS	**DS**	STORM SEWER (DOWNSPOUT)
	G	**G**	GAS LINE
	HG	**HG**	HOT GAS BYPASS LINE (HG)
	HHWR	**HHWR**	HEATING HOT WATER RETURN (HHWR)
	HHWS	**HHWS**	HEATING HOT WATER SUPPLY (HHWS)
	IA	**IA**	DRY COMPRESSED AIR (IA-INSTRUMENT AIR)
	P	**P**	PROCESS WATER ("P" WATER) LINE
	PW	**PW**	PROTECTED WATER OR PLANT WATER (PW)
	RD	**RD**	REFRIGERANT DISCHARGE LINE (RD)
	RS	**RS**	REFRIGERANT SUCTION LINE (RS)
	V	**V**	VENT LINE (V)

Paul Kovacs
APPROVED ..... CHIEF ENGINEER
DATE 7-1-2009

NOTE:

ALL SYMBOLS AND PATTERNS ON THIS DRAWING ARE PROPOSED UNLESS OTHERWISE NOTED.

Illinois Tollway

SYMBOLS AND PATTERNS

STANDARD D2-04

ELECTRICAL AND MECHANICAL ITEMS

CFM OR CFM — QUANTITY AND DIRECTION OF THE AIR FLOW

X OR X — DUCT SIZE (FIRST FIGURE SIZE OF SHOWN, SECOND FIGURE SIZE OF SIDE NOT SHOWN.)

SUPPLY DUCT SECTION

OR — RETURN OR EXHAUST DUCT SECTION

D OR D — DUCT DROPS IN THE DIRECTION OF FLOW

R OR R — DUCT RISES IN THE DIRECTION OF FLOW

OR — TURNING VANES

CFM OR CFM — 8" THROAT DIAMETER CEILING DIFFUSER; AIR FLOW -- 100 CFM

OR — BALANCING OR VOLUME DAMPER

M OR M — MOTOR OPERATED DAMPER

FLEXIBLE DUCT

FIRE DAMPER

A — SOUND ATTENUATOR

ZONE DAMPER

FLEXIBLE CONNECTION AT FAN OR EQUIPMENT

EXTRACTOR

OR — SPLITTER DAMPER

B — PLUG VALVE WITH MEMORY STOP (BALANCING)

PLUG VALVE

S — SOLENOID VALVE

TEMPERATURE CONTROL VALVE

THREE-WAY TEMPERATURE CONTROL VALVE DIAPHRAGM

THREE-WAY TEMPERATURE CONTROL VALVE TOP VIEW

PRESSURE REDUCING VALVE (NOS = INITIAL AND FINAL PRESSURE - PSIG)

PRV — AIR PRESSURE REDUCING STATION (NO. CORRESPONDS WITH AIR PRESSURE REDUCER SCHEDULE)

SAFETY VALVE (NOS. = PRESSURE SETTING - PSIG)

FLOAT OPERATED VALVE

QC — QUICK COUPLING (QC)

UH — HORIZONTAL UNIT HEATER (NO. CORRESPONDS WITH UNIT HEATER SCHEDULE)

UH — VERTICAL UNIT HEATER (NO. CORRESPONDS WITH UNIT HEATER SCHEDULE)

UH — CABINET TYPE UNIT HEATER (NO. CORRESPONDS WITH UNIT HEATER SCHEDULE)

T — THERMOSTAT OR ROOM TEMPERATURE SENSOR

GATE VALVE

FLOW SWITCH

GPM — VENTURI FLOW METER AND FLOW TO BE INDICATED

CONNECTION BETWEEN NEW AND EXISTING

GLOBE VALVE

BUTTERFLY VALVE

CHECK VALVE

ANGLE GATE VALVE

CONCENTRIC REDUCER

ECCENTRIC REDUCER

ORIFICE FLANGE

CROSSOVER

PIPE GUIDE

EXPANSION JOINT (SLIP TYPE)

EXPANSION JOINT (BELLOWS TYPE)

AIR ELIMINATOR (AIR VENT)

PIPE CAP

STRAIGHT CROSS

90° ELBOW

90° ELBOW TURNED DOWN

90° ELBOW TURNED UP

SIDE OUTLET ELBOW TURNED DOWN

SIDE OUTLET ELBOW TURNED UP

LATERAL

TEE

TEE OUTLET UP

TEE OUTLET DOWN

UNION

STRAINER

X — PIPE ANCHOR

THERMOMETER (NOS. = RANGE IN DEGREES FAHRENHEIT)

PRESSURE, VACUUM OR COMPOUND GAUGE

Paul Kovacs
APPROVED . . . . . DATE 7-1-2009
CHIEF ENGINEER

NOTE:

ALL SYMBOLS AND PATTERNS ON THIS DRAWING ARE PROPOSED UNLESS OTHERWISE NOTED.

Illinois Tollway

SYMBOLS AND PATTERNS

STANDARD D2-04



RIGHT OF WAY MARKER



RIGHT OF WAY MARKER (SPECIAL)



TYPICAL CENTERLINE MONUMENT AT MEDIAN BARRIER



ACCESS COVER (RECESSED HINGE)



ALUMINUM DOMED CAP

TOP VIEW



LETTERING DETAIL



* METHOD A- 4'-2'' LONG BARS
* METHOD B- 2'-6'' LONG BARS

SECTION B-B



BRONZE DOMED CAP



PERMANENT SURVEY MONUMENT (SPECIAL)



MONUMENT POST

RIGHT OF WAY MARKER

PERMANENT SURVEY MONUMENT

Paul Kovacs
APPROVED ..... CHIEF ENGINEER
DATE 1-1-2007

DATE	REVISIONS
07-01-10	NEW MONUMENT AND BARRIER MARKERS

Illinois Tollway

PERMANENT SURVEY MONUMENTS AND RIGHT-OF-WAY MARKERS

STANDARD D3-01

PERMANENT DELINEATION SPACING					
		MAINLINE		RAMP	
	REFLECTORS	TANGENT	CURVE	TANGENT	CURVE
*	GUARDRAIL	100′	100′	100′	TABLE A
*	BARRIER WALL (DOUBLE FACE)	100′	100′	100′	TABLE A
*	BARRIER WALL (SINGLE FACE)	100′	100′	100′	TABLE A
	SHOULDER NARROWING	3 @ 15′	3 @ 15′	3 @ 15′	3 @ 15′
	BRIDGE APPROACHES	3 @ 15′	3 @ 15′	3 @ 15′	3 @ 15′
*	BRIDGE PARAPET	50′	50′	50′	50′
*	NOISE ABATEMENT WALL (CRASH WORTHY)	100′	100′	100′	TABLE A

	ROADWAY DELINEATORS	MAINLINE		RAMP	
		TANGENT	CURVE	TANGENT	CURVE
	POST MOUNTED DELINEATOR	200′	200′	200′	TABLE A
	POST MOUNTED DELINEATOR (RAMP TAPERS AND TANGENTS)	100′	100′	NA	NA

	TEMPORARY DELINEATION SPACING				
		TANGENT	REVERSE CURVE	SHIFT	TAPER
	TEMPORARY CONCRETE BARRIER	50′	25′	25′	25′

* WHEN ADJACENT SHOULDER IS USED AS A TRAVELED LANE, USE SPACING REQUIREMENTS AS SHOWN FOR TEMPORARY DELINEATION.

TABLE A	
REFLECTOR SPACING ON RAMP-CURVES	
RADIUS OF CURVE (FT.)	SPACING ALONG CURVE (FT.)
LESS THAN 1050	50
1050-1299	100
1300-1999	125
2000-2999	150
3000-3999	175
MORE THAN 3999	200

Paul Kovacs
APPROVED ..... DATE 7-1-2009
CHIEF ENGINEER

GENERAL NOTES:

EMERGENCY TURNAROUNDS DELINEATION-THE FOLLOWING DELINEATION SHOULD BE INSTALLED ON THE LEFT SIDE OF THE PAVEMENT APPROACHING EMERGENCY TURNAROUNDS.

A. ONE-HALF OF A MILE IN ADVANCE OF THE EMERGENCY TURNAROUNDS ONE WHITE REFECTOR UNIT OVER THREE AMBER REFLECTOR UNITS.

B. ONE-FOURTH OF A MILE IN ADVANCE OF THE EMERGENCY TURNAROUNDS ONE WHITE REFLECTOR UNIT OVER TWO AMBER REFLECTOR UNITS.

C. AT A POINT NEAR THE INTERSECTION OF THE EDGE OF THE LEFT SHOULDER AND NEAR EDGE OF THE EMERGENCY TURNAROUNDS ONE WHITE REFLECTOR UNIT OVER ONE AMBER REFLECTOR UNIT.

NOTES FOR ROADWAY DELINEATORS, POST MOUNTED INSTALLATION:

1. A. MAINLINE-SINGLE WHITE REFECTOR UNITS SHALL BE PLACED CONTINUOUSLY ON THE RIGHT AND SINGLE AMBER REFLECTOR UNITS SHALL BE PLACED ON THE LEFT ON MAIN LINE SECTIONS WITHOUT BARRIER WALL.

   B. RAMPS-SINGLE REFLECTOR UNITS SHALL BE PLACED ON THE OUTSIDE OF ALL CURVED SECTIONS OF RAMPS, SINGLE WHITE SHALL BE PLACED ON THE RIGHT SIDE AND AMBER ON THE LEFT SIDE. THE DELINEATORS SHALL BE OVERLAPPED FOR A SHORT DISTANCE TO CLEARLY INDICATE WHERE DELINEATION ON ONE SIDE OF THE RAMP ENDS AND DELINEATION ON THE OTHER SIDE APPEARS.

   C. DOUBLE WHITE REFLECTOR UNITS SHALL BE PLACED ON THE RIGHT AT ALL ACCELERATION AND DECELERATION LANES.

2. REFLECTORS SHALL BE MOUNTED ON SUPPORTS SUCH THAT THE TOP OF REFLECTORS IS FOUR FEET ABOVE THE ROADWAY EDGE AND TWO FEET OUTSIDE THE OUTER EDGE OF THE PAVED SHOULDER OR TWO FEET MINIMUM AND SIX FEET MAXIMUM OUTSIDE THE BACKS OF CURBS OR GUTTERS.

3. IN ALL CASES, THE COLOR OF THE REFLECTORS SHALL BE THE SAME AS THE ADJACENT EDGE LINE EXCEPT AS SPECIFIED IN GENERAL NOTES.

4. POST MOUNTED REFLECTORS SHALL BE PLACED CONTINUOUSLY AS NOTED ABOVE IN CONJUNCTION WITH GUARDRAIL INSTALLED.

5. THE PLACEMENT OF ROADWAY DELINEATOR "CIRCULAR REFLECTORS" SHALL BE USED FOR ALL MINOR PROJECTS WHICH HAVE A LENGTH OF LESS THAN 5 MILES. THE PLACEMENT OF ROADWAY DELINEATOR "RECTANGULAR REFLECTORS" SHALL BE USED FOR ALL MAJOR PROJECTS WHICH HAVE A LENGTH GREATER THAN 5 MILES. ALL ROADWAY DELINEATORS WITHIN A ROADWAY SEGMENT SHALL BE OF THE SAME TYPE.

NOTES FOR GUARDRAIL AND BARRIER WALL REFLECTOR:

1. REFLECTORS TYPE B AND TYPE C SHALL HAVE REFLECTIVE SURFACE ON ONE SIDE ONLY.

DATE	REVISIONS
07-01-09	CHANGED BARRIER TO F-SHAPE CONFIG.
	ADDED SECTION C-C NEW BARRIER DELINEATORS
02-07-12	REVISED REFLECTOR MARKER TYPE C DIMENSION
11-01-12	REVISED NOTES, TABLE AND DELINEATION
	SPACING
3-11-2015	REVISED NOTES
3-31-2016	REVISED DELINEATOR ATTACHMENT TO POST

Illinois Tollway

ROADWAY DELINEATORS AND REFLECTORS

STANDARD D4-05



TANGENT PLACEMENT



ROADWAY DELINEATOR INSTALLATION



INTERCHANGE RAMP PLACEMENT



SECTION A-A

STEEL- 1.12 LBS/FT.



STEEL POST



SINGLE UNIT



DOUBLE UNIT

CIRCULAR REFLECTORS



SINGLE UNIT



DOUBLE UNIT

RECTANGULAR REFLECTORS

NOTE:

SEE SHEET 1 OF THIS SERIES FOR NOTES.

Paul Kovacs
APPROVED ..... DATE 7-1-2009
CHIEF ENGINEER

Illinois Tollway

ROADWAY DELINEATORS
AND REFLECTORS

STANDARD D4-05



CROSS-SECTION

TEMPORARY CONCRETE BARRIER



PLAN



SECTION A-A

REFLECTOR INSTALLATION ON GUARDRAIL AT BRIDGE APPROACHES

ALSO SEE SHEET 1 IN THIS SERIES FOR ADDITIONAL INFORMATION



BARRIER OR PARAPET REFLECTOR INSTALLATION



REFLECTOR, TYPE C



SECTION B-B



REFLECTOR, TYPE B



SECTION C-C

NOTE:

SEE SHEET 1 OF THIS SERIES FOR NOTES.

Paul Kovacs
APPROVED ..... CHIEF ENGINEER
DATE 7-1-2009

Illinois Tollway

ROADWAY DELINEATORS AND REFLECTORS

STANDARD D4-05



PLAN



SECTION A-A

ROADWAY AND SHOULDER STRIPING - NEW CONSTRUCTION

GENERAL NOTES:

1. DIAGONAL SHOULDER STRIPING REQUIRED WHERE THE SHOULDER WIDTH IS LESS THAN STANDARD.
2. ROADWAY MARKING MATERIALS TO BE USED ON FINISHED CONCRETE SURFACE AND ASPHALT SURFACE SHALL BE AS SHOWN ON THE PLANS.
3. WHERE THE GUARDRAIL ENCROACHES ON THE SHOULDER THE DIAGONAL MARKINGS SHALL EXTEND AS CLOSE TO THE FACE OF THE RAIL AS POSSIBLE.
4. ALL PERMANENT LANE LINES AND EDGE LINES SHALL BE GROOVED, ON ROADWAY SURFACES, UNLESS OTHERWISE NOTED.
5. DIAGONAL STRIPING SHALL BE SURFACE APPLIED.
6. GORE STRIPING (CHEVRON) SHALL BE SURFACE APPLIED.
7. ALL LANE LINES AND EDGE LINES SHALL BE SURFACE APPLIED ON BRIDGES.
8. PAVEMENT MARKINGS SHALL NOT BE GROOVED AT THE CASH SIDE OF MAINLINE TOLL PLAZAS OR THE OPEN ROAD TOLLING (ORT), 100′ CONTINUOUSLY REINFORCED CONCRETE (CRC) PAVEMENT SECTION OF MAINLINE UNDER MONOTUBES.

Paul Kovacs
APPROVED ..... DATE 7-1-2009
CHIEF ENGINEER

DATE	REVISIONS
7-01-09	ADDED LINE GROOVING NOTES
2-07-12	REVISED NOTES
11-01-12	REVISED EDGELINE OFFSET, REVISED NOTES
3-31-14	REVISED NOTES
3-31-16	REVISED NOTES

Illinois Tollway

PERMANENT PAVEMENT MARKINGS

STANDARD D5-06



EXIT - SINGLE LANE RAMP
LANE THREE TERMINATION

*OMIT R.P.M.



EXIT - SINGLE LANE LOOP RAMP - PARALLEL TYPE



EXIT - SINGLE LANE RAMP - LANE DROP



EXIT - TWO LANE PARALLEL RAMP



EXIT - SINGLE LANE RAMP - TAPER TYPE

*OMIT R.P.M.



EXIT - TWO LANE RAMP



ARROW & ONLY
DETAILS

NOTE:

PAVEMENT MARKING LETTERS AND SYMBOLS-ONLY AND ARROW ARE TO BE TYPICALLY PLACED AT 1/2 MILE EXIT ONLY GUIDE SIGN, AT GORE EXIT GUIDE SIGN AND APPROXIMATELY HALFWAY BETWEEN THE TWO.

GENERAL NOTES:

1. RUMBLE STRIPS SHALL BE INSTALLED BETWEEN THE THEORETICAL GORE AND TAPER WHEN LENGTHS OF AUXILIARY LANES, ACCELERATION LANES OR DECELERATION LANES, ARE GREATER THAN 1000'.
2. ROADWAY MARKING MATERIALS TO BE USED ON FINISHED CONCRETE SURFACE AND ASPHALT SURFACE SHALL BE AS SHOWN ON THE PLANS.
3. ALL LANE LINES AND EDGE LINES SHALL BE GROOVED.
4. GORE STRIPING (CHEVRON) SHALL BE SURFACE APPLIED.
5. LETTERS AND SYMBOL MARKING SHALL BE SURFACE APPLIED.
6. DOTTED LINES SHALL CONSIST OF 3' LINE AND 9' GAPS.

Paul Kovacs
APPROVED ..... DATE 7-1-2009
CHIEF ENGINEER

DATE	REVISIONS
07-01-09	ADDED LINE GROOVING NOTES
11-01-12	REVISED NOTES AND ADDED DOTTED LINE
03-01-13	REVISED SINGLE LANE LOOP RAMP DETAILS
03-31-14	ADDED LANE REDUCTION MARKINGS
3-11-2015	REVISED DETAILS, ADDED LANE-REDUCTION ARROWS AND SHEET 3
3-31-2016	REVISED NOTES, ADDED IPO PAVEMENT MARKING DETAIL.

Illinois Tollway

PAVEMENT MARKING
AND SHOULDER
RUMBLE STRIP DETAILS

STANDARD D6-06



ENTRANCE - SINGLE LANE RAMP - PARALLEL TYPE



ENTRANCE - SINGLE LANE RAMP - TAPER TYPE



LANE-REDUCTION ARROW

RIGHT LANE-REDUCTION ARROW SHOWN.
USE MIRROR IMAGE FOR LEFT LANE.

* WHEN LENGTH (L) IS GREATER THAN 1000'-0'' PLACE ARROWS AS SHOWN



ENTRANCE - TWO LANE RAMP



ENTRANCE - SINGLE LANE RAMP
WITH ADDED MAINLINE LANE



ENTRANCE - TWO LANE RAMP
WITH ADDED MAINLINE LANE



ENTRANCE - TWO LANE PARALLEL RAMP

Paul Kovacs
APPROVED ..... DATE 7-1-2009
CHIEF ENGINEER

SEE SHEET 1 IN THIS SERIES FOR GENERAL NOTES.

Illinois Tollway

PAVEMENT MARKING AND SHOULDER RUMBLE STRIP DETAILS

STANDARD D6-06



RAMP-1 LANE



RAMP-2 LANES



LOOP RAMP



TYPICAL PLAN VIEW
MAINLINE



SECTION A-A SECTION B-B PLAN DETAIL A

ASPHALT SHOULDER
RUMBLE STRIP DETAILS



SECTION A-A SECTION B-B PLAN DETAIL A

CONCRETE SHOULDER
RUMBLE STRIP DETAILS



IPO LANE PAVEMENT MARKING

SEE SHEET 1 IN THIS SERIES FOR GENERAL NOTES.

Illinois Tollway

PAVEMENT MARKING
AND SHOULDER
RUMBLE STRIP DETAILS

STANDARD D6-06

Paul Kovacs
APPROVED ..... DATE 7-1-2009
CHIEF ENGINEER



DECIDUOUS TREE PLANTING DETAIL
(4 1/2'' CALIPER AND LARGER)



DECIDUOUS TREE PLANTING DETAIL
GREATER THAN 4 FT HEIGHT AND LESS THAN 4 1/2'' CALIPER)

PLANTING NOTES:

1. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UNDERGROUND UTILITIES, FIBER OPTICS, STORM SEWERS AND DRAINAGE STRUCTURES IN THE FIELD PRIOR TO THE EXCAVATION OF ANY PLANT PITS OR PLANTING BEDS. LOCATIONS OF TREE AND SHRUB PLANTINGS SHALL BE ADJUSTED TO AVOID DAMAGING ANY UNDERGROUND FEATURES.

2. THE PLANT LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATELY ONLY. THE EXACT LOCATIONS SHALL BE ADJUSTED AS REQUIRED IN THE FIELD BY THE ENGINEER. TREE LOCATIONS SHALL NOT BE MOVED CLOSER TO PAVEMENT EDGES THAN SHOWN ON THE PLANS OR A MINIMUM OF FIFTY (50) FEET.

3. TREES SHALL BE SPACED A MINIMUM OF SIX (6) FEET FROM FENCES.

4. TREE AND SHRUB PLANTINGS SHALL NOT BLOCK ACCESS TO GATES IN FENCES.

5. TREES PLANTED IN TURF AREAS SHALL BE SPACED A MINIMUM OF TEN (10) FEET FROM THE EDGE OF A SHRUB BED.

6. TREES SHALL BE SPACED A MINIMUM OF TEN (10) FEET FROM NOISEWALLS OR OTHER STRUCTURES.

7. DITCHES SHALL BE KEPT CLEAR OF TREE AND SHRUB PLANTINGS. THE MINIMUM VERTICAL DISTANCE BETWEEN DITCH BOTTOMS AND PLANTS SHALL BE THREE (3) FEET.

8. IF DURING EXCAVATION, A PLANT HOLE OR PLANTING BED SHOWS POOR DRAINAGE, STANDING WATER OR AN IMPERVIOUS STRATUM OF SOIL, THE CONTRACTOR SHALL CEASE EXCAVATION AND SHALL NOTIFY THE ENGINEER. THE PLANT(S) SHALL BE RELOCATED AS DIRECTED BY THE ENGINEER AND THE HOLE(S) OR BED SHALL BE FILLED IN AND RESTORED TO MATCH THE CONDITION AND VEGETATION OF THE ADJACENT AREA.

9. IMPROPERLY PRUNED PLANTINGS WILL BE REJECTED AND REPLACEMENTS WILL IMMEDIATELY BE MADE BY THE CONTRACTOR.

10. THE SIDES OF ALL PLANT PITS SHALL BE LOOSENED TO DISJOIN ANY GLAZING WHICH MAY OCCUR DURING THE DIGGING OPERATION.

11. TREE WRAPPING SHALL EXTEND TO THE LOWEST MAJOR BRANCH.

12. TOP OF ROOTBALL SHALL BE APPROXIMATELY 2 INCHES ABOVE ADJACENT FINISHED GRADE.

13. SHRUB PLANTINGS:

    A. UNLESS NOTED OTHERWISE, ALL SHRUBS SHALL BE PLANTED IN MULCHED BEDS. THE EDGE OF THE MULCH BED SHALL EXTEND A MINIMUM OF THREE (3) FEET BEYOND THE CENTERS OF THE PERIPHERAL PLANTS IN THE BED.

    B. THE EDGE OF A MULCH BED FOR SHRUB PLANTINGS ADJACENT TO A WALL, FENCE, GUARDRAIL OR OTHER FIXED OBJECT SHALL EXTEND TO THE OBJECT. THE PERIPHERAL PLANTS IN THE BED SHALL NOT BE PLANTED WITHIN FIVE (5) FEET OF THE OBJECT.

    C. WHEN A TREE IS LOCATED IN A SHRUB BED, THE MINIMUM DISTANCE BETWEEN THE TREE AND THE ADJACENT SHRUBS SHALL BE SIX (6) FEET.

14. THE CONTRACTOR SHALL RESTORE ALL AREAS, OBJECTS AND VEGETATION DISTURBED BY THE LANDSCAPE OPERATIONS TO ORIGINAL CONDITIONS.

15. STAKES, GUYWIRES AND ALL TREE SUPPORTS SHALL BE REMOVED AFTER ONE YEAR OR AS DIRECTED BY THE ENGINEER.

16. REMOVE ALL TWINE, ROPE, WIRE AND BURLAP FROM TOP HALF OF ROOTBALL. THE LOWER HALF OF BURLAP SHALL BE FOLDED TOWARD THE BOTTOM OF THE ROOTBALL.



EVERGREEN TREE PLANTING DETAIL



STEEP SLOPE PLANTING DETAIL



SHRUB PLANTING DETAIL

Paul Kovacs
APPROVED ..... DATE 2-7-2012
CHIEF ENGINEER

DATE	REVISIONS
02-07-12	REVISED POST BRACING DETAIL
03-31-16	REVISED MULCH LAYER THICKNESS
	AND PLANTING NOTES

Illinois Tollway

LANDSCAPE PLANTING DETAILS

STANDARD D7-02



DETAIL A



DETAIL B



✳ MARKER TO BE INSTALLED WHEN LENGTHS OF AUXILIARY LANES ARE GREATER THAN 1000'.

DETAIL C



MAINLINE

RAISED PAVEMENT LANE MARKER DETAILS

NOTES:

1. FOR COLLECTOR-DISTRIBUTOR (C-D) ROADWAYS, PLACE ONE-WAY CRYSTAL MARKER, 2 EACH AT 100' CENTERS. USE DETAIL A.
2. FOR MULTI LANE DIRECTIONAL RAMPS, PLACE ONE-WAY CRYSTAL MARKER, 1 EACH AT 50' CENTERS. USE DETAIL B.
3. FOR AUXILIARY LANES, PLACE ONE-WAY CRYSTAL MARKER, 1 EACH AT 48' CENTERS. USE DETAIL C.

Paul Kovacs
APPROVED ..... CHIEF ENGINEER
DATE 7-1-2009

Illinois Tollway

DATE	REVISIONS
11-01-2012	REVISED DETAIL C.
3-31-2016	REVISED NOTES 1.

RAISED PAVEMENT LANE MARKER

STANDARD D8-02